STANDARD FORM 2 FEBRUARY 1965 EDITION GENERAL SERVICES ADMINISTRATION

US GOVERNMENT LEASE FOR REAL PROPERTY

mary 3, 2011

LEASE NO. GS-02B-23815 / BUILDING NO. NY7520

THIS LEASE, made and entered into this date by and between THE UNILAND PARTNERSHIP OF DELAWARE, LP

whose address is: 100 Corporate Parkway, Suite 500, Amherst, NY 14226-1200

and whose interest in the property hereinafter described is that of Owner hereinafter called the Lessor, and the UNITED STATES **OF AMERICA**, hereinafter called the Government:

WITNESSETH: The parties hereto for the considerations hereinafter mentioned, covenant and agree as follows:

The Lessor hereby leases to the Government the following described premises:

Twenty-three thousand eight hundred seventy-seven (23,877) rentable square feet (RSF) yielding twenty-one thousand six hundred fifty-nine (21,659) ANSI/BOMA Office Area square feet, of office and related space on the third (3rd) floor of the building known and designated as 300 Airborne Parkway, Cheektowaga, New York 14225 ("Building"), as shown on the floor plan labeled "Attachment A" attached hereto and made a part hereof; together with the right by the Government to use sixteen (16) secure, reserved surface parking spaces located at the Building, as shown on the plan labeled "Attachment B" attached hereto and made a part hereof (together known as the "Premises").

TO HAVE AND TO HOLD the said Premises with their appurtenances for the term beginning on:

SEE ATTACHED RIDER PARAGRAPH 8

The Government shall pay the Lessor annual rent of:

SEE ATTACHED RIDER PARAGRAPH 11

The Government may terminate this lease in whole or in part at any time:

SEE ATTACHED RIDER PARAGRAPH 9

This lease may be renewed at the option of the Government, for the following terms and at the following rentals:

IN WITNESS WHEREOF, the parties hereto have hereunto subscribed their names as of the date first above written. LESSOR The Uniland Partnership of Delaware, LP (Signature) IN PRESENCE OF UNITED STATES OF AMERICA Contracting Officer, General Services Administration (Signature)

RIDER TO LEASE No: GS-02B-23815

- 6. The following are attached and made a part hereof:
 - a) Rider To Lease, containing Paragraphs 6 through 25;
 - b) Section 1.0, Summary, paragraphs 1.1 through 1.13;
 - c) Section 2.0, Award Factors and Price Evaluation, paragraphs 2.1 through 2.6;
 - d) Section 3.0, How to Offer and Submittal Requirements, paragraphs 3.1 through 3.7;
 - e) Section 4.0, Utilities, Services and Lease Administration, paragraph 4.1 through 4.13;
 - f) Section 5.0, Design, Construction and Other Post Award Activities, paragraph 5.1 through 5.19;
 - g) Section 6.0, General Architecture, paragraphs 6.1 through 6.13;
 - h) Section 7.0, Architectural Finishes, paragraphs 7.1 through 7.16;
 - i) Section 8.0, Mechanical, Electrical, Plumbing, paragraphs 8.1 through 8.20;
 - j) Section 9.0, Fire Protection, Life Safety and Environmental Issues, paragraphs 9.1 through 9.12;
 - k) Section 10.0, Lease Security Standards, paragraphs 10.1 to 10.27;
 - l) Section 11.0, Special Requirements, paragraph 11.1;
 - m) Exhibit "A," Special Requirements for Buffalo Field Office Buffalo, NY, pages 1-24;
 - n) Exhibit "B," U.S. Customs and Border Protection Voice / Data Communications Room Requirements, pages 1-13;
 - o) Exhibit "C," HSDN Room Requirements, pages 1-11:
 - p) General Clauses, GSA Form 3517B, paragraphs 1 through 48;
 - q) Representations and Certifications, GSA Form 3518, paragraphs 1 through 11;
 - r) Attachment "A," third (3rd) floor plan depicting the demised premises:
 - s) Attachment "B," diagram depicting the parking area;
 - t) Attachment "C," Small Business Subcontracting Plan, pages 1-11.
- 7. The Lessor shall construct the Premises so as to deliver the space in accordance with all of the requirements of this Lease ready for occupancy by the Government, no later than one hundred twenty (120) working days after receiving the Tenant Improvement Notice to Proceed from the Government, as set forth in paragraph 5.11(F) of the SFO to this lease.
- 8. The term of this Lease shall commence upon Substantial Completion of all alterations specified in this Lease and shall run for a period of ten (10) years thereafter, subject to the termination right set forth below. The Commencement Date of the Lease shall be more particularly set forth in a Supplemental Lease Agreement (SLA) to this lease.
- 9. The Government shall have the right to terminate this Lease in whole or in part following the fifth (5th) anniversary of the lease by giving at least one hundred twenty (120) days prior notice in writing to the Lessor and no rental shall accrue after the effective date of termination. Should the Government exercise this right or not extend the Lease beyond the ten (10) year lease term, it shall not be required to pay the Lessor any unamortized balance of the Tenant Improvement Allowance (referenced below) outstanding on the effective date of such termination, or the conclusion of the ten (10) year lease term, respectively.
- - a) Amortize the additional tenant improvement cost into the rent in the same manner as set forth above, provided however, that the rent shall not be increased by more than the amount necessary to amortize an additional (b) (4) (4) (5)
 - b) Pay the Lessor the difference between (b) (4) and the total TI cost in a one-time lump sum payment upon Substantial Completion of the TI, acceptance thereof by the Government and submission of a proper invoice by the Lessor, or;
 - c) Reduce the Tenant Improvement Requirements.

In the event the TI cost is less than (b) (4) only the actual TI cost shall be amortized into the annual rent in the same manner as set forth above and the rental rate set forth in Paragraph No. 11 below shall be reduced accordingly. Such additional payment or rental reduction, if applicable, will be memorialized in a Supplemental Lease Agreement.

MILESSER GOVERNMENT

11. The Government shall pay the Lessor annual rental, as part of a fully-serviced lease, as follows:

For years 1 through 5 of the lease term, a total annual rental of \$545,111.91 per annum at the rate of \$45,425.99 per month in arrears, provided, there shall be no rent payable for the first two months of the lease term;

For years 6 through 7 of the lease term, a total annual rental of \$572,331.69 per annum at the rate of \$47,694.31 per month in arrears and;

For years 8 through 10 of the lease term, a total annual rental of \$645,872.85 per annum at the rate of \$53,822.74 per month in arrears; which annual rentals include \$109,235.90 per annum for the amortization of the Lessor's contribution to the TI cost (amortized over a 13-year term) plus annual operating cost escalations referenced in Paragraph 14 below. The annual rentals shall be subject to adjustment as set forth in paragraph 10 of this Rider above and paragraphs 4.3 and 4.4 of the SFO herein. Rent for a lesser period shall be prorated.

The annual rental includes the cost for sixteen (16) secured, reserved parking spaces. The Lessor shall secure the sixteen (16) reserved parking spaces in accordance with requirements set forth in Paragraph 10.17 of the SFO and Lease Exhibits.

| 12. | The Lessor and the Broker have agreed (b) (4) (b) (4) |
|-----|---|
| | |
| | |
| | |
| | |
| | |
| | Third month's rental payment of (b) (4) of which \$ (b) (4) is shell rent, minus Commission Credit of (b) (4) equals (b) (4) adjusted third month's rent; |
| | Fourth month's rental payment of (b) (4) of which (b) (4) shell rent, minus Commission Credit of (b) (4) equals (b) (4) adjusted fourth month's rent. |

- 13. For the purposes of the Real Estate Tax Adjustment clause pursuant to SFO Section 4.2 of the Lease, the Government is deemed to occupy 21.37% of the rentable area of the Building.
- 14. For the purposes of the Operating Cost Escalation pursuant to SFO Section 4.3 Operating Costs of the Lease, the base rate shall be (b) (4) per annum.
- 15. Pursuant to SFO Section 4.6, Overtime Usage, the overtime rate for heating and air conditioning (HVAC) shall be per hour.
- 16. The common area factor is established as 1.1024 (23,877 RSF / 21,659 USF).
- 17. In accordance with the SFO paragraph 4.4 entitled *Adjustment for Vacant Premises*, the adjustment is established as per USF for vacant space.
- 18. The Lease shall not be binding on either party until it has been executed by a duly authorized official of the U.S. General Services Administration and Lessor.
- 19. Wherever the words "Offeror" or "Successful Offeror" appear in the lease they shall be deemed to mean "Lessor". Wherever the words "Solicitation", "Solicitation for Offers" or "SFO" appear in this lease they shall be deemed to mean "this Lease"; wherever the words "space offered for lease" appear in this lease they shall be deemed to mean the "leased premises", "premises" or "Premises" and where the word "Lessee" is used herein it shall be deemed to mean Government.
- 20. Each employee of the Lessor and/or its contractor(s) employed in the operation of the Leased Premises shall be (1) citizen of the United

MINITALS & SUU GOVERNMENT

States of America; (2) an alien who has been lawfully admitted for permanent residency as evidenced by Alien Registration Receipt Card Form I-151; or (3) an alien who presents other information from the Immigration and Naturalization Services that employment will not effect his/her immigration status.

- 21. If during the term of the Lease, including extension, the title to this property is transferred to another person by either sale, foreclosures, condemnation or other transaction, the Lessor (transferor) shall promptly notify the Contracting Officer of said transfer. The following information shall accompany this notification:
 - a) A certified copy of the deed transferring title of the property from the Lessor to the new owner.
 - b) A letter from the new owner assuming, approving and agreeing to be bound by the terms of this lease.
 - c) A letter from the Lessor waiving all rights under this Lease against the Government up to the effective date of the transfer, provided the Government is current on rent and all other obligations under the Lease. The Lessor acknowledges that the Government pays rent one (1) month in arrears.
 - d) The new owner's taxpayer identification number or Social Security number.
 - e) The new owner's full legal name. If a corporation, indicate the state of incorporation. If a partnership, list all partners fully. If a limited partnership, list the names of all general partners and identify which state the limited partnership was created in. If a realty trust, give the names of all trustees and the recording date of the trust.

The foregoing information must be received by the fifteenth day of the month in which the transfer of title will be effected. The rent for that month, adjusted in accordance with the effective date of the transfer will be processed to the Lessor. Initial rental payment to the new owner will be processed on the first day of the second month following the transfer of title. If the notification of transfer and related information is not received until the sixteenth day of the month (or later), in which the transfer of title will be effected, the full contract rental for that month will be forwarded to the Lessor. In this instance, it will be the responsibility of both the Lessor and the new owner to submit, in conjunction with other requested information, a letter of agreement regarding disposition of the monthly rent with respect to the effective date of transfer. In any instance, failure to submit the documentation required for transfer of title will result in a stop payment of rent until such time as all documentation is received by the Contracting Officer

- 22. The Lessor shall not be reimbursed for any service not provided for in the Lease including, but not limited to repairs and alterations, nor will any rental be paid for occupancy in whole or in part except for the lease term specified in this Lease, unless approved in advance by a Contracting Officer of the US General Services Administration.
- 23. The Lessor shall not enter into negotiations concerning the space leased or to be leased with representatives of Federal agencies other than officers and employees of the U. S. General Services Administration or personnel authorized by the Contracting Officer.
- 24. All plans submitted for consideration shall have been generated by a Computer Aided Design (CAD) program which is compatible with the latest release of AutoCAD. The required file extension is .DWG. Clean and purged files shall be submitted on CD-ROM. All submissions shall be accompanied with a written matrix indicating the layering standard to ensure that all information is recoverable. Plans shall include a proposed corridor pattern for typical floors and/or partial floors. All architectural features of the space shall be accurately shown.
- 25. Prior to occupancy and at no additional cost to the Government, the Lessor shall use best efforts to renovate the space for any energy efficiency and conservation improvements that would be cost effective over the firm term of the lease, thereby reducing electricity or fossil fuel consumption, water, or other utility costs. Additional information on such improvements can be found on www.gsa.gov/leasing under "Green Leasing." However, in the event the Lessor obtains the Energy Star label prior to the Government's occupancy, the Lessor shall not be required to renovate the space for these improvements. To earn the ENERGY STAR label, the Lessor must follow the instructions on the Energy Star Web site at http://www.energystar.gov/eslabel."

MINTALE & SW LESSOR & GOVERNMENT

TABLE OF CONTENTS

| 1. 0 | SUMMARY | 4 |
|--------------------------|--|------------|
| 1.1 | AMOUNT AND THE OF SPACE (AUG 2008) | |
| 1.2 | ONIQUE REQUIREMENTS (AUG 2008) | |
| 1.3 | ELYOL TENN (OLF 2000) | 4 |
| 1.4 | OTT EN DOL DATE (AUG 2006) | |
| 1.5 | ACCECC AND AFFORTENANT AREAS IAUG ZUDAT | |
| 1.6 | OCIVIOLO, OTILITICO, MAINTENANCE: GENERAL (ALIG 2008) | 4 |
| 1.7 | ANEA OF CONSIDERATION FACE ZUGAT | |
| 1.8 | EGOVITOR: OCTOBE OF LOCATER MICH MICH MICH | |
| 1.9 | | |
| 1.10 | 11200 FIX 11 TO 140 (11/1/1 2000) | |
| 1.11 | | |
| 1.12 | DOJEDNA OLITER IVERONICIMENTO (ADICIVINA) | |
| 1.13 | LABOR STANDARDS (AUG 2003) | 6 |
| 2. 0 | AWARD FACTORS AND PRICE EVALUATION | |
| 2.1 | AWARD BASED ON PRICE (SEP 2000) | 7 |
| 2.2 | SEISMIC SAFETY (FEB 2007) | 7 |
| 2.3 | | |
| 2.4 | BROKER COMMISSION AND COMMISSION CREDIT (NOV 2006) | 7 |
| 2.5 | PRICE EVALUATION (PRESENT VALUE) (AUG 2008) | 7 |
| 2.6 | AWARD (AUG 2008) | 7 |
| | | 7 |
| 3. 0 | HOW TO OFFER AND SUBMITTAL REQUIREMENTS | _ |
| 3.1 | OFFER PROCEDURES (AUG 2008) | 8 |
| 3.2 | TENNIN INICIO VENIENTO INCLUIDED IN DEFERTADE VANO. | _ |
| 3.3 | TENTAL INTRODUCENT INCIDENTAL ADJUSTIMENT (ALICA 2008) | • |
| 3.4 | GSA FORMS AND PRICING INFORMATION (AUG 2008) | 8 |
| 3.5 | | |
| 3.6 | | |
| 3.7 | GREEN LEASE SUBMITTALS | 9 Q |
| | | 3 |
| 4. 0 | UTILITIES, SERVICES, AND LEASE ADMINISTRATION | |
| 4.1 | MEASUREMENT OF SPACE (AUG 2008) | 10 |
| 4.2 | TAX ADJUSTMENT (AUG 2008) | 10 |
| 4.3 | | |
| 4.4 | ADJUSTMENT FOR VACANT PREMISES, GSAR 552.270-16 (VARIATION) (DEC 2005) | 12 |
| 4.5 | | |
| 4.6 | | |
| 4.7 | | |
| 4.8 | | |
| 4.9 | | |
| 4.10 | | |
| 4.11 | | |
| 4.12 | | |
| 4.13 | CENTRAL CONTRACTOR REGISTRATION (AUG 2008) | . 14 15 |
| | | |
| 5. 0 | DESIGN, CONSTRUCTION, AND OTHER POST AWARD ACTIVITIES | 16 |
| 5.1 | ON ECONIDING AND DISSEMBATION OF SENSITIVE BITLING ASSIFIED (SBIT) BITLING INFORMATION (TIME 2000) | 40 |
| 5.2 | TENSINE INFROVEMENTS PRICING REQUIREMENTS (AUG 2008) | 47 |
| 5.3 | ODDEGOENT TENANT ALTERATIONS \$100,000 OR LESS (AUG 2008) | 47 |
| 5.4 | | |
| 5.5 | NEO ONSIDIENT OF THE LESSON AND LESSON'S ARCHITECT/ENGINEED (ALIC 2000) | 40 |
| 5.6 | | |
| 5.7 | ENDTING THEOUT, SALVAGED, OR RE-USED BUILDING MATERIAL (SED 2000) | 40 |
| 5.8 | OUNDINGOTION WAS TE MANAGEMENT TATIG VIOLET | |
| 5.9 | TABOOK AIN GOALITT DORING CONSTRUCTION (THE COUNT) | 40 |
| 5.10 5.11 | | |
| 5.12 | OCHOTHOUTON SOMEDULE AND ACCEPTANCE OF TENANT IMPROVEMENTS (MAR 2007) | 00 |
| 5.12 | 1 NOONEGO NEFONTO (AUG 2006) | 0.4 |
| 5.13 5.14 | OUND INDUITION INSPECTIONS (AUG 2008) | |
| 5.1 4 5.15 | TEOORT EARS ALLER OCCUPANCT (DEC 2005) | 04 |
| 5.15 5.16 | | |
| 5.17 | OF OCKLITI OK NEW CONSTRUCTION | ~~ |
| 5.18 | OFFICIAL OF MEM CONSTRUCTION | ^^ |
| 5.19 | TIME TROTECTION FOR NEW CONSTRUCTION | 22 |
| . 10 | | 22 |



| 6.0 | GENERAL ARCHITECTUREACCESSIBILITY (FFR 2007) | 24 |
|------------|---|--------------|
| 6.1 | | |
| 6.2 | =: (1 0 7 11 10 7 10 0 E 00 10 E 0 2007) | |
| 6.3 | | |
| 6.4 | | |
| 6.5 | | |
| 6.6 | FLOORS AND FLOOR LOAD (SEP 2000) | 24 |
| 6.7 | CEILINGS (SEP 2000) | 25 |
| 6.8 | | |
| 6.9 | | |
| 6.10 | | |
| 6.11 | | |
| 6.12 | LANDSCAPING (SEP 2000) | 26 |
| 6.13 | FLAGPOLE AND DISPLAY (AUG 2008) | 26 |
| | | 20 |
| 7.0 | ARCHITECTURAL FINISHES | |
| 7.1 | ARCHITECTURAL FINISHESRECYCLED CONTENT PRODUCTS (COMPRESEDENCE PROCUPEMENT OF UNDER VISION OF THE PRODUCTS (COMPRESEDENCE PROCUPEMENT OF UNDER VISION OF THE PROCUPEMENT OF UNDER VISION OF UNDER VISION OF THE PROCUPEMENT OF UNDER VISION OF UNDER VISI | 27 |
| 7.2 | RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (SEP 2000) | 27 |
| 7.3 | ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS (DEC 2007) | 27 |
| 7.4 | FINISH SELECTIONS (AUG 2008) | 27 |
| 7.5 | ADHESIVES AND SEALANTS (AUG 2008) | 27 |
| 7.6 | DOORS: SUITE ENTRY (AUG 2008) | 28 |
| 7.7 | DOORS: INTERIOR (AUG 2008) | 28 |
| 7.8 | | |
| 7.9 | DOORS: IDENTIFICATION (SEP 2000) | 28 |
| 7.10 | | |
| 7.11 | WALL FINISHES (AUG 2008)PAINTING (DEC 2007) | 28 |
| 7.12 | | |
| 7.13 | | |
| 7.14 | CARPET: BROADLOOM (AUG 2008) | 30 |
| 7.15 | CARPET TILE (AUG 2008) | .31 |
| 7.16 | ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS | .31 |
| | | . 3 I |
| 8. 0 | MECHANICAL ELECTRICAL DI UNADINO | |
| 8.1 | MECHANICAL, ELECTRICAL, PLUMBING | .33 |
| 8.2 | | |
| 8.3 | BUILDING SYSTEMS (AUG 2008) | .33 |
| 8.4 | ENERGY COST SAVINGS (AUG 2008) | . 33 |
| 8.5 | INSULATION: THERMAL, ACOUSTIC, AND HVAC (AUG 2008) | .33 |
| 8.6 | DRINKING FOUNTAINS (AUG 2008) | .33 |
| 8.7 | TOILET ROOMS (AUG 2008) | . 33 |
| 8.8 | TOILET ROOMS: FIXTURE SCHEDULE (SEP 2000) | .34 |
| 8.9 | JANITOR CLOSETS (DEC 2007) | . 34 |
| 8.10 | HEATING AND AIR CONDITIONING (AUG 2008)VENTILATION (AUG 2008) | . 35 |
| 8.11 | VENTILATION (AUG 2008) | . 35 |
| 8.12 | ELECTRICAL: DISTRIBUTION (AUG 2008) | . 36 |
| 8.13 | TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000) | .36 |
| 8.14 | TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008) | 36 |
| 8.15 | DATA DISTRIBUTION (AUG 2008) | .37 |
| 8.16 | ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (AUG 2008) | 37 |
| 8.17 | ADDITIONAL ELECTRICAL CONTROLS | 37 |
| 8.18 | ELEVATORS (AUG 2008) | |
| 8.19 | LIGHTING: INTERIOR AND PARKING (AUG 2008) | 38 |
| 8.20 | ENERGY COST SAVINGS | 38 |
| | | 39 |
| 9. 0 | FIRE PROTECTION LIFE CAPETY AND THURSDAY | |
| 9.1 | FIRE PROTECTION, LIFE SAFETY, AND ENVIRONMENTAL ISSUES | 40 |
| 9.2 | MEANS OF EGRESS (SEP 2007) | 40 |
| 9.3 | AUTOMATIC FIRE SPRINKLER SYSTEM (AUG 2008) | 40 |
| 9.4 | FIRE ALARM SYSTEM (AUG 2008) | 40 |
| 9.5 | OSHA REQUIREMENTS (SEP 2000) | 40 |
| 9.6 | ASBESTOS (SEP 2000) | 40 |
| 9.7 | INDOOR AIR QUALITY (DEC 2007) | 41 |
| 9.8 | RADON IN AIR (AUG 2008) | 41 |
| 9.9 | RADON IN WATER (AUG 2008) | 41 |
| 9.10 | RECYCLING (DEC 2007) | 41 |
| 9.11 | OCCUPANT EMERGENCY PLANS (ALIG 2008) | 41 |
| 9.12 | OCCUPANT EMERGENCY PLANS (AUG 2008) | 12 |
| | 4 | ļ 2 |
| 10.0 | | |
| 0.0 | LEASE SECURITY STANDARDS | 13 |
| 10.1 | | |
| 0.2 0.3 | | |
| 0.5 | ACCESS TO UTILITY AREAS (NOV 2005) | 13 |
| SFO N | o. 3NY0336 | |
| 2 | o. 3NY0336 LESSOR & GOVERNMENT | |
| | ELESSIPIC ZGOVERNMENT | |

| 10.4 | MECHANICAL PARENT TO CRITICAL SYSTEMS (SEP 2009) | 43 |
|-------|--|--------|
| 10.5 | MECHANICAL AREAS AND BUILDING ROOFS (NOV 2005) | 12 |
| 10.6 | ACCESS TO BUILDING INFORMATION (NOV 2005) | 40 |
| 10.7 | POSTING OF GOVERNMENT RULES AND REGULATIONS (TENANT IMPROVEMENT) (NOV 2005) | 11 |
| 10.8 | DEVELOPMENT, IMPLEMENTATION, AND PERIODIC REVIEW OF OCCUPANT EMERGENCY PLANS (NOV 2005) | 44 |
| 10.9 | BUILDING SECURITY PLAN (NOV 2005) | |
| 10.10 | ADDITIONAL SECURITY MEASURES AS DETERMINED BY THE GOVERNMENT (NOV 2005) | 44 |
| 10.11 | IDENTIFY VERIFICATION OF PERSONNEL (MAY 2007) | 44 |
| 10.12 | ENTRY SECURITY: INTRUSION DETECTION SYSTEM WITH CENTRAL MONITORING CAPABILITY (NOV 2005) | 44 |
| 10.13 | OCCUPANT/VISITOR SCREENING: VISITOR CONTROL/SCREENING SYSTEM (NOV 2005) | 44 |
| 10.14 | SECURE HVAC: OUTDOOR AIR INTAKES (BUILDING SHELL) (NOV 2005) | 11 |
| 10.15 | SECURE HVAC: AIRBORNE HAZARDS (NOV 2005) | 44 |
| 10.16 | SECURE HVAC: SECURE RETURN-AIR GRILLES (BUILDING SHELL) (NOV 2005) | 45 |
| 10.17 | PARKING SECURITY REQUIREMENTS (NOV 2005) | AE. |
| 10.18 | COTY MONITORING: COTY SURVEILLANCE CAMERAS WITH TIME LAPSE VIDEO RECORDING (NOV 2005) | 45 |
| 10.19 | CCTV MONITORING: POST SIGNS ADVISING OF 24-HOUR VIDEO SURVEILL ANCE (TENANT IMPROVEMENT) (NOV. 2005) | 45 |
| 10.20 | SHATTER-RESISTANT WINDOW PROTECTION REQUIREMENTS (NOV 2005) (BUILDING SHELL) | 45 |
| 10.21 | TEMPORARY SECURITY UPGRADE DUE TO IMMEDIATE THREAT (NOV 2005) | 40 |
| 10.22 | SECURIT DESIGN CRITERIA | 40 |
| 10.23 | SECURITY DESIGN CRITERIA: SETBACK (BUILDING SHELL) | 40 |
| 10.24 | SECURITY DESIGN CRITERIA: FAÇADE PROTECTION (BUILDING SHELL) | 40 |
| 10.25 | SECURITY DESIGN CRITERIA: SHATTER-RESISTANT WINDOWS (BUILDING SHELL) | 40 |
| 10.26 | SECURITY DESIGN CRITERIA: HVAC (BUILDING SHELL) | . 40 |
| 10.27 | SECURITY DESIGN CRITERIA: DESIGN AND ENGINEERING DOCUMENTS | .40 |
| | Z.O. LELANO DOCUMENTO | .40 |
| | | |
| 11.0 | SPECIAL REQUIREMENTS | .47 |
| 11.1 | SPECIAL REQUIREMENTS: | .47 |
| | | |

MT & GOVERNMENT

1.0 SUMMARY

1.1 AMOUNT AND TYPE OF SPACE (AUG 2008)

- A. Intentionally omitted.
- B. Intentionally omitted.
- C. Intentionally omitted.
- D. Intentionally omitted.
- E. Unless otherwise noted, all references in this SFO to square feet shall mean ANSI/BOMA Office Area square feet (ABOA). The terms ANSI/BOMA Office Area (ABOA) and usable square feet (usf) are used interchangeably throughout this SFO and its attachments.
- F. As part of this space requirement, the Government will require use of part of the building roof for the installation of antenna(s). Further specifications regarding the type of antenna(s) and mounting requirements are included as an attachment to this SFO.
- G. Approximately 250 square feet of the ANSI/BOMA Office Area space required above will be used for the operation of a vending facility(ies) by the blind under the provisions of the Randolph-Sheppard Act (United States Code 20 USC 107 et. seq.). The Government will control the number, kind, and locations of vending facilities and will control and receive income from all automatic vending machines. The Lessor is required to provide necessary utilities and to make related alterations. The cost of the improvements will be negotiated, and payment will be made by the Government either on a lump-sum basis or a rental increase.

The Government will not compete with other facilities having exclusive rights in the building. The Offeror shall advise the Government if such rights exist. During the term of the lease, the Lessor may not establish any vending facilities within the leased space that will compete with the Randolph-Sheppard vending facilities.

1.2 UNIQUE REQUIREMENTS (AUG 2008)

The offered building and/or location must have the following features:

- A. Space must be one contiguous block without being separated by public corridors.
- B. Space cannot be located on the ground floor; 2nd floor space or higher is required.
- C. Intentionally omitted.
- D. Intentionally omitted.

In the event of any conflict between the specifications in this section 1.2, Unique Requirements, and those specified on page 10 of Exhibit A, this section 1.2 Unique Requirements shall prevail.

1.3 LEASE TERM (SEP 2000)

Intentionally omitted.

1.4 OFFER DUE DATE (AUG 2008)

Intentionally omitted.

1.5 ACCESS AND APPURTENANT AREAS (AUG 2008)

The right to use appurtenant areas and facilities is included. The Government reserves the right to post Government rules and regulations where the Government leases space. See the Lease Security Standards section of this SFO for additional information.

1.6 SERVICES, UTILITIES, MAINTENANCE: GENERAL (AUG 2008)

Services, utilities, and maintenance shall be provided by the Lessor as part of the rental consideration. The Lessor shall have an onsite building superintendent or a locally designated representative available to promptly respond to deficiencies, and immediately address all emergency situations.

1.7 AREA OF CONSIDERATION (AUG 2008)

Intentionally omitted.

1.8 LOCATION: OUTSIDE CITY CENTER (AUG 2008)

Intentionally omitted.

MTM & SW.
LESSOR GOVERNMENT

1.9 OCCUPANCY DATE (AUG 2008) Intentionally omitted

1.10 NEGOTIATIONS (MAY 2005)

Intentionally omitted.

1.11 QUALITY AND APPEARANCE OF BUILDING (AUG 2008)

Intentionally omitted.

1.12 BUILDING SHELL REQUIREMENTS (AUG 2008)

- A. The Lessor's obligations in providing a building shell shall include the following as part of the Lessor's shell rent: All items identified in this solicitation as "building shell" are to be provided, installed, maintained, repaired, and/or replaced as part of the Lessor's shell rent.
 - 1. Base structure and building enclosure components shall be complete. All common areas accessible by the Government, such as lobbies, fire egress corridors and stairwells, elevators, garages, and services areas, shall be complete. Restrooms shall be complete and operational. All newly installed building shell components, including but not limited to, heating, ventilation, and air conditioning (HVAC), electrical, ceilings, sprinklers, etc., shall be furnished, installed, and coordinated with Tenant Improvements. Circulation corridors are provided as part of the base building only on multi-tenanted floors where the corridor is common to more than one tenant. On single tenant floors, only the fire egress corridor necessary to meet code is provided as part of the shell.
 - Accessibility Requirements. Accessibility to persons with disabilities shall be required throughout the common areas
 accessible to Government tenants in accordance with the Architectural Barriers Act Accessibility Standard (ABAAS),
 Appendices C and D to 36 CFR Part 1191 (ABA Chapters 1 and 2, and Chapters 3 through 10) and shall be installed and
 coordinated with Tenant Improvements. To the extent the standard referenced in the preceding sentence conflicts with local
 accessibility requirements, the more stringent standard shall apply.
 - 3. Ceilings. A complete acoustical ceiling system (which includes grid and lay-in tiles or other building standard ceiling system as approved by the Contracting Officer) throughout the Government-demised area and all common areas accessible to Government tenants shall be required in accordance with the "Ceilings" paragraph elsewhere in this SFO. The acoustical ceiling system shall be furnished, installed, and coordinated with Tenant Improvements.
 - 4. Doors. Exterior building doors and doors necessary to the lobbies, common areas, and core areas shall be required. This does not include suite entry or interior doors specific to Tenant Improvements. Related hardware shall be installed in accordance with the "Doors: Hardware" paragraph and the "Doors: Exterior" paragraph elsewhere in this SFO.
 - Partitions. Permanent, perimeter, and demising slab-to-slab partitions (including all columns) finished with paint and base shall be required in accordance with the "Partitions: General" paragraph and the "Partitions: Permanent" paragraph elsewhere in this SFO.
 - Flooring. All building common areas shall have finished floors in accordance with the "Floor Covering and Perimeters" paragraph elsewhere in this SFO.
 - 7. Plumbing. The Offeror shall include cost of plumbing in common areas, such as for toilet rooms and janitor closets as part of the building shell cost. Hot and cold water risers and domestic waste and vent risers, installed and ready for connections that are required for Tenant Improvements, shall be included in the shell rent.
 - HVAC. Central HVAC systems shall be installed and operational, including, as appropriate, main and branch lines, VAV boxes, dampers, flex ducts, and diffusers, for an open office layout, including all building common areas. Conditioned air through medium pressure duct work at a rate of .75 cubic feet per minute per ANSI/BOMA Office Area square foot shall be provided.
 - Electrical. Electrical power distribution panels and circuit breakers shall be available in an electrical closet, with capacity at 277/480 volt (V) and 120/208 V, 3-phase, 4-wire system providing 7 watts (W) per ANSI/BOMA Office Area square foot.
 - 10. Lighting. Parabolic type 2'-0" wide x 4'-0" long fluorescent lighting fixtures (or other building standard fixtures approved by the GSA Contracting Officer) shall be installed in the ceiling grid for an open office plan at the rate of 1 fixture per 80 ANSI/BOMA Office Area square feet. Lighting as necessary shall be provided in all building common areas in accordance with the "Lighting: Interior and Parking" paragraph elsewhere in this SFO.
 - 11. Safety and Environmental Management. Complete safety and environmental management shall be provided throughout the building in accordance with federal, state, and local codes and laws including, but not limited to, such items as fire detection and alarms, emergency building power for life safety systems, etc., and shall be in accordance with ABAAS. Where sprinklers are required in the Government-demised area, sprinkler mains and distribution piping in a "protection" layout (open plan) with heads turned down with an escutcheon or trim plate shall be provided.
 - Telephone Rooms. Building telecommunication rooms on each floor shall be completed, operational, and ready for Tenant Improvements. The telephone closets shall include a telephone backboard.

MIM & GOVERNMENT

- 13. Demolition. The Offeror shall remove existing abandoned electric, telephone and data cabling and devices as well as any other improvements or fixtures in place to accommodate the Government's design intent drawings. Any demolition of existing improvements that is necessary to satisfy the Government's layout shall be done at the Lessor's expense. Any demolition shall be completed in accordance with all applicable laws.
- 14. All of the above improvements are described in more detail hereinafter in this solicitation.
- 15. Unless an item is specifically labeled as Tenant Improvement (TI), it shall be considered a shell item.

1.13 LABOR STANDARDS (AUG 2003)

If an Offeror proposes to satisfy the requirements of this SFO through the construction of a new building or the complete rehabilitation or reconstruction of an existing building, and the Government will be the sole or predominant tenant such that any other use of the building will be functionally or quantitatively incidental to the Government's use and occupancy, the following Federal Acquisition Regulation (FAR) clauses shall apply to all work (including base building and tenant improvements) performed prior to the Government's acceptance of space as substantially complete. Full text versions of these clauses are available upon request from the Contracting Officer. Full text versions are also available at the following web site: HTTP://WWW.ARNET.GOV/FAR/

| | • |
|-----------|--|
| 52.222-4 | Contract Work Hours and Safety Standards Act - Overtime Compensation |
| 52.222-6 | Davis-Bacon Act |
| 52.222-7 | Withholding of Funds |
| 52.222-8 | Payrolls and Basic Records |
| 52.222-9 | Apprentices and Trainees |
| 52.222-10 | Compliance with Copeland Act Requirements |
| 52.222-11 | Subcontracts (Labor Standards) |
| 52.222-12 | Contract Termination-Debarment |
| 52.222-13 | Compliance with Davis-Bacon and Related Act Regulations |
| | |

52.222-14 Disputes Concerning Labor Standards

52.222-15 Certification of Eligibility

MIM & W ;

LESSOR & GOVERNMENT

2.0 **AWARD FACTORS AND PRICE EVALUATION**

- **AWARD BASED ON PRICE (SEP 2000)** 2.1 Intentionally omitted.
- 2.2 **SEISMIC SAFETY (FEB 2007)** Intentionally omitted.
- **RELOCATION ASSISTANCE ACT (MAR 2002)** 2.3 Intentionally omitted.

BROKER COMMISSION AND COMMISSION CREDIT (NOV 2006) SEE RIDER PARAGRAPH 12

- A. For the purposes of this SFO, Jones Lang LaSalle (the Broker) is the authorized real estate broker representing GSA. A GSA CONTRACTING OFFICER MUST REVIEW, APPROVE, AND EXECUTE THE LEASE. The government expects the Lessor to pay a commission to the Broker. By submitting an offer, the Lessor agrees that if the Lessor is paying a commission or fee in connection with this lease transaction to a listing agent, an offering agent, or broker, property manager, developer, or any other agent or representative, then the Lessor will pay a commission to the Broker that it normally would be entitled to pursuant to local business practices, as evidenced through a brokerage agreement between the Lessor and the Broker. The commission will be negotiated between the Lessor and the Broker and will be based on a lease term not to exceed the firm term of the lease contract. Commissions will not be negotiated or collected on option periods or for lease terms beyond the firm term of the lease. The Lessor agrees that the commission to be paid to the Broker shall be paid not later than the Lease Commencement date as defined in the "Construction Schedule of Tenant Improvements" paragraph in the MISCELLANEOUS section of this SFO. As part of the offer, the Offeror shall disclose any and all commissions and/or fees to be paid by the Lessor including both the Lessor's agent(s), broker(s), property manager, developer or any other agent or representative and the Broker.
- B. For the benefit of the Government, the Broker has agreed to forego thirty-four percent (34%) of the commission that it is entitled to receive in connection with this lease transaction. The resulting total dollar value of the foregone commission (the Commission Credit) shall be applied in equal monthly amounts against shell rental payments due and owing under the Lease. The rental amount payable shall be reduced by the Commission Credit at the commencement of the Lease, over the minimum number of months that will not exceed the monthly shell rental, until the Commission Credit has been fully recaptured. The parties agree to execute a Supplemental Lease Agreement setting forth the full nature, extent, terms, and conditions of commissions paid to the Broker and the Commission Credit to be applied against the Government's rental payment obligations under the Lease
- C. For purposes of price evaluation, the Commission Credit shall be treated as a deduction from the rent in accordance with the "Price Evaluation" paragraph in the SUMMARY section of this SFO. The amount of the commission paid to GSA's Broker shall not be considered separately as part of this price evaluation since the value of the commission is subsumed in the gross rent rate.
- PRICE EVALUATION (PRESENT VALUE) (AUG 2008) 2.5 Intentionally omitted.
- 2.6 **AWARD (AUG 2008)** Intentionally omitted.

3.0 **HOW TO OFFER AND SUBMITTAL REQUIREMENTS**

OFFER PROCEDURES (AUG 2008) 3.1 Intentionally omitted.

3.2

- TENANT IMPROVEMENTS INCLUDED IN OFFER (AUG 2008)

 A. The Tenant Improvement Allowance is (b) (4) per ANSI/BOMA Office Area square foot. (Tenant improvements are the finishes and fixtures that typically take space from the "shell" condition to a finished, usable condition.) The Tenant Improvement Allowance shall be used for the build out of the Government-demised area in accordance with the Government-approved design intent drawings. All Tenant Improvements required by the Government for occupancy shall be performed by the successful Offeror as part of the rental consideration, and all improvements shall meet the quality standards and requirements of this solicitation and its attachments.
- B. The Tenant Improvement Allowance shall include all the Offeror's administrative costs, general contractor fees, subcontractor's profit and overhead costs, Offeror's profit and overhead, design costs, and other associated project fees necessary to prepare construction documents and to complete the tenant improvements. It is the successful Offeror's responsibility to prepare all documentation (working/construction drawings, etc.) required to receive construction permits. NO COSTS ASSOCIATED WITH THE BUILDING SHELL SHALL BE INCLUDED IN THE TENANT IMPROVEMENT PRICING.

TENANT IMPROVEMENT RENTAL ADJUSTMENT (AUG 2008) 3.3

- All Tenant Improvements shall be identified after award of the contract in accordance with the provisions established in the "Design Intent Drawings" subparagraph in the "Construction Schedule and Acceptance of Tenant Improvements" paragraph in the DESIGN, CONSTRUCTION, AND OTHER POST AWARD ACTIVITIES section and elsewhere throughout this SFO
 - 1. The Government, at its sole discretion, shall make all decisions as to the usage of the Tenant Improvement Allowance. The Government may use all or part of the Tenant Improvement Allowance. The Government may return to the Lessor any unused portion of the Tenant Improvement Allowance in exchange for a decrease in rent according to the amortization rate over the firm term.
 - 2. The Government reserves the right to make cash payments for any or all work performed by the Lessor. Prior to occupancy, the Government, at its sole discretion, may choose to pay lump sum for any or all of the Tenant Improvement Allowance. If, prior to occupancy, the Government elects to make a lump sum payment for any portion of the Tenant Improvement Allowance, the payment of the Tenant Improvement Allowance by the Government will result in a decrease in the rent. At any time after occupancy and during the firm term of the lease, the Government, at its sole discretion, may choose to pay lump sum for any part or all of the remaining unpaid amortized balance of the Tenant Improvement Allowance if the original occupant agency vacates the space. If the Government elects to make a lump sum payment for the Tenant Improvement Allowance after occupancy, the payment of the Tenant Improvement Allowance by the Government will result in a decrease in the rent according to the amortization rate over the firm term of the lease.
 - 3. If it is anticipated that the Government will spend more than the allowance identified above, the Government reserves the right to either 1) reduce the Tenant Improvement requirements, 2) pay lump sum for the overage upon completion and acceptance of the improvements, or 3) increase the rent according to the negotiated amortization rate over the firm term of the lease SEE PARAGRAPH 10 OF THE LEASE RIDER
 - 4. Payment will not be made by the Government in instances where the Government accepts fixtures and/or other Tenant Improvements already in place. However, the Lessor will be reimbursed for costs to repair or improve the fixture(s) and/or any other improvements already in place.

3.4 GSA FORMS AND PRICING INFORMATION (AUG 2008) Intentionally omitted.

3.5 **EVIDENCE OF CAPABILITY TO PERFORM (AUG 2008)**

Intentionally omitted.

AFTER AWARD:

Within thirty (30) days after lease award, the Lessor shall provide to the Contracting Officer evidence of:

- A firm commitment of funds in an amount sufficient to perform the work.
- 2. The names of at least two proposed construction contractors, as well as evidence of the contractors' experience, competency, and performance capabilities with construction similar in scope to that which is required herein.
- The license or certification to practice in the state where the facility is located from the individual(s) and/or firm(s) providing architectural and engineering design services.

VI TM & GOVERNMENT

| C. | AFTER ISSUANCE OF NOTICE TO PROCEED FOR TENANT IMPROVEMENTS: | |
|----|--|-----------|
| | Within fifteen (15) days after the Contracting Officer issues the Notice to Proceed for Tenant Improvements, the Les | cor chall |
| | provide to the Contracting Officer evidence of: | soi snaii |

- Award of a construction contract for Tenant Improvements with a firm completion date. This date must be in accord with the
 construction schedule for tenant improvements as described in the "Construction Schedule and Acceptance of Tenant
 Improvements" paragraph of this SFO.
- 2. Issuance of a building permit covering construction of the improvements.

3.6 BUILDING AND SITE INFORMATION SUBMITTALS (AUG 2008)

A. Intentionally omitted.

B. AFTER AWARD:

- In accordance with the "Services, Utilities, Maintenance: General" paragraph in the Summary section of this SFO, provide the name and contact information for the onsite or locally designated representative.
- In accordance with the "Schedule of Periodic Services" paragraph in the UTILITIES, SERVICES, and LEASE ADMINISTRATION section of this SFO, provide the schedule of periodic services for other than daily, weekly or monthly services.

3.7 GREEN LEASE SUBMITTALS

Intentionally omitted.

B. AFTER AWARD, THE LESSOR SHALL SUBMIT TO THE CONTRACTING OFFICER:

- 1. Product Data sheets for floor coverings, paints and wall coverings, ceiling materials, all adhesives, wood products, suite and interior doors, subdividing partitions, wall base, door hardware finishes, window coverings, millwork substrate and millwork finishes, lighting and lighting controls, and insulation to be used within the leased space. This information must be submitted NO LATER THAN the submission of the Design Intent Drawings for the leased space, as outlined in the "Construction Schedule and Acceptance of Tenant Improvements" paragraph of the DESIGN, CONSTRUCTION, AND OTHER POST AWARD ACTIVITIES section of the SFO.
- Material Safety Data Sheets (MSDS) or other appropriate documents upon request for products listed in the Indoor Air Quality During Construction paragraph.
- Reuse Plan required in accordance with the "Existing Fit-out, Salvaged, or Re-used Building Material" paragraph in the DESIGN, CONSTRUCTION, AND OTHER POST AWARD ACTIVITIES section of this SFO.
- Any waiver needed when not using materials from the CPG and RMAN lists of acceptable products in accordance with the "Recycled Content Products" paragraph in the ARCHITECTURAL FINISHES section of the SFO.
- Radon test results as may be required by the "Radon in Air" and "Radon in Water" paragraphs in the FIRE PROTECTION, LIFE SAFETY, AND ENVIRONMENTAL ISSUES section of the SFO.
- 6. Construction Waste Management Plan:
 - Prior to construction commencement, a proposed plan following industry standards to recycle construction waste. The construction waste management plan shall quantify material diversion goals and maximize the materials to be recycled and/or salvaged (at least 50 percent) from construction, demolition, and packaging debris. Where the small quantity of material, the extraordinarily complex nature of the waste disposal method, or prohibitive expense for recycling would represent a genuine hardship, the Government, upon written request of the Lessor and approval of the Contracting Officer, may permit alternative means of disposal.
- 7. Building Recycling Service Plan:
 - A building recycling service plan with floor plans annotating recycling area(s) as part of Design Intent Drawings to be reflected on the Construction Drawing submission.
- A signed statement provided to the Contracting Officer, completed by the Lessor for the leased space, explaining how all HVAC systems serving the leased space will achieve the desired ventilation of the space during the flush-out period called for in the "Indoor Air Quality During Construction" (Dec 2007) paragraph in the DESIGN, CONSTRUCTION, AND OTHER POST AWARD ACTIVITIES section of this SFO.
- 9. In accordance with the incorporation of commissioning requirements called for in the "Mechanical, Electrical, Plumbing: General" (Aug 2008) paragraph in the MECHANICAL, ELECTRICAL, PLUMBING section of this SFO a written commissioning plan submitted to the Contracting Officer prior to the completion of Design Intent Drawings that includes:
 - a. a schedule of systems commissioning (revised as needed during all construction phases of the project -with such revisions provided to the Contracting Officer immediately) and
 - b. a description of how commissioning requirements will be met and confirmed.
- 10. Intentionally omitted.

Mam & Sul .

LESSOR & GOVERNMENT

4.0 <u>UTILITIES, SERVICES, AND LEASE ADMINISTRATION</u>

4.1 MEASUREMENT OF SPACE (AUG 2008)

A. ANSI/BOMA OFFICE AREA SQUARE FEET:

- For the purposes of this solicitation, the Government recognizes the American National Standards Institute/Building Owners and Managers Association (ANSI/BOMA) international standard (Z65.1-1996) definition for Office Area, which means "the area where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed."
- 2. ANSI/BOMA Office Area (ABOA) square feet shall be computed by measuring the area enclosed by the finished surface of the room side of corridors (corridors in place as well as those required by local codes and ordinances to provide an acceptable level of safety and/or to provide access to essential building elements) and other permanent walls, the dominant portion (refer to Z65.1) of building exterior walls, and the center of tenant-separating partitions. Where alcoves, recessed entrances, or similar deviations from the corridor are present, ABOA square feet shall be computed as if the deviation were not present.
- 3. ABOA square feet and usable square feet (USF) may be used interchangeably throughout the lease documents.

B. RENTABLE SPACE:

Rentable space is the area for which a tenant is charged rent. It is determined by the building owner and may vary by city or by building within the same city. The rentable space may include a share of building support/common areas such as elevator lobbies, building corridors, and floor service areas. Floor service areas typically include restrooms, janitor rooms, telephone closets, electrical closets, and mechanical rooms. The rentable space does not include vertical building penetrations and their enclosing walls, such as stairs, elevator shafts, and vertical ducts.

C. COMMON AREA FACTOR:

If applicable, the Offeror shall provide the Common Area Factor (a conversion factor(s) determined by the building owner and applied by the owner to the ANSI/BOMA Office Area square feet to determine the rentable square feet for the offered space).

4.2 TAX ADJUSTMENT (AUG 2008)

SEE RIDER PARAGRAPH 13

A. Purpose:

This paragraph provides for adjustment in the rent ("Tax Adjustment") to account for increases or decreases in Real Estate Taxes for the Property after the establishment of the Real Estate Tax Base, as those terms are defined herein. Tax Adjustments shall be calculated in accordance with this Clause.

B. Definitions:

The following definitions apply to the use of capitalized terms within this paragraph:

- "Property" is the land, buildings and other improvements of which the premises (as fully described in the U.S. Government Lease for Real Property, SF2) form all or a part.
- 2. "Real Estate Taxes" are those taxes that are levied upon the owners of real property by a Taxing Authority (as hereinafter defined) of a State or local Government on an ad valorem basis to raise general revenue for funding the provision of government services. The term excludes, without limitation, special assessments for specific purposes, assessments for business improvement districts, and/or community development assessments.
- "Taxing Authority" is a State, Commonwealth, Territory, County, City, Parish, or political subdivision thereof, authorized by law to levy, assess, and collect Real Estate Taxes.
- "Tax Year" refers to the 12-month period adopted by a Taxing Authority as its fiscal year for the purpose of assessing Real Estate Taxes on an annual basis.
- "Tax Abatement" is an authorized reduction in the Lessor's liability for Real Estate Taxes below that determined by applying the generally applicable Real Estate Tax rate to the Fully Assessed (as hereinafter defined) valuation of the Property.
- 6. "Unadjusted Real Estate Taxes" are the full amount of Real Estate Taxes that would be assessed for the Property for one full Tax Year without regard to the Lessor's entitlement to any Tax Abatements (except if such Tax Abatement came into effect after the date of award of the Lease), and not including any late charges, interest or penalties. If a Tax Abatement comes into effect after the date of award of the Lease, "Unadjusted Real Estate Taxes" are the full amount of Real Estate Taxes assessed for the Property for one full Tax Year, less the amount of such Tax Abatement, and not including any late charges, interest or penalties.
- 7. "Real Estate Tax Base" is the Unadjusted Real Estate Taxes for the first full Tax Year following the commencement of the Lease term. If the Real Estate Taxes for that Tax Year are not based upon a Full Assessment of the Property, then the Real Estate Tax Base shall be the Unadjusted Real Estate Taxes for the Property for the first full Tax Year for which the Real Estate Taxes are based upon a Full Assessment. Such first full Tax Year may be hereinafter referred to as the "Tax Base Year." Alternatively, the Real Estate Tax Base may be an amount negotiated by the parties that reflects an agreed upon base for a Fully Assessed value of the property.
- 8. The Property is deemed to be "Fully Assessed" (and Real Estate Taxes are deemed to be based on a "Full Assessment") only when a Taxing Authority has, for the purpose of determining the Lessor's liability for Real Estate Taxes, determined a

M JUST & BOVERNMENT

value for the Property taking into account the value of all improvements contemplated for the Property pursuant to the Lease, and issued to the Lessor a tax bill or other notice of levy wherein the Real Estate Taxes for the full Tax Year are based upon such Full Assessment. At no time prior to the issuance of such a bill or notice shall the Property be deemed Fully Assessed.

"Percentage of Occupancy" refers to that portion of the Property exclusively occupied or used by the Government pursuant to the Lease. For buildings, the Percentage of Occupancy is determined by calculating the ratio of the rentable square feet occupied by the Government pursuant to the Lease to the total rentable square feet in the building or buildings so occupied, and shall not take into account the Government's ancillary rights including, but not limited to, parking or roof space for antennas (unless facilities for such ancillary rights are separately assessed). This percentage shall be subject to adjustment to take into account increases or decreases in the amount of space leased by the Government or in the amount of rentable space on the Property.

C. Adjustment for Changes in Real Estate Taxes:

- After the Property is Fully Assessed, the Government shall pay its share of any increases and shall receive its share of any decreases in the Real Estate Taxes for the Property, such share of increases or decreases to be referred to herein as "Tax The amount of the Tax Adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base, less the portion of such difference not paid due to a Tax Abatement (except if a Tax Abatement comes into effect after the date of award of the Lease). If a Tax Abatement comes into effect after the date of award of the Lease, the amount of the Tax Adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base. The Government shall pay the Tax Adjustment in a single annual lump sum payment to the Lessor. In the event that this Tax Adjustment results in a credit owed to the Government, the Government may elect to receive payment in the form of a rental credit or lump sum payment.
- If the Property contains more than one separately assessed parcel, then more than one Tax Adjustment shall be determined based upon the Percentage of Occupancy, Real Estate Tax Base, and Real Estate Taxes for each respective parcel.
- After commencement of the Lease term, the Lessor shall provide to the Contracting Officer copies of all Real Estate Tax bills for the Property, all documentation of Tax Abatements, credits, or refunds, if any, and all notices which may affect the assessed valuation of the Property, for the Tax Year prior to the commencement of the Lease Term, and all such documentation for every year following. Lessor acknowledges that the Contracting Officer shall rely on the completeness and accuracy of these submissions in order to establish the Real Estate Tax Base and to determine Tax Adjustments. The Contracting Officer may memorialize the establishment of the Real Estate Tax Base by issuing a unilateral administrative Supplemental Lease Agreement indicating the Base Year, the amount of the Real Estate Tax Base, and the Government's Percentage of Occupancy.
- The Real Estate Tax Base is subject to adjustment when increases or decreases to Real Estate Taxes in any Tax Year are attributable to a) improvements or renovations to the Property not required by this Lease, or b) changes in net operating income for the Property not derived from this Lease. If either condition results in a change to the Real Estate Taxes, the Contracting Officer may re-establish the Real Estate Tax Base as the Unadjusted Real Estate Taxes for the Tax Year the Property is reassessed under such condition, less the amount by which the Unadjusted Real Estate Taxes for the Tax Year prior to reassessment exceeds the prior Real Estate Tax Base.
- If this Lease includes any options to renew the term of the Lease, or be otherwise extended, the Real Estate Tax Base for the purpose of determining Tax Adjustments during the renewal term or extension shall be the last Real Estate Tax Base established during the base term of the Lease.
- If any Real Estate Taxes for the Property are retroactively reduced by a Taxing Authority during the term of the Lease, the Government shall be entitled to a proportional share of any tax refunds to which the Lessor is entitled, calculated in accordance with this Clause.
- Lessor acknowledges that it has an affirmative duty to disclose to the Government any decreases in the Real Estate Taxes paid for the Property during the term of the Lease. Lessor shall annually provide to the Contracting Officer all relevant tax records for determining whether a Tax Adjustment is due, irrespective of whether it seeks an adjustment in any Tax Year.
- If the Lease terminates before the end of a Tax Year, or if rent has been suspended, payment for the Real Estate Tax increase due as a result of this section for the Tax Year will be prorated based on the number of days that the Lease and the rent were in effect. Any credit due the Government after the expiration or earlier termination of the Lease shall be made by a lump sum payment to the Government or as a rental credit to any succeeding lease, as determined in the Contracting Officer's sole discretion. Lessor shall remit any lump sum payment to the Government within 15 calendar days of payment or credit by the Taxing Authority to Lessor or Lessor's designee. If the credit due to the Government is not paid by the due date, interest shall accrue on the late payment at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978, as amended (41 USC § 611), that is in effect on the day after the due date. The interest penalty shall accrue daily on the amount of the credit and shall be compounded in 30-day increments inclusive from the first day after the due date through the payment date. The Government shall have the right to pursue the outstanding balance of any tax credit using all such collection methods as are available to the United States to collect debts. Such collection rights shall survive the expiration of this Lease.
- In order to obtain a Tax Adjustment, the Lessor shall furnish the Contracting Officer with copies of all paid tax receipts, or other similar evidence of payment acceptable to the Contracting Officer, and a proper invoice (as described in GSA Form 3517, General Clauses, 552.232-75, Prompt Payment) for the requested Tax Adjustment, including the calculation thereof. All such documents must be received by the Contracting Officer within 60 calendar days after the last date the Real Estate Tax payment is due from the Lessor to the Taxing Authority without payment of penalty or interest. FAILURE TO SUBMIT THE PROPER INVOICE AND EVIDENCE OF PAYMENT WITHIN SUCH TIME FRAME SHALL CONSTITUTE A WAIVER 6

OF THE LESSOR'S RIGHT TO RECEIVE A TAX ADJUSTMENT PURSUANT TO THIS CLAUSE FOR THE TAX YEAR AFFFECTED.

D. Tax Appeals:

If the Government occupies more than 50% of the Building by virtue of this and any other Government lease(s), the Government may, upon reasonable notice, direct the Lessor to initiate a tax appeal, or the Government may elect to contest the assessed valuation on its own behalf or jointly on behalf of Government and the Lessor. If the Government elects to contest the assessed valuation on its own behalf or on behalf of the Government and the Lessor, the Lessor shall cooperate fully with this effort, including, without limitation, furnishing to the Government information necessary to contest the assessed valuation in accordance with the filling requirements of the Taxing Authority, executing documents, providing documentary and testimonial evidence, and verifying the accuracy and completeness of records. If the Lessor initiates an appeal at the direction of the Government, the Government shall have the right to approve the selection of counsel who shall represent the Lessor with regard to such appeal, which approval shall not be unreasonably withheld, conditioned or delayed, and the Lessor shall be entitled to a credit in the amount of its reasonable expenses in pursuing the appeal.

4.3 OPERATING COSTS (AUG 2008)

SEE RIDER PARAGRAPH 14

- A. The base for the operating costs adjustment will be established during negotiations based upon ANSI/BOMA Office Area square feet.
 - Beginning with the second year of the lease and each year thereafter, the Government shall pay annual incremental
 adjusted rent for changes in costs for cleaning services, supplies, materials, maintenance, trash removal, landscaping,
 water, sewer charges, heating, electricity, and certain administrative expenses attributable to occupancy. Applicable costs
 listed on GSA Form 1217, Lessor's Annual Cost Statement, when negotiated and agreed upon, will be used to determine
 the base rate for operating costs adjustment.
 - 2. The amount of adjustment will be determined by multiplying the base rate by the annual percent of change in the Cost of Living Index. The percent change will be computed by comparing the index figure published for the month prior to the lease commencement date with the index figure published for the month prior which begins each successive 12-month period. For example, a lease which commences in June of 2005 would use the index published for May of 2005, and that figure would be compared with the index published for May of 2006, May of 2007, and so on, to determine the percent change. The Cost of Living Index will be measured by the Department of Labor revised Consumer Price Index for urban wage earners and clerical workers, U.S. city average, all items figure, (1982 to 1984 = 100) published by the Bureau of Labor Statistics. Payment will be made with the monthly installment of fixed rent. Rental adjustments will be effective on the anniversary date of the lease; however payment of the adjusted rental rate will become due on the first workday of the second month following the publication of the Cost of Living Index for the month prior to the commencement of each 12-month period.
 - In the event of any decreases in the Cost of Living Index occurring during the term of the occupancy under the lease, the rental amount will be reduced accordingly. The amount of such reductions will be determined in the same manner as increases in rent provided under this paragraph.
 - 4. The offer shall clearly state whether the rental is firm throughout the term of the lease or if it is subject to annual adjustment of operating costs as indicated above. If operating costs will be subject to adjustment, those costs shall be specified on GSA Form 1364, Proposal to Lease Space, referenced in this solicitation.
- B. If the Government exercises an option to extend the lease term at the same rate as that of the original term, the option price will be based on the adjustment during the original term. Annual adjustments will continue.

4.4 ADJUSTMENT FOR VACANT PREMISES, GSAR 552.270-16 (VARIATION) (DEC 2005) SEE RIDER PARAGRAPH 17

- A. If the Government fails to occupy any portion of the leased premises or vacates the premises in whole or in part prior to expiration of the term of the lease, the rental rate (i.e., the base for operating cost adjustments) will be reduced.
- B. The rate will be reduced by that portion of the costs per ANSI/BOMA Office Area square foot of operating expenses not required to maintain the space. This rate will be negotiated and incorporated into the lease. Said reduction shall occur after the Government gives 30 calendar days' prior notice to the Lessor and shall continue in effect until the Government occupies the vacant premises or the lease expires or is terminated.

4.5 NORMAL HOURS

Services, utilities, and maintenance shall be provided daily, extending 7:30 a.m. to 5:30 p.m. except Saturdays, Sundays, and federal holidays.

4.6 OVERTIME USAGE (AUG 2008)

SEE RIDER PARAGRAPH 15

A. The Government shall have access to the leased space at all times without additional payment, including the use, during other than normal hours, of necessary services and utilities such as elevators, toilets, lights, and electric power. There is no overtime charge or additional payment for cooling of specific rooms that require 24 hours per day, 7 days per week, 365 days per year cooling.

SFO No. 3NY0336

12

M Jusq & GOVERNMENT

- B. If heating or cooling is required on an overtime basis, such services will be ordered orally or in writing by the Contracting Officer or the GSA Buildings Manager, or a designated Tenant Agency official. When ordered, services shall be provided at the hourly rate established in the contract, which shall include all the Lessor's administrative costs. Costs for personal services shall only be included as authorized by the Government.
- C. When the cost of service is \$2,000 or less, the service may be ordered orally. An invoice shall be submitted to the official placing the order for certification and payment. Orders for services costing more than \$2,000 shall be placed using GSA Form 300, Order for Supplies or Services, or other approved service requisition procurement document. The two clauses from GSA Form 3517, General Clauses, 552.232-75, Prompt Payment, and 552.232-70, Invoice Requirements (Variation), apply to all orders for overtime services.
- D. All orders are subject to the terms and conditions of this lease. In the event of a conflict between an order and this lease, the lease shall control.
- E. Failure to submit a proper invoice within 120 days of providing overtime utilities shall constitute a waiver of the Lessor's right to receive any payment for such overtime utilities pursuant to this lease.

4.7 UTILITIES (AUG 2008)

The Lessor is responsible for providing all utilities necessary for base building and tenant operations and all associated costs are included as a part of the established rental rates.

4.8 JANITORIAL SERVICES (AUG 2008)

A. Cleaning shall be performed during tenant working hours.

B. SELECTION OF CLEANING PRODUCTS:

The Lessor shall make careful selection of janitorial cleaning products and equipment to:

- 1. use products that are packaged ecologically;
- use products and equipment considered environmentally beneficial and/or recycled products that are phosphate-free, non-corrosive, non-flammable, and fully biodegradable; and
- 3. minimize the use of harsh chemicals and the release of irritating fumes.
- Examples of acceptable products may be found www.gsa.gov/p2products.

C. SELECTION OF PAPER PRODUCTS:

The Lessor shall select paper and paper products (i.e., bathroom tissue and paper towels) with recycled content conforming to EPA's CPG.

- D. The Lessor shall maintain the leased premises, including outside areas, in a clean condition and shall provide supplies and equipment for the term of the lease. The following schedule describes the level of services intended. Performance will be based on the Contracting Officer's evaluation of results, not the frequency or method of performance.
 - 1. Daily. Empty trash receptacles. Sweep entrances, lobbies, and corridors. Spot sweep floors, and spot vacuum carpets. Clean drinking fountains. Sweep and damp mop or scrub toilet rooms. Clean all toilet fixtures, and replenish toilet supplies. Dispose of all trash and garbage generated in or about the building. Wash inside and out or steam clean cans used for collection of food remnants from snack bars and vending machines. Dust horizontal surfaces that are readily available and visibly require dusting. Spray buff resilient floors in main corridors, entrances, and lobbies. Clean elevators and escalators. Remove carpet stains. Police sidewalks, parking areas, and driveways. Sweep loading dock areas and platforms. Clean glass entry doors to the Government-demised area.
 - 2. Three Times a Week. Sweep or vacuum stairs.
 - Weekly. Damp mop and spray buff all resilient floors in toilets and health units. Sweep sidewalks, parking areas, and driveways (weather permitting).
 - 4. Every Two Weeks. Spray buff resilient floors in secondary corridors, entrance, and lobbies. Damp mop and spray buff hard and resilient floors in office space.
 - Monthly. Thoroughly dust furniture. Completely sweep and/or vacuum carpets. Sweep storage space. Spot clean all wall surfaces within 70 inches of the floor.
 - Every Two Months. Damp wipe toilet wastepaper receptacles, stall partitions, doors, window sills, and frames. Shampoo entrance and elevator carpets.
 - Three Times a Year. Dust wall surfaces within 70 inches of the floor, vertical surfaces and under surfaces. Clean metal and marble surfaces in lobbies. Wet mop or scrub garages.
 - 8. Twice a Year. Wash all interior and exterior windows and other glass surfaces. Strip and apply four coats of finish to resilient floors in toilets. Strip and refinish main corridors and other heavy traffic areas.

MIM & W.

- 9. Annually. Wash all venetian blinds, and dust 6 months from washing. Vacuum or dust all surfaces in the building of 70 inches from the floor, including light fixtures. Vacuum all draperies in place. Strip and refinish floors in offices and secondary lobbies and corridors. Shampoo carpets in corridors and lobbies. Clean balconies, ledges, courts, areaways, and flat roofs.
- 10. Every Two Years. Shampoo carpets in all offices and other non-public areas.
- 11. Every Five Years. Dry clean or wash (as appropriate) all draperies.
- 12. As Required. Properly maintain plants and lawns. Remove snow and ice from entrances, exterior walks, and parking lots of the building by the beginning of the normal working hours and continuing throughout the day. Provide initial supply, installation, and replacement of light bulbs, tubes, ballasts, and starters. Replace worn floor coverings (this includes the moving and returning of furnishings). Provide and empty exterior ash cans and clean area of any discarded cigarette butts.
- Control pests as appropriate, using Integrated Pest Management techniques, as specified in the GSA Environmental Management Integrated Pest Management Technique Guide (E402-1001).

4.9 SCHEDULE OF PERIODIC SERVICES (DEC 2005)

Within 60 days after occupancy by the Government, the Lessor shall provide to the Contracting Officer with a detailed written schedule of all periodic services and maintenance to be performed other than daily, weekly, or monthly.

4.10 LANDSCAPE MAINTENANCE (AUG 2008)

- A. Landscape maintenance shall be performed during the growing season at not less than a weekly cycle and shall consist of watering, weeding, mowing, and policing the area to keep it free of debris. Pruning and fertilization shall be done on an asneeded basis. In addition, dead, dying, or damaged plants shall be replaced.
- B. See additional information in the "Landscaping" paragraph in the GENERAL ARCHITECTURE section of this solicitation.

4.11 MAINTENANCE AND TESTING OF SYSTEMS (AUG 2008)

- A. The Lessor is responsible for the total maintenance and repair of the leased premises. Such maintenance and repairs include the site and private access roads. All equipment and systems shall be maintained to provide reliable, energy-efficient service without unusual interruption, disturbing noises, exposure to fire or safety hazards, uncomfortable drafts, excessive air velocities, or unusual emissions of dirt. The Lessor's maintenance responsibility includes initial supply and replacement of all supplies, materials, and equipment necessary for such maintenance. Maintenance, testing, and inspection of appropriate equipment and systems shall be done in accordance with current applicable codes, and inspection certificates shall be displayed as appropriate. Copies of all records in this regard shall be forwarded to the GSA Field Office Manager or a designated representative.
- B. Without any additional charge, the Government reserves the right to require documentation of proper operations or testing prior to occupancy of such systems as fire alarm, sprinkler, standpipes, fire pumps, emergency lighting, illuminated exit signs, emergency generator, etc. to ensure proper operation. These tests shall be witnessed by a designated representative of the Contracting Officer

4.12 NOVATION AND CHANGE OF NAME (AUG 2008)

- A. In the event of a transfer of ownership of the lease premises, an assignment of lease or a change in the Lessor's legal name, the Lessor must comply with the requirements of Subpart 42.12 of the Federal Acquisition Regulations (FAR).
- B. The Government and the Lessor may execute a Change of Name Agreement where only a change of the Lessor's name is involved and the Government's and the Lessor's rights and obligations remain unaffected. A sample form is found at FAR 42.1205
- C. The Government, the Lessor and the successor in interest may execute a Novation Agreement when the Lessor's rights or obligations under the lease are legally transferred.
- D. In addition to all documents required by Far 42.1204, the Contracting Officer may request additional information (i.e., copy of the deed, bill of sale, certificate of merger, contract, court decree, articles of incorporation, operation agreement, partnership certificate of good standing, etc.) from the transferor or transferee to validate the proposed changes.
- E. The transferee must submit a new GSA Form 3518, Representations and Certifications.
- F. Any separate agreement between the transferor and transferee regarding the assumption of liabilities shall be referenced specifically in the Novation Agreement.
- G. When it is in the best interest of the Government not to concur in the transfer of a contract from one entity to another, the original contractor remains under contractual obligation to the Government. The applicability of novation agreements is detailed at FAR 42.1204.
- H. When executed on behalf of the Government, a Novation Agreement will be made part of the lease via Supplemental Lease Agreement.

M TM & GOVERNMENT

SFO No. 3NY0336

- In the event of a change in ownership, rent will continue to be paid to the prior Lessor until the Supplemental Lease Agreement is
 executed by the Government. New Lessors must comply with all provisions of this Lease, including but not limited to, Central
 Contractor Registration and the provision of all information required by the Contracting Officer.
- J. Notwithstanding anything to the contrary in this Lease, the Government has no obligation to recognize a change of ownership or interest until (1) the payment of rent has commenced; and (2) any amounts due and owing to the Government hereunder have been paid in full or completely set off against this Lease.

4.13 CENTRAL CONTRACTOR REGISTRATION (AUG 2008)

The Offeror must have an active registration in the Central Contractor Registration (CCR) System (via the Internet at http://www.ccr.gov) prior to lease award and http://www.ccr.gov) pri

LESSOR & GOVERNMENT

SFO No. 3NY0336

5.0 DESIGN, CONSTRUCTION, AND OTHER POST AWARD ACTIVITIES

- 5.1 SAFEGUARDING AND DISSEMINATION OF SENSITIVE BUT UNCLASSIFIED (SBU) BUILDING INFORMATION (JUNE 2009)

 This paragraph applies to all recipients of SBU building information, including offerors, bidders, awardees, contractors, subcontractors, lessors, suppliers, and manufacturers.
 - A. MARKING SBU. Contractor-generated documents that contain building information must be reviewed by GSA to identify any SBU content, before the original or any copies are disseminated to any other parties. If SBU content is identified, the contracting officer may direct the contractor, as specified elsewhere in this contract, to imprint or affix SBU document markings to the original documents and all copies, before any dissemination.
 - B. AUTHORIZED RECIPIENTS. Building information considered SBU must be protected with access strictly controlled and limited to those individuals having a need to know such information. Those with a need to know may include Federal, State, and local government entities, and nongovernment entities engaged in the conduct of business on behalf of or with GSA. Nongovernment entities may include architects, engineers, consultants, contractors, subcontractors, suppliers, and others submitting an offer or bid to GSA or performing work under a GSA contract or subcontract. Contractors must provide SBU building information when needed for the performance of official Federal, State, and local government functions, such as for code compliance reviews and for the issuance of building permits. Public safety entities such as fire and utility departments may require access to SBU building information on a need to know basis. This clause must not prevent or encumber the dissemination of SBU building information to public safety entities.

C. DISSEMINATION OF SBU BUILDING INFORMATION:

- 1. BY ELECTRONIC TRANSMISSION. Electronic transmission of SBU information outside of the GSA firewall and network must use session (or alternatively file encryption). Sessions (or files) must be encrypted with an approved NIST algorithm, such as Advanced Encryption Standard (AES) or Triple Data Encryption Standard (3DES), in accordance with Federal Information Processing Standards Publication (FIPS PUB) 140-2, Security Requirements for Cryptographic Modules. Encryption tools that meet FIPS 140-2 are referenced on the NIST web page found at the following URL: http://CSRC.NIST.GOV/GROUPS/STM/CMVP/DOCUMENTS/140-1/1401VEND.HTM. All encryption products used to satisfy the FIPS 140-2 requirement should have a validation certificate that can be verified at the following URL: http://CSRC.NIST.GOV/GROUPS/STM/CMVP/VALIDATION.HTML#02. (Not all vendors of security products that claim conformance with FIPS 140-2 have validation certificates.) Contractors must provide SBU building information only to authorized representatives of State, Federal, and local government entities and firms currently registered as "active" in the Central Contractor Registration (CCR) database at www.ccr.gov that have a need to know such information. If a subcontractor is not registered in the CCR and has a need to possess SBU building information, the subcontractor shall provide to the contractor its DUNS number or its tax ID number and a copy of its business license.
- BY NON-ELECTRONIC FORM OR ON PORTABLE ELECTRONIC DATA STORAGE DEVICES. Portable electronic data storage devices include but are not limited to CDs, DVDs, and USB drives. Non-electronic forms of SBU building information include paper documents.
 - By mail. Utilize only methods of shipping that provide services for monitoring receipt such as track and confirm, proof of delivery, signature confirmation, or return receipt.
 - b. In person. Contractors must provide SBU building information only to authorized representatives of State, Federal, and local government entities and firms currently registered as "active" in the CCR database that have a need to know such information.
- 3. RECORD KEEPING. Contractors must maintain a list of the State, Federal, and local government entities and the firms to which SBU is disseminated under sections C1 and C2 of this clause. This list must include at a minimum (1) the name of the State, Federal, or local government entity or firm to which SBU has been disseminated; (2) the name of the individual at the entity or firm who is responsible for protecting the SBU building information, with access strictly controlled and limited to those individuals having a need to know such information; (3) contact information for the named individual; and (4) a description of the SBU building information provided. Once work is completed, or for leased space with the submission of the "as built" drawings, the contractor must collect all lists maintained in accordance with this clause, including those maintained by any subcontractors and/or suppliers, and submit them to the contracting officer. For federal buildings, final payment may be withheld until the lists are received.
- D. RETAINING SBU DOCUMENTS. SBU building information (both electronic and paper formats) must be protected, with access strictly controlled and limited to those individuals having a need to know such information.
- E. DESTROYING SBU BUILDING INFORMATION. SBU building information must be destroyed such that the marked information is rendered unreadable and incapable of being restored, or returned to the contracting officer, when no longer needed, in accordance with guidelines provided for media sanitization within Appendix A of NIST Special Publication 800-88, Guidelines for Media Sanitization, available at http://csrc.nist.gov/publications/ And NIST Special Publication 800-88, Guidelines for Media Sanitization, available at http://csrc.nist.gov/publications/ And NIST Special Publication 800-88, Guidelines for Sublication within a publication and information is not returned to the contracting officer, examples of acceptable destruction methods for SBU building information are burning or shredding hardcopy; physically destroying portable electronic storage devices such as CDs, DVDs, and USB drives; deleting and removing files from electronic recycling bins; and removing material from computer hard drives using a permanent-erase utility such as bit wiping software or disk crushers.
- F. NOTICE OF DISPOSAL. The contractor must notify the Contracting Officer that all SBU building information has been destroyed, or returned to the Contracting Officer, by the contractor and its subcontractors or suppliers in accordance with section (e) of this clause, with the exception of the contractor's record copy. This notice must be submitted to the contracting officer at the

MITTERSOR & GOVERNMENT

- completion of the contract in order to receive final payment. For leases, this notice must be submitted to the Contracting Officer at the completion of the lease term.
- G. INCIDENTS. All improper disclosures of SBU building information must be immediately reported to the contracting officer at Susan Walsh, GSA, 26 Federal Plaza, New York, NY 10278. If the contract provides for progress payments, the contracting officer may withhold approval of progress payments until the contractor provides a corrective action plan explaining how the contractor will prevent future improper disclosures of SBU building information. Progress payments may also be withheld for failure to comply with any provision in this clause until the contractor provides a corrective action plan explaining how the contractor will rectify any noncompliance and comply with the clause in the future.
- H. SUBCONTRACTS. The Contractor must insert the substance of this clause in all subcontracts.

5.2 TENANT IMPROVEMENTS PRICING REQUIREMENTS (AUG 2008)

- A. Under the provisions of FAR Subpart 15.4, the Lessor must submit information that is adequate for the Government to evaluate the reasonableness of the price or determining cost realism in conjunction with the Tenant Improvements.
- B. In lieu of submitting detailed cost or pricing data and entering into negotiations to determine a final cost for the subject work, the Government (in accordance with FAR 15.403) is willing to negotiate a price based upon the results of a competitive proposal process if the following conditions are met:
 - The Lessor shall submit to the Government a proposal including overhead, profit, and architectural-engineering fees, as well
 as permits and regulatory fees for all Tenant Improvements. The Lessor shall submit an A/E cost proposal to the
 Government and upon acceptance by the Government, the Government shall issue a Notice To Proceed to the Lessor for
 preparation of Construction Drawings.
 - The Tenant Improvements scope of work includes the lease, the SFO, all SFO attachments, the construction
 drawings/documents, and written specifications. In cases of discrepancies, the Lessor shall immediately notify the
 Contracting Officer for resolution. All differences will be resolved by the Contracting Officer in accordance with the terms
 and conditions of the lease.
 - 3. No building shell items shall be included in the pricing for the Tenant Improvements.
 - 4. Each proposal shall be 1) submitted in the attached 21 Division Tenant Improvement Cost Summary table by the proposed General Contractors (or subcontractors) and 2) reviewed by the Government. The General Contractors shall submit the supporting bids from the major subcontractors. The Government reserves the right to determine if bids meet the scope of work, that the price is reasonable, and that the Lessor's proposed contractors are qualified to perform the work. The Government reserves the right to reject all bids, at its sole discretion.
 - 5. A minimum of two qualified general contractors shall be invited to participate in the competitive proposal process. Each participant shall compete independently in the process. In the absence of sufficient competition from the general contractors, a minimum of two qualified subcontractors from each trade of the attached 21 Division Tenant Improvement Cost Summary table shall be invited to participate in the competitive proposal process.
 - The Government reserves the right to be represented at all negotiation sessions between the Lessor and potential contractors.
 - The Lessor shall demonstrate to the Government that best efforts have been made to obtain the most competitive prices possible, and the Lessor shall accept responsibility for all prices through direct contracts with all contractors.
 - 8. The Lessor shall complete the competition and the cost proposal process in the time frame specified in the "Construction Schedule of Tenant Improvements" paragraph in this section.
 - 9. Once the Government determines that there is adequate competition, and upon the Government's acceptance of the Lessor's cost proposal based upon that competition (provided the Lessor selects the competition's lowest priced bid of a contractor qualified to perform the subject work), the Contracting Officer shall issue to the Lessor a notice to proceed for the subject work.
 - The Lessor shall complete the work within the time frame requirements illustrated in the "Construction Schedule and Acceptance of Tenant Improvements" paragraph in this section.

5.3 SUBSEQUENT TENANT ALTERATIONS \$100,000 OR LESS (AUG 2008)

- A. The Lessor may be requested to provide alterations during the term of the lease. Alterations will be ordered by issuance of GSA Form 276, Supplemental Lease Agreement, GSA Form 300, Order for Supplies or Services, or a Tenant Agency-approved form when specifically authorized to do so by the Contracting Officer. The two clauses from GSA Form 3517, General Clauses, 552.232-75, Prompt Payment, and 552.232-70, Invoice Requirements (Variation), apply to orders for alterations. All orders are subject to the terms and conditions of this lease.
- B. Orders for Tenant Improvement \$100,000 or less may be placed by the Contracting Officer or GSA Buildings Manager. Tenant Agency officials may place orders for Tenant Improvements \$100,000 or less when specifically authorized to do so by the Contracting Officer. The Contracting Officer will provide the Lessor with a list of Tenant Agency officials authorized to place orders and will specify any limitations on the authority delegated to Tenant Agency officials. The Tenant Agency officials are not authorized to deal with the Lessor on any other matters.

MIM & SOVERNMENT

C. Payments for alterations ordered by the Tenant Agency under the authorization described in paragraph B above, will be made directly by the Tenant Agency placing the order.

5.4 WORK PERFORMANCE (SEP 2000)

All work in performance of this lease shall be done by skilled workers or mechanics and shall be acceptable to the Contracting Officer. The Contracting Officer retains the right to reject the Lessor's workers 1) if such are either unlicensed, unskilled, or otherwise incompetent, or 2) if such have demonstrated a history of either untimely or otherwise unacceptable performance in connection with work carried out in conjunction with either this contract or other Government or private contracts.

5.5 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (AUG 2008)

- A. The Lessor shall be responsible for the professional quality, technical accuracy, and the coordination of all designs, drawings, specifications, and other services furnished by the Lessor under this contract. The Lessor shall, without additional compensation, correct or revise any errors or deficiencies in its designs, drawings, specifications or other services.
- B. THE LESSOR REMAINS SOLELY RESPONSIBLE FOR DESIGNING, CONSTRUCTING, OPERATING, AND MAINTAINING THE LEASED PREMISES IN FULL ACCORDANCE WITH THE REQUIREMENTS OF THE LEASE. The Government retains the right to review and approve many aspects of the Lessor's design, including without limitation, review of the Lessor's design and construction drawings, shop drawings, product data, finish samples, and completed Base Building and Tenant Improvement construction. The Government shall work closely with the Lessor, in an integrated manner, to identify potential design flaws, to minimize costly misdirection of effort, and to assist the Lessor in its effort to monitor whether such design and construction comply with applicable laws and satisfy all Lease requirements.
- C. Neither the Government's review, approval or acceptance of, nor payment through rent of the services required under this contract, shall be construed to operate as a waiver of any rights under this contract or of any cause of action arising out of the performance of this contract, and the Lessor shall be and remain liable to the Government in accordance with applicable law for all damages to the Government caused by the Lessor's negligent performance of any of the services required under this contract.
- D. Design and construction and performance information is contained throughout several of the documents which will comprise a resulting lease. The Lessor shall provide to space planners, architects, engineers, construction contractors, etc., all information required whether it is found in this SFO, Special Requirements and Attachments, Price Lists or Design Intent Drawings. Reliance upon one of these documents to the exclusion of any other may result in an incomplete understanding of the scope of the work to be performed and/or services to be provided.

5.6 LIQUIDATED DAMAGES (AUG 2008)

In case of failure on the part of the Lessor to complete the work within the time fixed in the lease contract, the Lessor shall pay the Government as fixed and agreed liquidated damages, pursuant to this paragraph, the sum of one full day's rent for each and every calendar day that the delivery is delayed beyond the date specified for delivery of all the space ready for occupancy by the Government. This remedy is not exclusive and is in addition to any other remedies which may be available under this lease or at law. This liquidated sum is not meant as a penalty, but as an approximation of actual damages that would be suffered by the Government as a result of the Lessor's delay.

5.7 EXISTING FIT-OUT, SALVAGED, OR RE-USED BUILDING MATERIAL (SEP 2000)

- A. Items and materials existing in the offered space, or to be removed from the offered space during the demolition phase, are eligible for reuse in the construction phase of the project. The reuse of items and materials is preferable to recycling them; however, items considered for reuse shall be in refurbishable condition and shall meet the quality standards set forth by the Government in this SFO. In the absence of definitive quality standards, the Lessor is responsible to confirm that the quality of the item(s) in question shall meet or exceed accepted industry or trade standards for first quality commercial grade applications.
- B. The Lessor shall submit a reuse plan to the Contracting Officer. The Government will not pay for existing fixtures and other Tenant Improvements accepted in place. However, the Government will reimburse the Lessor, as part of the Tenant Improvement Allowance, the costs to repair or improve such fixtures or improvements identified on the reuse plan and approved by the Contracting Officer.

5.8 CONSTRUCTION WASTE MANAGEMENT (AUG 2008)

- A. Recycling construction waste is mandatory for initial space alterations for tenant improvements and subsequent alterations under the lease.
- B. Recycling construction waste means providing all services necessary to furnish construction materials or wastes to organizations which will employ these materials or wastes in the production of new materials. Recycling includes required labor and equipment necessary to separate individual materials from the assemblies of which they form a part.
- C. SUBMITTAL REQUIREMENT: Refer to the Green Lease Submittal Requirement paragraph in the How to Offer and Submittal Requirements Section of this SFO.
- D. The Lessor shall recycle the following items during both the demolition and construction phases of the project, subject to economic evaluation and feasibility:
 - 1. ceiling grid and tile;
 - 2. light fixtures, including proper disposal of any transformers, ballasts, and fluorescent light bu

& GOVERNMENT

- 3. duct work and HVAC equipment;
- 4. wiring and electrical equipment;
- aluminum and/or steel doors and frames;
- 6. hardware;
- 7. drywall;
- 8. steel studs:
- 9. carpet, carpet backing, and carpet padding;
- 10. wood:
- 11. insulation;
- 12. cardboard packaging;
- 13. pallets;
- 14. windows and glazing materials:
- 15. all miscellaneous metals (as in steel support frames for filing equipment); and
- 16. all other finish and construction materials.
- E. If any waste materials encountered during the demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCB's) (such as fluorescent lamp ballasts), or other harmful substances, they shall be handled and removed in accordance with federal and state laws and requirements concerning hazardous waste.
- F. In addition to providing "one time" removal and recycling of large scale demolition items such as carpeting or drywall, the Lessor shall provide continuous facilities for the recycling of incidental construction waste during the initial construction.
- G. Construction materials recycling records shall be maintained by the Lessor and shall be accessible to the Contracting Officer. Records shall include materials recycled or landfilled, quantity, date, and identification of hazardous wastes.

5.9 INDOOR AIR QUALITY DURING CONSTRUCTION (DEC 2007)

- A. The Lessor shall provide to the Government material safety data sheets (MSDS) or other appropriate documents upon request, but prior to installation or use for the following products including but not limited to: adhesives, caulking, sealants, insulating materials, fireproofing or fire stopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finishes for wood surfaces, janitorial cleaning products, and pest control products.
- B. The Contracting Officer may eliminate from consideration products with significant quantities of toxic, flammable, corrosive, or carcinogenic material and products with potential for harmful chemical emissions. Materials used often or in large quantities will receive the greatest amount of review.
- C. All MSDS shall comply with Occupational Safety and Health Administration (OSHA) requirements. The Lessor and its agents shall comply with all recommended measures in the MSDS to protect the health and safety of personnel.
- D. To the greatest extent possible, the Lessor shall sequence the installation of finish materials so that materials that are high emitters of volatile organic compounds (VOC) are installed and allowed to cure before installing interior finish materials, especially soft materials that are woven, fibrous, or porous in nature, that may adsorb contaminants and release them over time.
- E. Where demolition or construction work occurs adjacent to occupied space, the Lessor shall erect appropriate barriers (noise, dust, odor, etc.) and take necessary steps to minimize interference with the occupants. This includes maintaining acceptable temperature, humidity, and ventilation in the occupied areas during window removal, window replacement, or similar types of work.

F. FLUSH-OUT PROCEDURE:

- A final flush-out period of 72 hours minimum is required after installation of all interior finishes and before the tenant agency's occupancy of the space. The Lessor shall ventilate 24 hours a day, with new filtration media at 100% outdoor air (or maximum outdoor air while achieving a relative humidity not greater than 60%).
- 2. After the 3-day period the space may be occupied; however, the flush-out must continue for 30 days using the maximum percentage of outdoor air consistent with achieving thermal comfort and humidity control.
- 3. Any deviation from this ventilation plan must be approved by the Contracting Officer.
- G. The Lessor is required to provide regularly occupied areas of the tenant space with new air filtration media before occupancy that provides a Minimum Efficiency Reporting Value (MERV) of 13 or better.

LESSON & GOVERNMENT

- H. During construction, meet or exceed the recommended design approaches of the Sheet Metal and Air Conditioning National Contractors Association (SMACNA) IAQ Guideline for Occupied Buildings Under Construction, 1995, Chapter 3.
- Protect stored onsite and installed absorptive materials from moisture damage.
- J. If air handlers are used during construction, the Lessor shall provide filtration media with a Minimum Efficiency Reporting Value (MERV) of 8 at each return air grill, as determined by ASHRAE (American Society of Heating, Refrigeration and Air-Conditioning Engineers) 52.2-1999.

5.10 **CONSTRUCTION SCHEDULE (MAR 2007)**

- A. Within fifteen (15) days after award of the lease contract, the successful Offeror shall submit to the Contracting Officer a tentative construction schedule giving the dates on which the various phases of construction will be completed to coincide with the Government's required occupancy date. Refer to the "Occupancy Date" paragraph in the SUMMARY section of this SFO. The finalized schedule shall be submitted no later than thirty (30) days after award.
- B. The schedule shall include timing for completion of design and construction milestones including, but not limited to: 1) submittal of preliminary plans and specifications; 2) submittal of other working drawings; 3) issuance of a building permit; 4) completed construction documents; 5) start of construction; 6) completion of principal categories of work; 7) phased completion and availability for occupancy of each portion of the Government-demised area (by floor, block, or other appropriate category); and 8) final construction completion.

CONSTRUCTION SCHEDULE AND ACCEPTANCE OF TENANT IMPROVEMENTS (MAR 2007) 5.11

A. The construction schedule shall commence upon lease award, unless otherwise expressly agreed by the Lessor and Government as stated in the lease. The schedule shall be divided into six tasks for each phase. These are: 1) the generation of the design intent drawings;; 2) the Lessor's generation of the Government's construction documents;3) the Government's review of the construction documents; 4) the TI submittal, review and Notice to Proceed (NTP) process; 5) the Lessor's construction of the subject leased area; and 6) the Government's acceptance of the Lessor's construction. Each of these tasks is detailed below. References to "approval" shall mean such approval granted by the GSA Contracting Officer. During the construction schedule, the Government may request regularly scheduled progress meetings and request that the Lessor keep meeting minutes of discussion topics and attendance. During design and construction, the Lessor may discover instances where the Government's directives conflict. In such cases, the Lessor shall immediately notify the GSA Contracting Officer so that the Government may issue a determination as to how to proceed beyond the building shell.

The Government shall prepare and provide to the Lessor the Government's approved design intent drawings based upon the base building drawings provided by the Lessor as required in the "BUILDING AND SITE INFORMATION SUBMITTALS" paragraph of These design intent drawings will detail the Tenant Improvements to be made by the Lessor within the Government-demised area. Design intent drawings, for the purposes of this lease, are defined as fully-dimensioned drawings of the leased space which consist of enough information to prepare construction drawings including: 1) furniture, wall, door, and built-in millwork locations; telephone, electrical, and data outlet types and locations; and repositioned sprinklers, ceilings, and lighting, where impacted; 2) specifications necessary for calculation of electrical and HVAC loads; and 3) all finish and signage selections. Design intent drawings shall be due from the Government within twenty-five (25) working days from award.

WORKING/CONSTRUCTION DRAWINGS:

The Lessor shall prepare, as part of the Tenant Improvement Allowance, final working/construction drawings for the improvements illustrated on the Government-approved design intent drawings. The working/construction drawings shall include all mechanical, electrical, plumbing, fire safety, lighting, structural, and architectural improvements scheduled for inclusion into the Government-demised area. Working/construction drawings shall also be annotated with all applicable specifications. The resulting product shall reflect requirements which are substantially the same as that specified by the Government-approved design intent drawings and shall incorporate neither extraneous additions nor deletions of requirements. The Lessor's working/construction drawings shall be due to the Government within thirty five (35) working days of the Government's approval of the design intent drawings. Working/construction drawings shall clearly identify 1) Tenant Improvements already in place and 2) the work to be done by the Lessor or others.

D. REVIEW OF WORKING/CONSTRUCTION DRAWINGS:

The Government retains the right to review, and request modifications (if necessary) to, the Lessor's construction documents prior to the Lessor's commencement of interior construction. The Government's review of the construction documents is limited to the construction documents' conformance to the specific requirements of the SFO and to the approved design intent drawings. The Government shall perform all reviews of construction documents within ten (10) working days of receipt of such from the Lessor. Should the Government require that modifications be made to the Lessor's construction documents, the Government shall state such in writing to the Lessor, and the Lessor shall have ten (10) working days to cure all noted defects before returning the construction documents to the Government for a subsequent review. Upon complete Government review for conformance of the construction documents to the design intent drawings, the Lessor shall obtain the necessary permits. Notwithstanding the Government's review of the construction documents, the Lessor is solely responsible and liable for the technical accuracy of the construction documents in meeting all requirements and provisions of the lease and the Government-approved design intent drawings. The Lessor shall obtain the necessary permits and may commence construction of the shell space.

E. TENANT IMPROVEMENTS PRICE PROPOSAL

Within thirty (30) working days of Government review for conformance of the construction drawings, the Lessor must submit the written price proposal along with adequate cost and pricing data or the documentation of the competitive proposals (as described in the "Tenant Improvements Pricing Requirements" paragraph in this section) and for any costs or credits to the Government that are beyond the scope of the original SFO and its attachments. Any work shown on the construction documents that is building shell shall be clearly identified and priced as such. After negotiation and acceptance of the Tenant/Improvements price, A 1470336

NOTICE TO PROCEED SHALL BE TRANSMITTED TO THE LESSOR, and the Lessor shall commence construction of the Tenant Improvements.

F. CONSTRUCTION OF TENANT IMPROVEMENTS:

The Lessor shall construct all Tenant Improvements in accordance with 1) the Government reviewed working/construction drawings and 2) all terms and conditions of the SFO. The Lessor shall complete Tenant Improvements within one hundred and twenty (120) working days of receiving the notice to proceed from the Government. The Lessor shall furnish a detailed construction schedule (such as Critical Path Method) to the Government within 5 days of issuance of the notice to proceed. Such schedule shall also indicate the dates available for the Government contractors to install telephone/data lines or equipment. The Government reserves the right to access any space within the building during the conduct of interior construction for the purposes of performing inspections or for installing Government-furnished equipment. The Government shall coordinate with the Lessor the activity of Government contractors in order to minimize conflicts with, and disruption to, other contractors on site. Access shall not be denied to authorized Government officials including, but not limited to, Government contractors, subcontractors, or consultants acting on behalf of the Government with regard to this project.

G. ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY:

Ten (10) working days prior to the completion of interior construction, the Lessor shall issue written notice to the Government to inspect the space. The Government shall have five (5) working days to inspect and to either accept or reject the subject space.

- Substantially completed space will be accepted by the Government subject to the completion of minor punch list items (see
 the Definitions paragraph of GSA Form 3517, General Clauses). Space which is not substantially complete will not be
 accepted by the Government. Should the Government reject the Lessor's space as not substantially complete as defined
 herein, the Lessor shall immediately undertake remedial action and when ready shall issue a subsequent notice to inspect
 to the Government.
- 2. The Lessor shall provide a valid Certificate of Occupancy, issued by the local jurisdiction, for the intended use of the Government and shall maintain and operate the building in conformance with current local codes and ordinances. If the local jurisdiction does not issue Certificates of Occupancy, the Lessor shall obtain the services of a licensed fire protection engineer to verify the offered space meets all applicable local codes and ordinances to ensure an acceptable level of safety is provided.

H. RENT COMMENCEMENT:

The rent commencement date (for each increment) shall be the date that space acceptance is made by the Government. Any rental paid by the Government prior to actual occupancy shall be less the cost for services and utilities. In any event, the Government will not be required to accept space and commence rent prior to substantial completion.

I. LEASE COMMENCEMENT:

The Government shall issue GSA Form 276, Supplemental Lease Agreement, to establish the lease commencement date after the acceptance of all space, if different from the date previously established in the lease. In any case, the lease commencement date shall not be prior to the rent commencement date.

5.12 PROGRESS REPORTS (AUG 2008)

After start of construction, at the Government's discretion, the Lessor shall submit to the GSA Contracting Officer, written progress reports at intervals of thirty (30) days. Each report shall include information as to 1) percentage of the work completed by phase and trade; 2) a statement as to expected completion and occupancy date; 3) changes introduced into the work; and 4) general remarks on such items as material shortages, strikes, weather, etc. In addition, at the Government's discretion, the Lessor shall conduct meetings every two (2) week(s) to brief Government personnel and/or contractors regarding the progress of design and construction of the Government-demised area. The Lessor shall be responsible for taking and distributing minutes of these meetings, with review and approval by the GSA Contracting Officer. Such meetings shall be held at a location to be designated by the Government.

5.13 CONSTRUCTION INSPECTIONS (AUG 2008)

- A. Construction inspections will be made periodically by the Contracting Officer and/or designated technical representatives to review compliance with the SFO requirements and the final working drawings.
- B. Periodic reviews, witnessing of tests, and inspections by the Government are not to be interpreted as resulting in any approval of the Lessor's apparent progress toward meeting the Government's objectives but are intended to discover any information which the Contracting Officer may be able to call to the Lessor's attention to prevent costly misdirection of effort. The Lessor shall respond in writing to the GSA Contracting Officer regarding the Government's comments resulting from the subject reviews, test, and inspections. The Lessor shall remain completely responsible for designing, constructing, operating, and maintaining the building in full accordance with the requirements of this solicitation.

5.14 FLOOR PLANS AFTER OCCUPANCY (DEC 2005)

- A. Paper Medium: Within thirty (30) days after occupancy, as-built reproducible full floor plans, scaled at 1/8" = 1'-0", showing the space under lease, as well as corridors, stairways, and core areas, shall be provided to the Contracting Officer.
- B. Electronic Medium: Computer-Aided Design (CAD) files of as-built floor plans showing the space under lease, as well as corridors, stairways, and core areas, shall be provided to the Contracting Officer. The plans shall have been generated by a CAD program which is compatible with the latest release of AutoCAD. The required file extension is .DWG. Clean and purged files shall be submitted on CD-ROM. They shall be labeled with building name, address, list of drawing(s), date of the drawing(s), and Lessor's architect and phone number. The Lessor's operator shall demonstrate the submission on GSA equipment, if requested by the Contracting Officer.

LESSOR & GOVERNMENT

5.15 WAIVER OF RESTORATION (AUG 2008)

The Lessor hereby waives, releases and discharges, and forever relinquishes any right to make a claim against the Government for waste, damages, or restoration arising from or related to (a) the Government's normal and customary use of the leased premises during the term of the lease (including any extensions thereof), as well as (b) any initial or subsequent alteration to the leased premises, including cabling, or removal thereof, during the term of this lease (including any extensions thereof), where such alterations or removals are performed by the Lessor or by the Government with the Lessor's consent, which shall not be unreasonably withheld. The Government may, at its sole option, abandon property in the leased space following expiration of the Lease, in which case the property will become the property of the Lessor and the Government will be relieved of any liability in connection therewith.

5.16 SECURITY FOR NEW CONSTRUCTION

Intentionally omitted.

5.17 SEISMIC SAFETY FOR NEW CONSTRUCTION

Intentionally omitted.

5.18 FIRE PROTECTION FOR NEW CONSTRUCTION

Intentionally omitted.

5.19 CONSTRUCTION WASTE MANAGEMENT

- A. Recycling construction waste is mandatory for initial space alterations for tenant improvements and subsequent alterations under the lease.
- B. Recycling construction waste means providing all services necessary to furnish construction materials or wastes to organizations which will employ these materials or wastes in the production of new materials. Recycling includes required labor and equipment necessary to separate individual materials from the assemblies of which they form a part.
- C. SUBMITTAL REQUIREMENT: Refer to the Green Lease Submittal Requirement paragraph in the How to Offer and Submittal Requirements Section of this SFO.
- D. The Lessor shall recycle the following items during both the demolition and construction phases of the project, subject to economic evaluation and feasibility:
 - 1. ceiling grid and tile;
 - light fixtures, including proper disposal of any transformers, ballasts, and fluorescent light bulbs;
 - 3. duct work and HVAC equipment;
 - 4. wiring and electrical equipment;
 - 5. aluminum and/or steel doors and frames;
 - hardware;
 - 7. drywall;
 - 8. steel studs;
 - 9. carpet, carpet backing, and carpet padding;
 - 10. wood:
 - 11. insulation;
 - 12. cardboard packaging;
 - 13. pallets;
 - 14. windows and glazing materials;
 - 15. all miscellaneous metals (as in steel support frames for filing equipment); and
 - all other finish and construction materials.
- E. If any waste materials encountered during the demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCB's) (such as fluorescent lamp ballasts), or other harmful substances, they shall be handled and removed in accordance with federal and state laws and requirements concerning hazardous waste.

26

SFO No. 3NY0336

22

VI TM & SW.
LESSOR & GOVERNMENT

- F. In addition to providing "one time" removal and recycling of large scale demolition items such as carpeting or drywall, the Lessor shall provide continuous facilities for the recycling of incidental construction waste during the initial construction.
- G. Construction materials recycling records shall be maintained by the Lessor and shall be accessible to the Contracting Officer. Records shall include materials recycled or landfilled, quantity, date, and identification of hazardous wastes.

LESSOR & GOVERNMENT

6.0 GENERAL ARCHITECTURE

6.1 ACCESSIBILITY (FEB 2007)

The building, leased space, and areas serving the leased space shall be accessible to persons with disabilities in accordance with the Architectural Barriers Act Accessibility Standard (ABAAS), Appendices C and D to 36 CFR Part 1191 (ABA Chapters 1 and 2, and Chapters 3 through 10). To the extent the standard referenced in the preceding sentence conflicts with local accessibility requirements, the more stringent shall apply.

6.2 EXITS AND ACCESS (DEC 2007)

- A. Vestibules shall be provided at public entrances and exits wherever weather conditions and heat loss are important factors for consideration. In the event of negative air pressure conditions, provisions shall be made for equalizing air pressure.
- B. The Lessor shall provide permanent entryway systems (such as grilles or grates) to control dirt and particulates from entering the building at all primary exterior entryways.

6.3 DOORS: EXTERIOR (SEP 2000)

A. BUILDING SHELL:

- Exterior doors shall be provided at the Lessor's expense unless explicitly requested by the Government in addition to those
 provided by the Lessor. Exterior doors shall be weather-tight and shall open outward. Hinges, pivots, and pins shall be
 installed in a manner which prevents removal when the door is closed and locked.
- 2. These doors shall have a minimum clear opening of 32" clear wide x 80" high (per leaf). Doors shall be heavy-duty, flush, 1) hollow steel construction, 2) solid-core wood, or 3) insulated tempered glass. As a minimum requirement, hollow steel doors shall be fully insulated, flush, #16-gauge hollow steel. Solid-core wood doors and hollow steel doors shall be at least 1-3/4 inches thick. Door assemblies shall be of durable finish and shall have an aesthetically-pleasing appearance acceptable to the Contracting Officer. The opening dimensions and operations shall conform to the governing building, fire safety, accessibility for the disabled, and energy codes and/or requirements.

6.4 WINDOWS (AUG 2008)

- A. Office space shall have windows in each exterior bay unless waived by the Contracting Officer.
- B. All windows shall be weather-tight. Operable windows that open shall be equipped with locks. Off-street, ground level windows and those accessible from fire escapes, adjacent roofs, and other structures that can be opened must be fitted with a sturdy locking device. Windows accessible from fire escapes must be readily operable from the inside of the building.

6.5 WINDOW COVERINGS (DEC 2005)

A. Window Blinds. All exterior windows shall be equipped with window blinds in new or like new condition, which shall be provided as part of the Tenant Improvement Allowance. The blinds may be aluminum or plastic vertical blinds, horizontal blinds with aluminum slats of 1-inch width or less, solar fabric roller shades, or an equivalent product pre-approved by the Contracting Officer. The window blinds shall have non-corroding mechanisms and synthetic tapes. Color selection will be made by the Contracting Officer.

B. DRAPERIES:

If draperies are required, they shall be part of the Tenant Improvement Allowance and the following minimum specifications shall apply:

- Fabrics shall be lined with either white or off-white plain lining fabric suited to the drapery fabric weight. Draperies shall be floor-, apron-, or sill-length, as specified by the Government, and shall be wide enough to cover window and trim. Draperies shall be hung with drapery hooks on well-anchored heavy duty traverse rods. Traverse rods shall draw from the center, right, or left side.
- 2. Construction. Any draperies to be newly installed shall be made as follows:
 - fullness of 100 percent, including overlap, side hems, and necessary returns;
 - b. double headings of 4 inches turned over a 4-inch permanently finished stiffener;
 - c. doubled side hems of 1-1/2 inches; 4-inch doubled and blind stitched bottom hems;
 - d. three-fold pinch pleats;
 - e. safety stitched intermediate seams:
 - f. matched patterns;
 - g. tacked corners; and
 - no raw edges or exposed seams.

LESSOR & GOVERNMENT

Use of existing draperies must be approved by the Contracting Officer.

6.6 FLOORS AND FLOOR LOAD (SEP 2000)

- A. All adjoining floor areas shall be:
 - of a common level not varying more than 1/4 inch over a 10-foot horizontal run in accordance with the American Concrete Institute standards,
 - 2. non-slip, and,
 - 3. acceptable to the Contracting Officer.
- B. Underfloor surfaces shall be smooth and level. Office areas shall have a minimum live load capacity of 50 pounds per ANSI/BOMA Office Area square foot plus 20 pounds per ANSI/BOMA Office Area square foot for moveable partitions. Storage areas shall have a minimum live load capacity of 100 pounds per ANSI/BOMA Office Area square foot including moveable partitions. A report showing the floor load capacity, at no cost to the Government, by a registered professional engineer may be required. Calculations and structural drawings may also be required.

6.7 CEILINGS (SEP 2000)

- A. Ceilings shall be at least eight (8) feet, six (6) inches and no more than 12 feet, 0 inches measured from floor to the lowest obstruction. Areas with raised flooring shall maintain these ceiling height limitations above the finished raised flooring. Bulkheads and hanging or surface-mounted light fixtures which impede traffic ways shall be avoided. Ceilings shall be uniform in color and appearance throughout the leased space, with no obvious damage to tiles or grid.
- B. Prior to closing the ceiling, the Lessor shall coordinate with the Government for the installation of any items above the ceiling.
- C. Should the ceiling be installed in the Government-demised area prior to construction of the Tenant Improvements, then the Lessor shall be responsible for all costs in regard to the disassembly, storage during construction, and subsequent re-assembly of any of the ceiling components which may be required to complete the Tenant Improvements. The Lessor shall also bear the risk for any damage to the ceiling or any components thereof during the construction of the Tenant Improvements.
- D. Ceilings shall be a flat plane in each room and shall be suspended with ample light fixtures and finished as follows unless an alternate equivalent is pre-approved by the Contracting Officer:
 - 1. Restrooms. Plastered or spackled and taped gypsum board.
 - Offices and Conference Rooms. Mineral and acoustical tile or lay in panels with textured or patterned surface and tegular edges or an equivalent pre-approved by the Contracting Officer. Tiles or panels shall contain recycled content.
 - 3. Corridors and Eating/Galley Areas. Plastered or spackled and taped gypsum board or mineral acoustical tile.

6.8 ACOUSTICAL REQUIREMENTS (SEP 2000)

A. BUILDING SHELL:

- Reverberation Control. Private office and conference rooms using suspended acoustical ceilings shall have a noise reduction coefficient (NRC) of not less than 0.65 in accordance with ASTM C-423. Open office using suspended acoustical ceilings shall have an NRC of not less than 0.75. Private offices, conference rooms, and open offices using acoustical cloud or acoustical wall panels with a minimum of 70% coverage shall have an NRC of not less than 0.85.
- Ambient Noise Control. Ambient noise from mechanical equipment shall not exceed noise criteria curve (NC) 35 in accordance with the ASHRAE Handbook of Fundamentals in offices and conference rooms; NC 40 in corridors, cafeterias, lobbies, and toilets; NC 50 in other spaces.
- Noise Isolation. Rooms separated from adjacent spaces by ceiling-high partitions (not including doors) shall not be less than the following noise isolation class (NIC) standards when tested in accordance with ASTM E-336:

a. Conference rooms

NIC 40

b. Offices

NIC 35

4. *Testing*: The Contracting Officer may require, at no cost to the Government, test reports by a qualified acoustical consultant showing that acoustical requirements have been met.

6.9 PARTITIONS: GENERAL (DEC 2007)

BUILDING SHELL:

Partitions in public areas shall be marble, granite, hardwood, or sheetrock covered with durable wall covering or high performance coating, or equivalent pre-approved by the Contracting Officer.

MIM & W.
LESSOR & GOVERNMENT

6.10 PARTITIONS: PERMANENT (SEP 2000)

BUILDING SHELL:

Permanent partitions shall extend from the structural floor slab to the structural ceiling slab. They shall be provided by the Lessor as part of shell rent as necessary to surround the Government-demised area, stairs, corridors, elevator shafts, toilet rooms, all columns, and janitor closets. They shall have a flame spread rating of 25 or less and a smoke development rating of 50 or less (ASTM E-84). Stairs, elevators, and other floor openings shall be enclosed by partitions and shall have the fire resistance required by the applicable building code, fire code and ordinances adopted by the jurisdiction in which the building is located (such as the International Building Code, etc.) current as of the award date of this lease.

6.11 BUILDING DIRECTORY (DEC 2005)

BUILDING SHELL:

A tamper-proof directory with lock shall be provided in the building lobby listing the Government agency(ies). It must be acceptable to the Contracting Officer.

6.12 LANDSCAPING (SEP 2000)

- A. Where conditions permit, the site shall be landscaped for low maintenance and water conservation with plants that are either native or well-adapted to local growing conditions.
- B. Landscape management practices shall prevent pollution by:
 - 1. employing practices which avoid or minimize the need for fertilizers and pesticides;
 - 2. prohibiting the use of the 2,4-Dichlorophenoxyacetic Acid (2,4-D) herbicide and organophosphates; and
 - 3. composting/recycling all yard waste.
- C. The Lessor shall use landscaping products with recycled content as required by Environmental Protection Agency's (EPA's) Comprehensive Procurement Guidelines (CPG) for landscaping products. Refer to EPA's CPG web site, WWW.EPA.GOV/CPG.
- D. The Contracting Officer shall approve the landscaping to be provided.

6.13 FLAGPOLE AND DISPLAY (AUG 2008)

A. BUILDING SHELL:

- If the Government is the sole occupant of the building, a flag pole shall be provided at a location to be approved by the Contracting Officer. The flag will be provided by the Lessor, as part of shell rent, and replaced at all times during the lease term when showing signs of wear.
- 2. The Lessor shall be responsible for flag display on all workdays and federal holidays. The Lessor may light the flag in lieu of raising and lowering the flag daily. The Government will provide instructions when flags shall be flown at half-staff.

MIM & SW.
LESSOR & GOVERNMENT

SFO No. 3NY0336

7.0 ARCHITECTURAL FINISHES

7.1 RECYCLED CONTENT PRODUCTS (COMPREHENSIVE PROCUREMENT GUIDELINES) (SEP 2000)

- A. The Lessor shall comply to the extent feasible with the Resource Conservation and Recovery Act (RCRA), Section 6002, 1976. The Lessor shall use recycled content products as indicated in this SFO and as designated by the U.S. Environmental Protection Agency (EPA) in the Comprehensive Procurement Guidelines (CPG), 40 CFR Part 247, and its accompanying Recovered Materials Advisory Notice (RMAN). The CPG lists the designated recycled content products. EPA also provides recommended levels of recycled content for these products. The list of designated products, EPA's recommendations, and lists of manufacturers and suppliers of the products can be found at the WWW.EPA.GOV/CPG/PRODUCTS.HTM web site.
- B. The Offeror, if unable to comply with both the CPG and RMAN lists, shall submit a request for waiver for each material to the Contracting Officer with the Tenant Improvements pricing submittal. The request for waiver shall be based on the following criteria:
 - 1. the cost of the recommended product is unreasonable;
 - 2. inadequate competition exists;
 - 3. items are not available within a reasonable period of time; and
 - 4. items do not meet the SFO's performance standards.

7.2 ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS (DEC 2007)

- A. The Lessor shall use environmentally preferable products and materials. The Lessor is encouraged to consider the lifecycle analysis of the product in addition to the initial cost.
- B. Refer to EPA's environmentally preferable purchasing web site, www.epa.gov/epp and USDA BioPreferred products web site www.biobased.oce.usda.gov/fb4p/. In general, environmentally preferable products and materials do one or more of the following:
 - Contain recycled material, are biobased, are rapidly renewable (10-year or shorter growth cycle), or have other positive environmental attributes;
 - 2. Minimize the consumption of resources, energy, and water;
 - 3. Prevent the creation of solid waste, air pollution, or water pollution; or
 - 4. Promote the use of nontoxic substances and avoid toxic materials or processes.
- C. The Lessor is encouraged to use products that are extracted and manufactured regionally.

7.3 FINISH SELECTIONS (AUG 2008)

- A. All required finish option samples must be provided within ten (10) working days of the request for such by the Contracting Officer. GSA must deliver necessary finish selections to the Lessor within ten (10) working days after award or after receipt of plans and samples, whichever is later.
- B. All building finishes must be for first class, modern space.
- C. The Lessor must consult with the Contracting Officer prior to developing a minimum of three (3) finish options to include coordinated samples of finishes for all interior elements such as paint, wall coverings, base coving, carpet, window treatments, laminates, and flooring. All samples provided must be in compliance with specifications set forth elsewhere in this SFO. The Lessor must provide the required finish options within ten (10) working days of the request for such by the Contracting Officer. The finish options must be approved by GSA prior to installation. Upon review with the Tenant, the Contracting Officer must select one finish option within ten (10) working days, and unless otherwise specified prior to lease award, the Offeror may assume that one finish option will be accepted for all finishes in the entire space under lease. The Lessor may not make any substitutions after the finish option is selected.

7.4 WOOD PRODUCTS (AUG 2008)

- A. For all new installations of wood products, the Lessor is encouraged to use independently certified forest products. For information on certification and certified wood products, refer to the Forest Certification Resource Center (www.certifiedwood.org), the Forest Stewardship Council United States (www.fscus.org), or the Sustainable Forestry Initiative (www.aboutsfi.org).
- B. New installations of wood products used under this contract shall not contain wood from endangered wood species, as listed by the Convention on International Trade in Endangered Species. The list of species can be found at the following web site: www.cites.org/eng/resources/species.html
- C. Particle board, strawboard, and plywood materials shall comply with Department of Housing and Urban Development (HUD) standards for formaldehyde emission controls. Plywood materials shall not emit formaldehyde in excess of 0.2 parts per million (ppm), and particleboard materials shall not emit formaldehyde in excess of 0.3 ppm.

MIM & SW.

LESSOR & GOVERNMENT

D. All materials comprised of combustible substances, such as wood plywood and wood boards, shall be treated with fire retardant chemicals by a pressure impregnation process or other methods that treats the materials throughout as opposed to surface treatment.

7.5 ADHESIVES AND SEALANTS (AUG 2008)

All adhesives employed on this project (including, but not limited to, adhesives for carpet, carpet tile, plastic laminate, wall coverings, adhesives for wood, or sealants) shall be those with the lowest possible VOC content below 20 grams per liter and which meet the requirements of the manufacturer of the products adhered or involved. The Lessor shall use adhesives and sealants with no formaldehyde or heavy metals. Adhesives and other materials used for the installation of carpets shall be limited to those having a flash point of 140 degrees F or higher.

7.6 DOORS: SUITE ENTRY (AUG 2008)

TENANT IMPROVEMENT INFORMATION:

Suite entry doors shall be provided as part of the Tenant Improvements at the Government's expense and shall have a minimum clear opening of 32" wide x 84" high (per leaf). Doors shall meet the requirements of being a flush, solid-core, 1-3/4-inch thick, wood door with a natural wood veneer face or an equivalent pre-approved by the Contracting Officer. Hollow core wood doors are not acceptable. They shall be operable by a single effort; and shall meet the requirement of NFPA 101, *Life Safety Code* (current as of the award date of this Lease). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi-gloss oil-based paint finish with no formaldehyde.

7.7 DOORS: INTERIOR (AUG 2008)

TENANT IMPROVEMENT INFORMATION:

Doors within the Government-demised area shall be provided as part of the Tenant Improvements and shall have a minimum clear opening of 32" wide x 80" high. Doors shall be flush, solid-core, wood with a natural wood veneer face or an equivalent door pre-approved by the Contracting Officer. Hollow core wood doors are not acceptable. They shall be operable with a single effort, and shall meet the requirements of NFPA 101, *Life Safety Code* (current as of the award date of this lease). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semi-gloss oil-based paint with no formaldehyde.

7.8 DOORS: HARDWARE (DEC 2007)



7.9 DOORS: IDENTIFICATION (SEP 2000)

A. BUILDING SHELL:

All signage required in common areas unrelated to tenant identification shall be provided and installed by the Lessor.

B. TENANT IMPROVEMENT INFORMATION:

Door identification shall be installed in approved locations adjacent to office entrances as part of the Tenant Improvement Allowance. The form of door identification shall be approved by the Contracting Officer.

7.10 PARTITIONS: SUBDIVIDING (AUG 2008)

A. <u>BUILDING SHELL</u>:

Any demolition of existing improvements which is necessary to satisfy the Government's layout shall be done by the Lessor at the Lessor's expense.

B. TENANT IMPROVEMENT INFORMATION:

- 1. Office subdividing partitions shall comply with applicable building codes and local requirements and ordinances shall be provided as part of the Tenant Improvement Allowance. Partitioning shall extend from the finished floor to the finished ceiling and shall be designed to provide a minimum sound transmission class (STC) of 37. Partitioning shall be installed by the Lessor at locations to be determined by the Government as identified in the design intent drawings. They shall have a flame spread rating of 25 or less and a smoke development rating of 50 or less (ASTM E-84).
- 2. HVAC shall be rebalanced and lighting repositioned, as appropriate, after installation of partitions.

LESSOR & GOVERNMENT

SFO No. 3NY0336

- 3. If installed in accordance with the "Automatic Fire Sprinkler System" and "Fire Alarm System" paragraphs in the FIRE PROTECTION, LIFE SAFETY, AND ENVIRONMENTAL ISSUES section, sprinklers and fire alarm notification appliances shall be repositioned as appropriate after installation of partitions to maintain the level of fire protection and life safety.
- Partitioning requirements may be satisfied with existing partitions if they meet the Government's standards and layout requirements.

7.11 WALL FINISHES (AUG 2008)

A. BUILDING SHELL:

- 1. Physical Requirements.
 - a. Prior to occupancy, all restrooms within the building common areas of Government-occupied floors shall have 1) ceramic tile in splash areas and 2) semi gloss paint on remaining wall areas or other finish approved by the Contracting Officer.
 - b. Prior to occupancy, all elevator areas that access the Government-demised area and hallways accessing the Government-demised area shall be covered with wall coverings not less than 20 ounces per square yard, high performance paint or an equivalent.
- 2. Replacement. The Lessor must maintain all wall coverings, high-performance paint coatings, and paints in "like new" condition for the life of the lease. The Lessor, at its expense, must replace or repair paints, high-performance coatings, or wall coverings any time during the Government's occupancy if they are torn, peeling, permanently stained, marked, or damaged from impact. Repair or replace the ceramic tile in the restrooms if it is loose, chipped, broken, or permanently discolored. All repair and replacement work must occur after working hours.

B. TENANT IMPROVEMENT INFORMATION:

- 1. In the event the Government chooses to install a wall covering as part of the Tenant Improvement Allowance, the minimum standard is vinyl-free, chlorine-free, plasticizer-free wall covering with recycled content or biobased commercial wall covering weighing not less than 13 ounces per square yard or equivalent. In the event the Government chooses to install a high-performance paint coating, it shall comply with the VOC (Volatile Organic Compound) limits of the Green Seal Standard GS-11.
- 2. All wall covering in the Government-demised area shall be maintained in "like new" condition for the life of the lease. Repair or replacement of wall covering shall be at the Lessor's expense and shall include the moving and returning of furnishings, (except where wall covering has been damaged due to the negligence of the Government), any time during the occupancy by the Government if it is torn, peeling, or permanently stained. All repair and replacement work shall be done after working hours.

7.12 PAINTING (DEC 2007)

A. BUILDING SHELL:

- The Lessor shall bear the expense for all painting associated with the building shell. These areas shall include all common areas. Exterior perimeter walls and interior core walls within the Government demised area shall be spackled and prime painted with low VOC primer. If any building shell areas are already painted prior to Tenant Improvements, then the Lessor shall repaint, at the Lessor's expense, as necessary during Tenant Improvements.
- 2. Public areas shall be painted at least every 3 years.
- 3. If the Government desires cyclical repainting within the demised tenant spaces during the term of the lease, the Lessor shall include the cost within shell rent. Cyclical repainting of demised tenant spaces shall occur every three (3) years of occupancy. This cost, including the moving and returning of furnishings, as well as disassembly and reassembly of systems furniture, will be borne by the Lessor as part of the shell rent.

B. TENANT IMPROVEMENT INFORMATION:

- Prior to occupancy, all surfaces within the Government-demised area which are designated by GSA for painting shall be newly finished in colors acceptable to GSA.
- The Lessor shall provide interior paints and coatings that meet or are equivalent to the following standards for Volatile Organic Compound (VOC) offgassing:
 - a. Topcoat paints: Green Seal Standard GS-11, Paints, First Edition, May 20, 1993.
 - All other architectural coatings, primers, and undercoats: South Coast Air Quality Management District (SCAQMD) Rule 1113, Architectural Coatings, effective January 1, 2004.
 - Architectural paints, coatings, and primers applied to interior walls and ceilings:
 - i. Flats: 50 grams per litre (g/L).
 - ii. Non-flats: 150 g/L.
 - d. Anticorrosive and antirust paints applied to interior ferrous metal substrates: 250 g/L.
 - e. Clear wood finishes:
 - i. Varnish: 350 g/L.

LESSOR GOVERNMENT

- ii. Lacquer: 550 g/L.
- f. Floor coatings: 100 g/L
- g. Sealers:
 - i. Waterproofing sealers: 250 g/L.
 - ii. Sanding sealers: 275 g/L.
 - iii. All other sealers: 200 g/L.
- h. Shellacs:
 - i. Clear: 730 g/L.
 - ii. Pigmented: 550 g/L.
- i. Stains: 250 g/L.
- j. Use reprocessed latex paint in accordance with EPA's CPG (Comprehensive Procurement Guidelines) on all painted surfaces where feasible. The type of paint shall be acceptable to the Contracting Officer.
- 3. Painted surfaces shall be repainted at the Lessor's expense, including the moving and returning of furnishings, any time during the occupancy by the Government if it is peeling or permanently stained, except where damaged due to the negligence of the Government. All work shall be done after normal working hours as defined elsewhere in this SFO.

7.13 FLOOR COVERING AND PERIMETERS (AUG 2008)

A. BUILDING SHELL:

- Exposed interior floors in primary entrances and lobbies shall be marble, granite or terrazzo. Exposed interior floors in secondary entrances, elevator lobbies, and primary interior corridors shall be high-grade carpet, marble, granite, or terrazzo. Resilient flooring shall be used in telecommunications rooms. Floor perimeters at partitions shall have wood, rubber, vinyl, marble or carpet base.
- 2. Terrazzo, unglazed ceramic tile, recycled glass tile, and/or quarry tile shall be used in all toilet and service areas.
- 3. Any alternate flooring must be pre-approved by the Contracting Officer.
- 4. In addition to the building shell flooring discussed above, the Government-demised areas which are designated by GSA for cyclic carpet replacement shall be recarpeted every five (5) years with a product meeting this solicitation's requirements. This cost, including the moving and returning of furnishings, including disassembly and reassembly of systems furniture, will be borne by the Lessor as part of the shell rent.

B. TENANT IMPROVEMENT INFORMATION:

- Floor covering shall be either carpet or resilient flooring, as specified in the Government's approved design intent drawings.
 Floor perimeters at partitions shall have wood, rubber, vinyl or carpet base.
- The use of existing carpet may be approved by the Contracting Officer; however, existing carpet shall be repaired, stretched, and cleaned before occupancy and shall meet the static buildup requirement for new carpet.
- If the Government requires restrooms and/or shower rooms in the Government-demised area, floor covering shall be terrazzo, unglazed ceramic tile, and/or quarry tile.
- 4. Any alternate flooring shall be pre-approved by the Contracting Officer.

C. INSTALLATION:

Floor covering shall be installed in accordance with manufacturing instructions to lay smoothly and evenly.

D. FLOORING - REPAIR OR REPLACEMENT:

- Except when damaged by the Government, the Lessor shall repair or replace flooring as part of shell rent at any time during the lease term when:
 - backing or underlayment is exposed:
 - b. there are noticeable variations in surface color or texture;
 - c. it has curls, upturned edges, or other noticeable variations in texture,
 - d. tiles are loose, or
 - e. tears and/or tripping hazards are present.
- Repair or replacement shall include the moving and returning of furnishings, including disassembly and reassembly of systems furniture, if necessary. Work shall be performed after normal working hours as defined elsewhere in this SFO.

MAMA SOVERNMENT

7.14 CARPET: BROADLOOM (AUG 2008)

- A. Any carpet to be newly installed pursuant to this paragraph or replaced during the life of the lease shall meet the following specifications:
 - Pile Yarn Content. Pile yarn content shall be staple filament or continuous filament premium grade nylon branded by a major fiber producer [e.g., Invista, Solutia, Shaw, Honeywell].
 - Environmental Requirements. The Lessor shall use carpet that meets the "Green Label Plus" requirements of the Carpet
 and Rug Institute unless an exception is granted by the Contracting Officer. Refer to EPA's environmentally preferable
 purchasing web site, <u>WWW.EPA.GOV/EPP.</u>
 - 3. Carpet Pile Construction. Carpet pile shall be level loop, textured loop, level cut pile, or level cut/uncut pile.
 - 4. Pile Weight. Pile weight shall be a minimum of 28 oz/ square yard for level loop or textured loop construction. Pile weight shall be a minimum weight of 30 oz/square yard for level cut/uncut construction.
 - 5. Secondary Back. The secondary back shall be made from 100% synthetic fibers for glue-down installation.
 - 6. Density. The density shall be a minimum of 5,000 oz/ cubic yard.
 - Pile Height. The maximum pile height shall be 1/2 inch (13 mm). Exposed edges of carpet shall be fastened to floor surfaces and shall have trim along the entire length of the exposed edge.
 - 8. Static Buildup. Static buildup shall be a maximum of 3.5 KV when tested in accordance with AATCC-134.
 - Flammability: Carpet shall meet the flammability requirements of ASTE E-648 Test Method for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source.
 - 10. Carpet Reclamation. Where possible and required by law, dispose of any carpet replaced during the life of the lease from the site to a carpet recycling program or participate in a carpet buyback program. When carpet is replaced, submit documentation of carpet reclamation to the GSA Contracting Officer.

7.15 CARPET TILE (AUG 2008)

- A. Any carpet to be newly installed pursuant to this paragraph shall meet the following specifications:
 - Pile Yarn Content. Pile Yarn Content. Pile yarn content shall be staple filament or continuous filament premium branded nylon branded by a major fiber producer [e.g., Invista (formerly DuPont), Solutia (formerly Monsanto), Shaw, and Honeywell (formerly BASF).
 - Environmental Requirements. The Lessor shall use carpet tiles that meet the "Green Label Plus" requirements of the
 Carpet and Rug Institute unless an exception is granted by the Contracting Officer. Refer to the EPA's environmentally
 preferable purchasing web site, www.epa.gov/epp.
 - 3. Carpet Pile Construction. Carpet pile shall be level loop, textured loop, level cut pile, or level cut/uncut pile.
 - 4. Pile Weight. Pile weight shall be a minimum of 20 oz/square yard for level loop or textured loop construction. Pile weight shall be a minimum weight of 30 oz/yd2 for level cut/uncut construction.
 - Secondary Back. The secondary backing shall be PVC free made from Polyurethane hardback, Thermoplastic Polyolefin Composite, Ethylene Vinyl Acetate-EVA, Polyurethane Cushion, or Olefin hardback reinforced with fiberglass.
 - 6. Total Weight. Total weight shall be a minimum of 90 oz/ square yard.
 - 7. Density. The density shall be a minimum of 5,000 oz/cubic yard.
 - Pile Height. The minimum pile height shall be 1/8 inch. The combined thickness of the total product shall not exceed 1/2 inch (13 mm).
 - 9. Static Buildup. Static buildup shall be a maximum of 3.5 kilovolt, when tested in accordance with AATCC 134.
 - Flammability: Carpet shall meet the flammability requirements of ASTE E-648 Test Method for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source.
 - 11. Carpet Construction. Carpet construction shall be a minimum of 64 tufts per square inch.
 - Carpet Reclamation. Dispose of any carpet replaced during the life of the lease from the site to a carpet recycling program
 or participate in a carpet buyback program. When carpet is replaced, submit documentation of carpet reclamation to GSA.

7.16 ENVIRONMENTALLY PREFERABLE BUILDING PRODUCTS AND MATERIALS

A. The Lessor shall use environmentally preferable products and materials. The Lessor is encouraged to consider the lifecycle analysis of the product in addition to the initial cost.

SFO No. 3NY0336

- B. Refer to EPA's environmentally preferable purchasing web site, www.epa.gov/epp and USDA BioPreferred products web site www.biobased.oce.usda.gov/fb4p/. In general, environmentally preferable products and materials do one or more of the following:
 - Contain recycled material, are biobased, are rapidly renewable (10-year or shorter growth cycle), or have other positive environmental attributes;
 - 2. Minimize the consumption of resources, energy, and water;
 - 3. Prevent the creation of solid waste, air pollution, or water pollution; or
 - 4. Promote the use of nontoxic substances and avoid toxic materials or processes.
- C. The Lessor is encouraged to use products that are extracted and manufactured regionally.

MIM Sui LESSOR GOVERNMENT

8.0 MECHANICAL, ELECTRICAL, PLUMBING

8.1 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (AUG 2008)

A. BUILDING SHELL:

The Lessor shall provide and operate all building equipment and systems in accordance with applicable technical publications, manuals, and standard procedures. Mains, lines, and meters for utilities shall be provided by the Lessor. Exposed ducts, piping, and conduits are not permitted in office space.

B. SYSTEMS COMMISSIONING:

The Lessor shall incorporate commissioning requirements to verify that the installation and performance of energy consuming systems meet the Government's project requirements. The commissioning shall cover only work associated with tenant improvements or alterations or at a minimum: heating, ventilating, air conditioning and refrigeration (HVAC&R) systems and associated controls, lighting controls, and domestic hot water systems.

C. TENANT IMPROVEMENT INFORMATION:

The Lessor shall provide and operate all equipment and systems installed as Tenant Improvements in accordance with applicable codes, technical publications, manuals, and standard procedures.

8.2 BUILDING SYSTEMS (AUG 2008)

Whenever requested, the Lessor shall furnish to GSA as part of shell rent, a report by a registered professional engineer(s) showing that the building and its systems as designed and constructed will satisfy the requirements of this lease.

8.3 ENERGY COST SAVINGS (AUG 2008)

- A. For existing buildings, the Offeror is encouraged to use 1) Energy Savings Performance Contracts (ESPC) or 2) utility agreements to achieve, maintain, and/or exceed the ENERGY STAR Benchmark Score of 75. The Offeror is encouraged to include shared savings in the offer as a result of energy upgrades where applicable. ENERGY STAR tools and resources can be found at the www.energystar.gov web site.
- B. The Offeror may obtain a list of energy service companies qualified under the Energy Policy Act to perform ESPC, as well as additional information on cost-effective energy efficiency, renewables, and water conservation. For the ESPC qualified list, refer to the www.eere.energy.gov/femp web site, or call the FEMP Help Desk at 1-877-337-3463.
- C. Incandescent bulbs shall not be used. Where it is not feasible to eliminate incandescent bulbs, exceptions must be approved by the Contracting Officer.
- D. The Offeror is encouraged to purchase at least 50% of the Government tenant's electricity from renewable sources.

E. SUBMITTAL REQUIREMENT:

If renewable source power is purchased, provide documentation to the Contracting Officer within 9 months of occupancy.

8.4 INSULATION: THERMAL, ACOUSTIC, AND HVAC (AUG 2008)

- A. All insulation products shall contain recovered materials as required by EPA's CPG and related recycled content recommendations.
- B. No insulation installed with this project shall be material manufactured using chlorofluorocarbons (CFC's), nor shall CFC's be used in the installation of the product.
- C. All insulation containing fibrous materials exposed to air flow shall be rated for that exposure or shall be encapsulated.
- Insulating properties for all materials shall meet or exceed applicable industry standards. Polystyrene products shall meet American Society for Testing and Materials (ASTM) C578 91.
- E. All insulation shall be low emitting with not greater than .05 ppm formaldehyde emissions.
- F. The maximum flame spread and smoke developed index for insulation shall meet the requirements of the applicable local codes and ordinances (current as of the award date of this Lease) adopted by the jurisdiction in which the building is located.

8.5 DRINKING FOUNTAINS (AUG 2008)

A. BUILDING SHELL:

The Lessor shall provide, on each floor of Government occupied space, a minimum of one chilled accessible drinking fountain with potable water within every 200 feet of travel.

8.6 TOILET ROOMS (AUG 2008)

A. <u>BUILDING SHELL</u>:

1. Separate toilet facilities for men and women shall be provided on each floor occupied by the Government in the building. The facilities shall be located so that employees will not be required to travel more than 200 feet, on one floor to reach the toilets. Each toilet room shall have sufficient water closets enclosed with modern stall partitions and doors, urinals (in men's room), and hot (set in accordance with applicable building codes) and cold water. Water closets and urinals shall not be visible when the exterior door is open.

GOVERNMENT

SFO No. 3NY0336

- 2. Each main toilet room shall contain the following:
 - a mirror and shelf above the lavatory;
 - a toilet paper dispenser in each water closet stall, that will hold at least two rolls and allow easy, unrestricted dispensing;
 - c. a coat hook on the inside face of the door to each water closet stall and on several wall locations by the lavatories;
 - at least one modern paper towel dispenser, soap dispenser, and waste receptacle for every two lavatories;
 - e. a coin-operated sanitary napkin dispenser in women's toilet rooms with a waste receptacle in each water closet stall;
 - f. ceramic tile, recycled glass tile, or comparable wainscot from the floor to a minimum height of 4 feet, 6 inches;
 - g. a disposable toilet seat cover dispenser; and
 - h. a counter area of at least 2 feet, 0 inches in length, exclusive of the lavatories (however, it may be attached to the lavatories) with a mirror above and a ground fault interrupt-type convenience outlet located adjacent to the counter area. The counter should be installed to minimize pooling or spilling of water at the front edge.
 - i. a floor drain.
- B. If newly installed, toilet partitions shall be made from recovered materials as listed in EPA's CPG.

8.7 TOILET ROOMS: FIXTURE SCHEDULE (SEP 2000)

A. <u>BUILDING SHELL</u>:

- The toilet fixture schedule specified below shall be applied to each full floor based on one person for each 135 ANSI/BOMA
 Office Area square feet of office space in a ratio of forty percent (40%) men and sixty percent (60%) women.
- 2. Refer to the schedule separately for each sex.

| NUMBER OF MEN*/WOMEN | | | | WATER CLOSETS | | | | LAVATORIES | | | |
|-------------------------|-----------------|---------------|------------|---------------|--|---------------|--------|------------|----------------|---------|--|
| \$4. ° | 1 | • 13a. | 15 | | | 1 | 1 28 T | | diad | 1 | |
| | 16 36 | - <u>-</u> | 35 55 | | | 2 3 | | | 1 Uses 1247 | 2 3 | |
| | 56 61 | - E & | 60 80 | 373) Sec. | | 4 | | 48 18 | | 3 4 | |
| K | 81 91 | - - - | 90 | | | 5 5 | | | | 4 5 | |
| | 111 126 > | - - 150 | 125 150 | | | 6 6 *** | | | 6 1890 ° . | 5 ** | |

- In men's facilities, urinals may be substituted for 1/3 of the water closets specified.
- Add one lavatory for each 45 additional employees over 125.
- Add one water closet for each 40 additional employees over 150.

3. For new installations:

- Water closets shall not use more than 1.6 gallons per flush.
- b. Urinals shall not use more than 1.0 gallons per flush. Waterless urinals are acceptable.
- c. Faucets shall not use more than 2.5 gallons per minute at a flowing water pressure of 80 pounds per square inch.

8.8 JANITOR CLOSETS (DEC 2007)

A. BUILDING SHELL:

 Janitor closets with service sink, hot and cold water, and ample storage for cleaning equipment, materials, and supplies shall be provided on all floors. Each janitor closet door shall be fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch.

GOVERNMENT

SFO No. 3NY0336

- When not addressed by local code, provide containment drains plumbed for appropriate disposal of liquid wastes in spaces where water and chemical concentrate mixing occurs for maintenance purposes. Disposal is not permitted in restrooms.
- Refer to the "Indoor Air Quality for Ventilation Requirements" paragraph in the SAFETY AND ENVIRONMENTAL MANAGEMENT section of this Solicitation for Offers (SFO).

8.9 HEATING AND AIR CONDITIONING (AUG 2008)

A. BUILDING SHELL:

- 1. Temperatures shall conform to local commercial equivalent temperature levels and operating practices in order to maximize tenant satisfaction. These temperatures shall be maintained throughout the leased premises and service areas, regardless of outside temperatures, during the hours of operation specified in the lease. The Lessor shall perform any necessary systems start-up required to meet the commercially equivalent temperature levels prior to the first hour of each day's operation. At all times, humidity shall be maintained below 60% relative humidity.
- 2. During non working hours, heating temperatures shall be set no higher than 55° Fahrenheit, and air conditioning shall not be provided except as necessary to return space temperatures to a suitable level for the beginning of working hours. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the GSA Field Office Manager.
- 3. Simultaneous heating and cooling are not permitted.
- Areas having excessive heat gain or heat loss, or affected by solar radiation at different times of the day, shall be independently controlled.
- Equipment Performance. Temperature control for office spaces shall be provided by concealed central heating and air conditioning equipment. The equipment shall maintain space temperature control over a range of internal load fluctuations of plus 0.5 W/sq. ft. to minus 1.5 W/sq. ft. from initial design requirements of the tenant.
- HVAC Use During Construction. The permanent HVAC system may be used to move both supply and return air during the construction process only if the following conditions are met:
 - a. a complete air filtration system with 60 percent efficiency filters is installed and properly maintained;
 - b. no permanent diffusers are used;
 - c. no plenum type return air system is employed;
 - d. the HVAC duct system is adequately sealed to prevent the spread of airborne particulate and other contaminants; and
 - following the building "flush out," all duct systems are vacuumed with portable high-efficiency particulate arrestance (HEPA) vacuums and documented clean in accordance with National Air Duct Cleaners Association (NADCA) specifications.
- 7. Ductwork Re-use and Cleaning. Any ductwork to be reused and/or to remain in place shall be cleaned, tested, and demonstrated to be clean in accordance with the standards set forth by NADCA. The cleaning, testing, and demonstration shall occur immediately prior to Government occupancy to avoid contamination from construction dust and other airborne particulates.
- The Lessor shall conduct HVAC system balancing after any HVAC system alterations during the term of the lease and shall make a reasonable attempt to schedule major construction outside of office hours.
- 9. Normal HVAC systems maintenance shall not disrupt tenant operations.
- Thermal Comfort. During all working hours, comply with ASHRAE Standard 55-2004, Thermal Comfort Conditions for Human Occupancy.

B. TENANT IMPROVEMENT INFORMATION:

1. Zone Control. Provide individual thermostat control for office space with control areas not to exceed 1,500 ANSI/BOMA office area square feet. Interior spaces must be separately zoned. Specialty occupancies (conference rooms, kitchens, etc.) must have active controls capable of sensing space use and modulating HVAC system in response to space demand. Areas that routinely have extended hours of operation shall be environmentally controlled through dedicated heating and air conditioning equipment. Special purpose areas (such as photocopy centers, large conference rooms, computer rooms, etc.) with an internal cooling load in excess of 5 tons shall be independently controlled. Provide concealed package air conditioning equipment to meet localized spot cooling of tenant special equipment. Portable space heaters are prohibited.

8.10 VENTILATION (AUG 2008)

A. BUILDING SHELL:

 During working hours in periods of heating and cooling, ventilation shall be provided in accordance with the latest edition of ANSI/ASHRAE Standard 62.1, Ventilation for Acceptable Indoor Air Quality.

MIM & J.W. GOVERNMENT

SFO No. 3NY0336

- Air filtration shall be provided and maintained with filters having a minimum efficiency rating as determined by ANSI/ASHRAE Standard 52.2, Method of Testing General Ventilation Air Cleaning Devices for Removal Efficiency by Particle Size. Pre-filters shall have a MERV efficiency of 8. Final filters shall have an MERV efficiency of 13.
- Toilet rooms shall be properly exhausted, with a minimum of 10 air changes per hour.

8.11 ELECTRICAL: GENERAL (SEP 2000)

The Lessor shall be responsible for meeting the applicable requirements of local codes and ordinances. When codes conflict, the more stringent standard shall apply. Main service facilities shall be enclosed. The enclosure may not be used for storage or other purposes and shall have door(s) fitted with an automatic deadlocking latch bolt with a minimum throw of 1/2 inch. Distribution panels shall be circuit breaker type with 10 percent spare power load and circuits.

8.12 ELECTRICAL: DISTRIBUTION (AUG 2008)

A. BUILDING SHELL:

- 1. Main power distribution switchboards and distribution and lighting panel boards shall be circuit breaker type with copper buses that are properly rated to provide the calculated fault circuits. All power distribution panel boards shall be supplied with separate equipment ground buses. All power distribution equipment shall be required to handle the actual specified and projected loads plus 10 percent spare load capacity. Distribution panels are required to accommodate circuit breakers for the actual calculated needs plus 10 percent spare circuits that will be equivalent to the majority of other circuit breakers in the panel system. All floors shall have 120/208 V, 3-phase, 4-wire with bond, 60 hertz electric service available.
- Main distribution for standard office occupancy shall be provided at the Lessor's expense. In no event shall such power distribution (not including lighting and HVAC) for the Government-demised area fall below 7 W per ANSI/BOMA Office Area square foot.
- Convenience outlets shall be installed in accordance with NFPA Standard 70, National Electrical Code, or local code, whichever is more stringent.
- 4. The Lessor shall provide duplex utility outlets in toilet rooms, corridors, and dispensing areas. Fuses and circuit breakers shall be plainly marked or labeled to identify circuits or equipment supplied through them.

B. TENANT IMPROVEMENT INFORMATION:

- All electrical, telephone, and data outlets within the Government-demised area shall be installed by the Lessor in accordance with the design intent drawings. All electrical outlets shall be installed in accordance with NFPA Standard 70, or local code, whichever is more stringent.
- All tenant outlets shall be marked and coded for ease of wire tracing; outlets shall be circuited separately from lighting. All floor outlets shall be flush with the plane of the finished floor. Outlet cover colors shall be coordinated with partition finish selections.
- The Lessor shall in all cases safely conceal outlets and associated wiring (for electricity, voice, and data) to the
 workstation(s) shall be safely concealed in partitions, ceiling plenums, in recessed floor ducts, under raised flooring, or by
 use of a method acceptable to the Contracting Officer.

8.13 TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)

A. BUILDING SHELL:

- 1. Sufficient space shall be provided on the floor(s) where the Government occupies space for the purposes of terminating telecommunications service into the building. The building's telecommunications closets located on all floors shall be vertically-stacked. Telecommunications switchrooms, wire closets, and related spaces shall be enclosed. The enclosure shall not be used for storage or other purposes and shall have door(s) fitted with an automatic door-closer and deadlocking latch bolt with a minimum throw of 1/2 inch.
- Telecommunications switchrooms, wire closets, and related spaces shall meet applicable Telecommunications Industry Association (TIA) and Electronic Industries Alliance (EIA) standards. These standards include the following:
 - a. TIA/EIA-568, Commercial Building Telecommunications Cabling Standard,
 - b. TIA/EIA 569, Commercial Building Standard for Telecommunications Pathways and Spaces,
 - c. TIA/EIA-570, Residential and Light Commercial Telecommunications Wiring Standard, and
 - d. TIA/EIA-607, Commercial Building Grounding and Bonding Requirements for Telecommunications Standard.
- Telecommunications switchrooms, wire closets, and related spaces shall meet applicable NFPA standards. Bonding and grounding shall be in accordance with NFPA Standard 70, National Electrical Code, and other applicable NFPA standards and/or local code requirements.

B. TENANT IMPROVEMENT INFORMATION:

Telecommunications floor or wall outlets shall be provided as part of the Tenant Improvement Allowance. At a minimum, each outlet shall house one 4-pair wire jack for voice and one 4-pair wire jack for data. The Lessor shall ensure that all outlets and associated wiring, copper, coaxial cable, optical fiber, or other transmission medium used to transmit telecommunications (voice, data, video, Internet, or other emerging technologies) service to the workstation shall be safely concealed under raised floors, in

SFO No. 3NY0336

36

GOVERNMENT & GOVERNMENT

floor ducts, walls, columns, or molding. All outlets/junction boxes shall be provided with rings and pull strings to facilitate the installation of cable. Some transmission medium may require special conduit, inner duct, or shielding as specified by the Government.

8.14 TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)

A. BUILDING SHELL:

- The Government reserves the right to contract its own telecommunications (voice, data, video, Internet or other emerging technologies) service in the space to be leased. The Government may contract with one or more parties to have inside wiring (or other transmission medium) and telecommunications equipment installed.
- 2. The Lessor shall allow the Government's designated telecommunications providers access to utilize existing building wiring to connect its services to the Government's space. If the existing building wiring is insufficient to handle the transmission requirements of the Government's designated telecommunications providers, the Lessor shall provide access from the point of entry into the building to the Government's floor space, subject to any inherent limitations in the pathway involved.
- 3. The Lessor shall allow the Government's designated telecommunications providers to affix telecommunications antennae (high frequency, mobile, microwave, satellite, or other emerging technologies), subject to weight and wind load conditions, to roof, parapet, or building envelope as required. Access from the antenna(e) to the leased space shall be provided.
- 4. The Lessor shall allow the Government's designated telecommunications providers to affix antennae and transmission devices throughout its leased space and in appropriate common areas frequented by the Government's employees so as to allow the use of wireless telephones and communications devices necessary to conduct business.

B. TENANT IMPROVEMENT INFORMATION:

Provide sealed conduit to house the agency telecommunications system when required.

8.15 DATA DISTRIBUTION (AUG 2008)

A. TENANT IMPROVEMENT INFÓRMATION:

The Government shall be responsible for purchasing and installing data cable. The Lessor shall safely conceal data outlets and the associated wiring used to transmit data to workstations shall be in floor ducts, walls, columns, or below access flooring. The Lessor shall provide as part of the Tenant Improvement Allowance outlets, which shall include rings and pull strings to facilitate the installation of the data cable. When cable consists of multiple runs, the Lessor shall provide ladder-type or other acceptable cable trays to prevent Government-provided cable coming into contact with suspended ceilings or sprinkler piping. Cable trays shall form a loop around the perimeter of the Government-demised area such that they are within a 30-foot horizontal distance of any single drop.

8.16 ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (AUG 2008)

A. TENANT IMPROVEMENT INFORMATION:

- 1. The Lessor shall provide as part of the Tenant Improvement Allowance separate data, telephone, and electric junction boxes for the base feed connections to Government-provided modular or systems furniture, when such feeds are supplied via wall outlets or floor penetrations. When overhead feeds are used, junction boxes shall be installed for electrical connections. Raceways shall be provided throughout the furniture panels to distribute the electrical, telephone, and data cable. The Lessor shall provide all electrical service wiring and connections to the furniture at designated junction points. Each electrical junction shall contain an 8-wire feed consisting of 3 general-purpose 120-V circuits with 1 neutral and 1 ground wire, and a 120-V isolated-ground circuit with 1 neutral and 1 isolated-ground wire. A 20-ampere circuit shall have no more than 8 general-purpose receptacles or 4 isolated-ground "computer" receptacles.
- 2. The Government shall be responsible for purchasing data and telecommunications cable. Said cable shall be installed and connected to systems furniture by the Lessor/contractor with the assistance and/or advice of the Government or computer vendor. The Lessor shall provide wall-mounted data and telephone junction boxes, which shall include rings and pull strings to facilitate the installation of the data and telecommunications cable. When cable consists of multiple runs, the Lessor shall provide ladder-type or other acceptable cable trays to prevent Government-provided cable coming into contact with suspended ceilings or sprinkler piping. Cable trays shall form a loop around the perimeter of the Government-demised area such that they are within a 30-foot horizontal distance of any single drop. Said cable trays shall provide access to both telecommunications data closets and telephone closets.
- 3. The Lessor shall furnish and install suitably sized junction boxes in the vicinity of the "feeding points" of the furniture panels. All "feeding points" shall be shown on Government-approved design intent drawings. The Lessor shall temporarily cap off the wiring in the junction boxes until the furniture is installed. The Lessor shall make all connections in the power panel and shall keep the circuit breakers off. The Lessor shall identify each circuit with the breaker number and shall identify the computer hardware to be connected to it. The Lessor shall identify each breaker at the panel and identify the devices that it serves.
- 4. The Lessor's electrical contractor must connect power poles or base feeds in the junction boxes to the furniture electrical system and test all pre-wired receptacles in the systems furniture. Other Government contractors will be installing the data cable in the furniture panels for the terminal and printer locations, installing the connectors on the terminal/printer ends of the cable, and continuity testing each cable. Work shall be coordinated and performed in conjunction with the furniture, telephone, and data cable installers. Much of this work may occur over a weekend on a schedule that requires flexibility and on-call visits. The Lessor must coordinate the application of Certification of Occupancy with furniture installation.

MTM & GOVERNMENT

SFO No. 3NY0336

8.17 ADDITIONAL ELECTRICAL CONTROLS

If the Government pays separately for electricity, no more than 500 square feet of office may be controlled by one switch or automatic light control for all space on the Government meter, whether through a building automation system, time clock, occupant sensor, or other comparable system acceptable to the Contracting Officer.

8.18 ELEVATORS (AUG 2008)

A. The Lessor shall provide suitable passenger and, when required by the Government, freight elevator service to any Government-demised area not having ground level access. Service shall be available during the hours specified in the "Normal Hours" paragraph in the SERVICES, UTILITIES AND LEASE ADMINISTRATION section of this SFO. However, one passenger and, when required by the Government, one freight elevator shall be available at all times for Government use. When a freight elevator is required by the Government, shall be accessible to the loading areas. When possible, the Government shall be given 24-hour advance notice if the service is to be interrupted for more than 1-1/2 hours. Normal service interruption shall be scheduled outside of the Government's normal working hours. The Lessor shall also use best efforts to minimize the frequency and duration of unscheduled interruptions.

B. CODE

Elevators shall conform to the current requirements of the American Society of Mechanical Engineers ASME A17.1, Safety Code for Elevators and Escalators (current as of the award date of this SFO). Where provided, elevator lobby and elevator machine room smoke detectors shall activate the building fire alarm system, provide Phase 1 automatic recall of the elevator(s), and automatically notify the local fire department or approved central station. The elevator shall be inspected and maintained in accordance with the current edition of the ASME A17.2, Inspectors' Manual for Elevators. Except for the reference to ASME A17.1 in ABAAS Section F105.2.2, all elevators must meet ABAAS requirements for accessibility in Sections 407, 408, and 409 of ABAAS.

C. SAFETY SYSTEMS:

Elevators shall be equipped with telephones or other two-way emergency communication systems. The system used shall be marked and shall reach an emergency communication location staffed 24 hours per day, 7 days per week.

D. SPEED:

The passenger elevators shall have a capacity to transport in 5 minutes 15 percent of the normal population of all upper floors (based on 150 square feet per person). Further, the dispatch interval between elevators during the up-peak demand period shall not exceed 35 seconds.

E. INTERIOR FINISHES:

Elevator cab walls shall be hardwood, marble, granite, or an equivalent pre-approved by the Contracting Officer. Elevator cab floors shall be marble, granite, terrazzo, or an equivalent pre-approved by the Contracting Officer.

8.19 LIGHTING: INTERIOR AND PARKING (AUG 2008)

A. BUILDING SHELL:

- In accordance with subparagraph (10) of the, "Building Shell Requirements" paragraph in the Summary section of this SFO, the Lessor shall provide interior lighting, as part of the building shell cost, as follows:
 - a. Unless alternate lighting is approved by the Contracting Officer, the Lessor shall provide deep-cell parabolic louver 2'-0" wide x 4'-0" high or 2'-0" wide x 2'-0" high (or building standard that meets or exceeds this standard) or modern, diffused fluorescent fixtures using no more than 2.0 W per ANSI/BOMA Office Area square foot. Such fixtures shall be capable of producing a light level of 50 average maintained foot-candles at working surface height throughout the space. Tubes shall then be removed to provide 1) 30 foot-candles in portions of work areas other than work surfaces and 2) 1 foot-candle to 10 foot-candles, or minimum levels sufficient for safety, in non-working areas. Exceptions may be granted by the GSA Buildings Manager, and approved by the GSA Contracting Officer. When the space is not in use by the Government, interior and exterior lighting, except that essential for safety and security purposes, shall be turned off.
 - b. Exterior parking areas, vehicle driveways, pedestrian walkways, and building perimeter shall have 5 foot-candles for doorway areas, 3 foot-candles for transition areas (including stairwells), and at least 1 foot-candle overlapping throughout the lot, except where local codes conflict. Illumination shall be designed based on Illuminating Engineering Society of North America (IESNA) standards. Indoor parking shall have a minimum of 10 foot-candles and shall be designed based on IESNA standards. The intent is to provide adequate lighting at entrances/exits, garages, parking lots or other adjacent areas to the building to discourage crimes against persons.
 - Exterior building lighting must have emergency power backup to provide for safe evacuation of the building in case of natural disaster, power outage, or criminal/terrorist activity.
 - d. The Lessor shall provide occupancy sensors and/or scheduling controls through the building automation system to reduce the hours that the lights are on when the space is unoccupied. The Lessor shall provide daylight dimming controls in atriums or within 15 feet of windows where daylight can contribute to energy savings.

B. TENANT IMPROVEMENTS:

Once the design intent drawings are approved, the Lessor shall design and provide interior lighting yielding a uniform 50 foot-candles at working surface height (30" above the floor). The increase between the number of fixtures required in the building shell and the space layout is part of the Tenant Improvement Allowance. The light fixtures shall meet the requirements as stated in the above Building Shell subparagraph A.

W TESSON & GOVERNMENT

- 2. If pendant style indirect lighting fixtures are used, the increase between the number of fixtures required in the building shell and the space layout is also part of the Tenant Improvement Allowance.
- 3. The design intent drawings may require a mixed use of recessed and pendant style fixtures in the leased space.
- 4. There may be additional security requirements for lighting in exterior parking areas, vehicle driveways, pedestrian walkways, and building perimeter. Please see Security Requirements elsewhere in this solicitation.
- 8.20 ENERGY COST SAVINGS Intentionally omitted.

A JUN.
GOVERNMENT

SFO No. 3NY0336

9.0 FIRE PROTECTION, LIFE SAFETY, AND ENVIRONMENTAL ISSUES

9.1 MEANS OF EGRESS (SEP 2007)

- A. Offered space shall meet or be upgraded to meet prior to occupancy, the applicable egress requirements in the National Fire Protection Association (NFPA) 101, Life Safety Code (current as of the award date of this lease), or an alternative approach or method for achieving a level of safety deemed equivalent and acceptable by the Government.
- B. Offered space shall provide unrestricted access to a minimum of two remote exits on each floor of Government occupancy. Scissor stairs shall only be counted as one approved exit. Open air exterior fire escapes shall not be counted as an approved exit. In addition, the requirements for exit remoteness and discharge from exits shall meet the requirements in NFPA 101, Life Safety Code (current as of the award date of this lease), or an alternative approach or method for achieving a level of safety deemed equivalent and acceptable to the Government.

9.2 AUTOMATIC FIRE SPRINKLER SYSTEM (AUG 2008)

- A. Offered space located below-grade, including parking garage areas, and all areas in a building referred to as "hazardous areas" (defined in NFPA 101) that are located within the entire building (including non-Government areas) shall be protected by an automatic fire sprinkler system or an equivalent level of safety.
- B. For buildings in which any portion of the offered space is on or above the sixth floor, then, at a minimum, the building up to and including the highest floor of Government occupancy shall be protected by an automatic fire sprinkler system or an equivalent level of safety.
- C. For buildings in which any portion of the offered space is on or above the sixth floor, and lease of the offered space will result, either individually or in combination with other Government leases in the offered building, in the Government leasing 35,000 square feet or more ANSI/BOMA Office Area square feet of space in the offered building, then the entire building shall be protected throughout by an automatic fire sprinkler system or an equivalent level of safety.
- D. Automatic sprinkler system(s) shall be maintained in accordance with the requirements NFPA 25, Standard for the Inspection, Testing, and Maintenance of Water-based Fire Protection Systems (current as of the award date of this lease), or the applicable local codes.

E. **DEFINITIONS**:

- "Automatic sprinkler system" means an electronically supervised, integrated system of underground and overhead piping, designed in accordance with National Fire Protection Association (NFPA) 13, Installation of Sprinkler Systems. The system is usually activated by heat from fire and discharges water over the fire area. The system includes an adequate water supply.
- "Equivalent level of safety" means an alternative design or system (which may include automatic sprinkler systems), based upon fire protection engineering analysis, which achieves a level of safety equal to or greater than that provided by automatic sprinkler systems.

9.3 FIRE ALARM SYSTEM (AUG 2008)

- A. A building-wide fire alarm system shall be installed in buildings in which any portion of the offered space is located 2 or more stories in height above the lowest level of exit discharge. The fire alarm system shall meet the installation and operational requirements of the applicable local codes and ordinances adopted by the jurisdiction in which the building is located.
- B. The fire alarm system shall be maintained in accordance with the requirements of the applicable local codes or NFPA 72, National Fire Alarm Code (current as of the award of the lease) The fire alarm system wiring and equipment shall be electrically-supervised and shall automatically notify the local fire department or approved central station. Emergency power shall be provided for the fire alarm system.
- C. If a building's fire alarm control unit is over 25 years old, the Offeror shall install a new fire alarm system in accordance with the requirements of NFPA 72, National Fire Alarm Code (current as of the award of the lease) or applicable local codes prior to Government acceptance and occupancy of the offered space.

9.4 OSHA REQUIREMENTS (SEP 2000)

The Lessor shall maintain buildings and space in a safe and healthful condition according to OSHA standards.

9.5 ASBESTOS (SEP 2000)

A. Offers are requested for space with no asbestos-containing materials (ACM), or with ACM in a stable, solid matrix (e.g., asbestos flooring or asbestos cement panels) which is not damaged or subject to damage by routine operations. For purposes of this paragraph, "space" includes the 1) space offered for lease; 2) common building area; 3) ventilation systems and zones serving the space offered; and 4) the area above suspended ceilings and engineering space in the same ventilation zone as the space offered. If no offers are received for such space, the Government may consider space with thermal system insulation ACM (e.g., wrapped pipe or boiler lagging) which is not damaged or subject to damage by routine operations.

B. **DEFINITION**:

ACM is defined as any materials with a concentration of greater than 1 percent by dry weight of asbestos

SFO No. 3NY0336

40

MIM & SOVERNMENT

C. Space with ACM of any type or condition may be upgraded by the Offeror to meet conditions described in subparagraph A by abatement (removal, enclosure, encapsulation, or repair) of ACM not meeting those conditions. If any offer involving abatement of ACM is accepted by the Government, the Lessor shall, prior to occupancy, successfully complete the abatement in accordance with OSHA, EPA, Department of Transportation (DOT), state, and local regulations and guidance.

D. MANAGEMENT PLAN:

If space is offered which contains ACM, the Offeror shall submit an asbestos-related management plan for acceptance by the Government prior to lease award. This plan shall conform to EPA guidance, be implemented prior to occupancy, and be revised promptly when conditions affecting the plan change. If asbestos abatement work is to be performed in the space after occupancy, the Lessor shall submit to the Contracting Officer the occupant safety plan and a description of the methods of abatement and reoccupancy clearance, in accordance with OSHA, EPA, DOT, state, and local regulations and guidance, at least 4 weeks prior to the abatement work.

9.6 **INDOOR AIR QUALITY (DEC 2007)**

- A. The Lessor shall control contaminants at the source and/or operate the space in such a manner that the GSA indicator levels for carbon monoxide (CO), carbon dioxide (CO2), and formaldehyde (HCHO) are not exceeded. The indicator levels for office areas shall be: CO 9 ppm time weighted average (TWA 8 hour sample); CO2 1,000 ppm (TWA); HCHO 0.1 ppm (TWA).
- B. The Lessor shall make a reasonable attempt to apply insecticides, paints, glues, adhesives, and HVAC system cleaning compounds with highly volatile or irritating organic compounds, outside of working hours. Except in an emergency, the Lessor shall provide at least 72 hours advance notice to the Government before applying noxious chemicals in occupied spaces and shall adequately ventilate those spaces during and after application.
- C. The Lessor shall promptly investigate indoor air quality (IAQ) complaints and shall implement the necessary controls to address the complaint.
- D. The Government reserves the right to conduct independent IAQ assessments and detailed studies in space that it occupies, as well as in space serving the Government demised area (e.g., common use areas, mechanical rooms, HVAC systems, etc.). The Lessor shall assist the Government in its assessments and detailed studies by 1) making available information on building operations and Lessor activities; 2) providing access to space for assessment and testing, if required; and 3) implementing corrective measures required by the Contracting Officer.
- E. The Lessor shall provide to the Government material safety data sheets (MSDS) upon request for the following products prior to their use during the term of the lease: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, janitorial cleaning products, pesticides, rodenticides, and herbicides. The Government reserves the right to review such products used by the Lessor within 1) the Government demised area; 2) common building areas; 3) ventilation systems and zones serving the leased space; and 4) the area above suspended ceilings and engineering space in the same ventilation zone as the leased space.
- F. Where hazardous gasses or chemicals (any products with data in the Health and Safety section of the MSDS sheets) may be present or used, including large-scale copying and printing rooms, segregate areas with deck-to-deck partitions with separate outside exhausting at a rate of at least 0.5 cubic feet per minute per square foot, no air recirculation. The mechanical system must operate at a negative pressure compared with the surrounding spaces of at least an average of 5 Pa (pascal) (0.02 inches of water gauge) and with a minimum of 1 Pa (0.004 inches of water gauge) when the doors to the rooms are closed.

9.7 **RADON IN AIR (AUG 2008)**

If space planned for occupancy by the Government is on the second floor above grade or lower, the Lessor shall, prior to occupancy, test the leased space for 2 days to 3 days using charcoal canisters or electret ion chambers. The Lessor is responsible to provide space in which in air levels are below EPA's action concentration of 4 picoCuries per liter. After the initial testing, a follow-up test for a minimum of 90 days using alpha track detectors or electret ion chambers shall be completed. For further information on radon, see EPA's website on radon at WWW.EPA.GOV/IAQ/RADON/ZONEMAP.HTML

9.8 **RADON IN WATER (AUG 2008)**

- A. If the water source is not from a public utility, the Lessor shall demonstrate that water provided in the leased space is in compliance with EPA requirements and shall submit certification to the Contracting Officer prior to the Government occupying the space.
- B. If the EPA action level is reached or exceeded, the Lessor shall institute appropriate abatement methods which reduce the radon levels to below this action.

HAZARDOUS MATERIALS (OCT 1996) 9.9

The leased space shall be free of hazardous materials according to applicable federal, state, and local environmental regulations.

9.10 **RECYCLING (DEC 2007)**

A. Where State or local law, code, or ordinance requires recycling programs (including mercury containing lamps) for the space to be provided pursuant to this SFO, the successful Offeror shall comply with such State and/or local law, code, or ordinance in accordance with GSA Form 3517, General Clauses, 552.270-8, Compliance with Applicable Law. In all other cases, the successful Offeror shall establish a recycling program for (at a minimum) paper, corrugated cardboard, glass, plastics, and metals where local markets for recovered materials exist. Provide an easily accessible, appropriately sized (2 square feet per 1,000 square feet of building gross floor area) area that serves the tenant space for the collection and storage of materials for NY0336

45

GOVERNMENT

SFO No. 3NY0336

recycling. Telecom rooms are not acceptable as recycling space. During the lease term, the Lessor agrees, upon request, to provide the Government with additional information concerning recycling programs maintained in the building and in the leased space.

9.11 OCCUPANT EMERGENCY PLANS (AUG 2008)

The Lessor is required to participate in and comply with the development and implementation of the Government Occupant Emergency Plan. The Plan must, among other things, include emergency notification procedures of the Lessor's building engineer or manager, building security, local emergency personnel, and GSA personnel. For further information and guidelines on Occupant Emergency Plans, see also the following website:

http://www.9-11summit.org/materials9-

11/911/acrobat/27/P3&C10EmergencyPreparednessPlans/GSAOccupantEmergencyProgram.pdf.

9.12 MOLD (AUG 2008)

- A. Actionable Mold is mold of types and concentrations in excess of that found in the local outdoor air.
- B. The Lessor shall provide space to the Government that is free from Actionable Mold and free from any conditions that reasonably can be anticipated to permit the growth of Actionable Mold or are indicative of the possibility that Actionable Mold will be present ("Indicators").
- C. At such times as the Government may direct, including but not limited to: after a flood, water damage not caused by the Government, or repairs caused by the Lessor, the Lessor, at its sole cost, expense and risk shall: (i) cause an industrial hygienist certified by the American Board of Industrial Hygienists or a qualified consultant ("the Inspector") who, in either instance, is reasonably acceptable to the Government, to inspect and evaluate the space for the presence of Actionable Mold or mold Indicators; and (ii) cause the Inspector to deliver the results of its inspection and evaluation (the "Report") to the Government within 30 days after it conducts same and, in all events, at the same time that it delivers the Report to Lessor. With the delivery of the Report to the Government, the Inspector shall notify the Government, in writing via cover letter to the report, if the Inspector discovers or suspects the existence of Actionable Mold or Indicators in the leased space.
- D. The presence of Actionable Mold in the premises may be treated as a Casualty, as determined by the Government, in accordance with the Fire and Other Casualty clause contained in the General Clauses of this lease. In addition to the provisions of the Fire and Other Casualty clause of this lease, should a portion of the premises be determined by the Government to be un-tenantable due to an act of negligence by the Lessor or his agents, the Lessor shall provide reasonably acceptable alternative space at the Lessor's expense, including the cost of moving, and any required alterations.
- E. If the Report indicates that Actionable Mold or Indicators are present in the leased space, the Lessor, at its sole cost, expense, and risk, shall within thirty (30) days after its receipt of the Report: 1) retain an experienced mold remediation contractor reasonably acceptable to the Government to prepare and submit to the Government and Lessor a remediation plan (the "Plan") and within thirty (30) days after the Government's approval of the Plan, remediate the Actionable Mold or the Indicators in the leased space, but prior to commencing such remediation, Lessor shall send the Government a notice stating: (i) the date on which the Actionable Mold remediation shall start and how long it is projected to continue; (ii) which portion of the leased space shall be subject to the remediation; and (iii) the remediation procedures and standards to be used to implement the Plan and the clearance criteria to be employed at the conclusion of the remediation; and 2) notify, in accordance with any applicable Federal, state, and local health and safety requirements, the Government employees as well as all other occupants of and visitors to the leased space of the nature, location and schedule for the planned remediation and reasons therefore.
- F. The Lessor shall be responsible for conducting the remediation in accordance with the relevant provisions of the document entitled "Mold Remediation in Schools and Commercial Buildings" (EPA 402-K-01-001, March 2001), published by the U.S. Environmental Protection Agency, as same may be amended or revised from time to time, and any other applicable federal, state, or local laws, regulatory standards and guidelines.
- G. The Lessor acknowledges and agrees that the Government shall have a reasonable opportunity to inspect the leased space after conclusion of the remediation. If the results of the Government's inspection indicate that the remediation does not comply with the Plan or any other applicable federal, state, or local laws, regulatory standards or guidelines, the Lessor, at its sole cost, expense and risk, shall immediately take all further actions necessary to bring the remediation into compliance.
- H. If the Lessor fails to exercise due diligence, or is otherwise unable to remediate the Actionable Mold, the Government may implement a corrective action program and deduct its costs from the rent.

MIN & GOVERNMENT

SFO No. 3NY0336

10.0 LEASE SECURITY STANDARDS

| 10.1 | GENERAL REQUIREMENTS (NOV 2005) |
|-------------|---|
| | (b) (/)(F) |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| . I 10.2 | |
| 10.2 | DETERRENCE TO UNAUTHORIZED ENTRY (NOV 2005) The Lessor shall provide a level of security that reasonably prevents unauthorized entry to the space during non-duty hours and deters loitering or disruptive acts in and around the space leased. The Lessor shall ensure that security cameras and lighting are not obstructed. |
| 10.3 | ACCESS TO UTILITY AREAS (NOV 2005) Utility areas shall be secure, and only authorized personnel shall have access. |
| 10.4 | EMERGENCY POWER TO CRITICAL SYSTEMS (SEP 2009) (b) (7)(F) |
| | |
| | |
| | |
| | |
| 10.5 | MECHANICAL AREAS AND BUILDING ROOFS (NOV 2005) b) (7)(F) |
| | |
| | |
| | |
| 10.6 | ACCESS TO BUILDING INFORMATION (NOV 2005) |
| | b) (7)(F) |
| | |
| | |
| | |

SFO No. 3NY0336 43 MIM SW. GOVERNMENT

POSTING OF GOVERNMENT RULES AND REGULATIONS (TENANT IMPROVEMENT) (NOV 2005)

The Government will post applicable Government rules and regulations at the entrance to any Government-occupied space for such things as, but not limited to, barring the unauthorized possession of firearms and dangerous weapons. The Government will coordinate with the Lessor to ensure signage is consistent with the Lessor's standards.

DEVELOPMENT, IMPLEMENTATION, AND PERIODIC REVIEW OF OCCUPANT EMERGENCY PLANS (NOV 2005) 10.8


The Lessor shall cooperate and participate in the development of an Occupant Emergency Plan (OEP) and if necessary, a supplemental Sheltering-in Place (SIP) Plan. Periodically, the Government may request that the Lessor assist in reviewing and revising the OEP and SIP plan(s).

10.9 **BUILDING SECURITY PLAN (NOV 2005)**

The Offeror shall provide a Pre-Lease Building Security Plan, as attached, with the offer that addresses its compliance with the lease security standards, as described in this SFO and its attachments.

10.10 ADDITIONAL SECURITY MEASURES AS DETERMINED BY THE GOVERNMENT (NOV 2005)

The Government reserves the right, prior to the submission of final revised proposals, to require additional security measures to meet specific tenant occupancy requirements, as may be determined by the Government's building security assessment or any type of Government risk assessment evaluation of the proposed building, location, and tenant mix.



10.12 ENTRY SECURITY: INTRUSION DETECTION SYSTEM WITH

10.13 OCCUPANT/VISITOR SCREENING: VISITOR CONTROL/SCREENING

10.14 SECURE HVAC: OUTDOOR AIR INTAKES (BUILDING SHELL) (NOV 2005)

SFO No. 3NY0336

44

48 M T MSOR & GOVERNMENT

| (b) (7)(F) | | | |
|--|-------------|-----------------|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| 40.45 | | | |
| 10.15 SECURE HVAC: AIRBORNE HAZARDS (NOV 2005) (b) (7)(F) | | | |
| | | | |
| 10.16 SECURE HVAC: SECURE RETURN-AIR GRILLES (BU | III DING SH | ELL) (NOV 2005) | |
| 10.16 SECURE HVAC: SECURE RETURN-AIR GRILLES (RU (b) (7)(F) | | | |
| | | | |
| 10.17 PARKING SECURITY REQUIREMENTS (NOV 2005) | | | |
| (b) (7)(F) | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| 10.18 (b) (7)(F) | | | |
| | | | |
| /L\ /7\/F\ | | | |
| 10.19 (b) (7)(F) | | | |
| 10.20 (b) (7)(F) | | | |
| | | | |
| | | | |
| SFO No. 3NY0336 45 | | 8 M. | |
| | 49 | * GOVERNMENT | |

(b) (7)(F)

(b) (7)(F)

- 10.22 SECURITY DESIGN CRITERIA Intentionally omitted.
- 10.23 SECURITY DESIGN CRITERIA: SETBACK (BUILDING SHELL) Intentionally omitted.
- 10.24 SECURITY DESIGN CRITERIA: FAÇADE PROTECTION (BUILDING SHELL) Intentionally omitted.
- 10.25 SECURITY DESIGN CRITERIA: SHATTER-RESISTANT WINDOWS (BUILDING SHELL) Intentionally omitted.
- 10.26 SECURITY DESIGN CRITERIA: HVAC (BUILDING SHELL) Intentionally omitted.
- 10.27 SECURITY DESIGN CRITERIA: DESIGN AND ENGINEERING DOCUMENTS Intentionally omitted.

MIMESSOR & SOVERNMENT

SFO No. 3NY0336

11.0 SPECIAL REQUIREMENTS

11.1 SPECIAL REQUIREMENTS:

Exhibit A: (b) (7)(F)

Exhibit B:

Exhibit C:

SFO No. 3NY0336 47

51

Mam & SU.

LESSOR & GOVERNMENT

GENERAL CLAUSES (Acquisition of Leasehold Interests in Real Property)

| CATEGORY | CLAUSE NO | . 48 CFR REF | CLAUSE TITLE |
|----------------------|-----------|--------------|---|
| DEFINITIONS | 1 | 552.270-4 | Definitions (Variation) |
| GENERAL | 2 | 552.270-5 | Cubication and A |
| | 3 | 552.270-5 | Subletting and Assignment |
| | 4 | 552.270-11 | Successors Bound Subordination, Nondisturbance and |
| | E | FF0 070 04 | Attornment |
| | 5 | 552.270-24 | Statement of Lease |
| | 6 | 552.270-25 | Substitution of Tenant Agency |
| | 7 | 552.270-26 | No Waiver |
| | 8 | 552.270-27 | Integrated Agreement |
| | 9 | 552.270-28 | Mutuality of Obligation |
| PERFORMANCE | 10 | 552.270-17 | Delivery and Condition |
| | 11 | 552.270-18 | Default in Delivery—Time Extensions |
| | | 002.270 10 | (Variation) |
| | 12 | 552.270-19 | Progressive Occupancy |
| | 13 | 552.270-21 | Effect of Acceptance and Occupancy |
| | 14 | 552.270-6 | Maintenance of Building and Premises— |
| | | | Right of Entry (Variation) |
| | 15 | 552.270-10 | Failure in Performance |
| | 16 | 552.270-22 | Default by Lessor During the Term |
| | 17 | 552.270-7 | Fire and Couldty Dame and |
| | 18 | 552.270-8 | Fire and Casualty Damage |
| | 19 | 552.270-12 | Compliance with Applicable Law |
| | 20 | 552.270-12 | Alterations Acceptance of Space (Variation) |
| INSPECTION | 0.1 | | · |
| | 21 | 552.270-9 | Inspection—Right of Entry |
| PAYMENT | 22 | 52.204-7 | Central Contractor Registration (Variation) |
| | 23 | 552.232-75 | Prompt Payment |
| | 24 | 552.232-76 | Electronic Funds Transfer Payment |
| | 25 | EE0 000 70 | (Variation) |
| | 26 26 | 552.232-70 | Invoice Requirements (Variation) |
| | 20 | 52.232-23 | Assignment of Claims \ |
| | 27 | 552.270-20 | Payment (Variation) |
| STANDARDS OF CONDUCT | Г 28 | 552.203-5 | Covenant Against Contingent Fees |
| | 29 | 52.203-7 | Anti-Kickback Procedures |
| | 30 | 52.223-6 | Drug-Free Workplace |
| ADJUSTMENTS | 31 | 552.203-70 | Price Adjustment for Illegal or Improper Activity |
| | 32 | 52.215-10 | Price Reduction for Defective Cost or Pricing Data |
| | 33 | 552.270-13 | Proposals for Adjustment |
| | 34 | 552.270-14 | Changes (Variation) |
| AUDITS | 35 | 552.215-70 | Francis at (D) |
| | 36 | 52.215-2 | Examination of Records by GSA Audit and Records—Negotiation |
| DISPUTES | 37 | 52.233-1 | Disputes |
| NITIAI & A . | Lu2 | | • |
| LEISON G | ØVERNMENT | - 91 | GSA FORM 3517B PAGE 1 (REV 06/08) |
| . | | | 33.11 31.11 1011 DI AGE I (NEV 00/08) |

| 1.4505.05445.555 | | | |
|------------------|----|-----------|--|
| LABOR STANDARDS | 38 | 52.222-26 | Equal Opportunity |
| | 39 | 52.222-24 | Preaward On-Site Equal Opportunity Compliance Evaluation |
| | 40 | 52.222-21 | Prohibition of Segregated Facilities |
| | 41 | 52.222-35 | Equal Opportunity for Special Disabled Veterans, Veterans of the Vietnam Era, and Other Eligible Veterans |
| | 42 | 52.222-36 | Affirmative Action for Workers with Disabilities |
| | 43 | 52.222-37 | Employment Reports on Special Disabled Veterans, Veterans of the Vietnam Era, and Other Eligible Veterans |
| SUBCONTRACTING | 44 | 52.209-6 | Protecting the Government's Interest When Subcontracting With Contractors Debarred, Suspended, or Proposed for Debarment |
| | 45 | 52.215-12 | Subcontractor Cost or Pricing Data |
| | 46 | 52.219-8 | Utilization of Small Business Concerns |
| | 47 | 52.219-9 | Small Business Subcontracting Plan |
| | 48 | 52.219-16 | Liquidated Damages—Subcontracting Plan |

The information collection requirements contained in this solicitation/contract, that are not required by regulation, have been approved by the Office of Management and Budget pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

INITIALS: LESSOR & COVERNMENT

GENERAL CLAUSES (Acquisition of Leasehold Interests in Real Property)

1. 552.270-4 DEFINITIONS (SEP 1999) (VARIATION)

The following terms and phrases (except as otherwise expressly provided or unless the context otherwise requires) for all purposes of this lease shall have the respective meanings hereinafter specified:

- (a) "Commencement Date" means the first day of the term.
- (b) "Contract" and "Contractor" means "Lease" and "Lessor," respectively.
- (c) "Contracting Officer" means a person with the authority to enter into, administer, and/or terminate contracts and make related determinations and findings. The term includes certain authorized representatives of the Contracting Officer acting within the limits of their authority as delegated by the Contracting Officer.
- (d) "Delivery Date" means the date specified in or determined pursuant to the provisions of this lease for delivery of the premises to the Government, improved in accordance with the provisions of this lease and substantially complete, as such date may be modified in accordance with the provisions of this lease.
- (e) "Delivery Time" means the number of days provided by this lease for delivery of the premises to the Government, as such number may be modified in accordance with the provisions of this lease.
- (f) "Excusable Delays" mean delays arising without the fault or negligence of Lessor and Lessor's subcontractors and suppliers at any tier, and shall include, without limitation:

(1) acts of God or of the public enemy,

(2) acts of the United States of America in either its sovereign or contractual capacity,
 (3) acts of another contractor in the performance of a contract with the Government,

(4) fires,

- (5) floods.
- (6) epidemics,
- (7) quarantine restrictions,
- (8) strikes,
- (9) freight embargoes,

(10) unusually severe weather, or

- delays of subcontractors or suppliers at any tier arising from unforeseeable causes beyond the control and without the fault or negligence of both the Lessor and any such subcontractor or supplier.
- (g) "Lessor" means the sub-lessor if this lease is a sublease.
- (h) "Lessor shall provide" means the Lessor shall furnish and install at Lessor's expense.
- (i) "Notice" means written notice sent by certified or registered mail, Express Mail or Comparable service, or delivered by hand. Notice shall be effective on the date delivery is accepted or refused.
- (j) "Premises" means the space described on the Standard Form 2, U.S. Government Lease for Real Property, of this lease.
- (I) "Substantially complete" and "substantial completion" means that the work, the common and other areas of the building, and all other things necessary for the Government's access to the premises and occupancy, possession, use and enjoyment thereof, as provided in this lease, have been completed or obtained, excepting only such minor matters as do not interfere with or materially diminish such access, occupancy, possession, use or enjoyment.
- (m) "Usable square feet" means the ANSI/BOMA Z65.1-1996 definition for BOMA usable office area, which means "The area where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed."
- (n) "Work" means all alterations, improvements, modifications, and other things required for the preparation or continued occupancy of the premises by the Government as specified in this lease.

LESSOR & SOVERNMENT

2. 552.270-5 SUBLETTING AND ASSIGNMENT (SEP 1999)

The Government may sublet any part of the premises but shall not be relieved from any obligations under this lease by reason of any such subletting. The Government may at any time assign this lease, and be relieved from all obligations to Lessor under this lease excepting only unpaid rent and other liabilities, if any, that have accrued to the date of said assignment. Any assignment shall be subject to prior written consent of Lessor, which shall not be unreasonably withheld.

3. 552.270-11 SUCCESSORS BOUND (SEP 1999)

This lease shall bind, and inure to the benefit of, the parties and their respective heirs, executors, administrators, successors, and assigns.

4. 552.270-23 SUBORDINATION, NONDISTURBANCE AND ATTORNMENT (SEP 1999)

- Lessor warrants that it holds such title to or other interest in the premises and other property as is necessary to the Government's access to the premises and full use and enjoyment thereof in accordance with the provisions of this lease. Government agrees, in consideration of the warranties and conditions set forth in this clause, that this lease is subject and subordinate to any and all recorded mortgages, deeds of trust and other liens now or hereafter existing or imposed upon the premises, and to any renewal, modification or extension thereof. It is the intention of the parties that this provision shall be self-operative and that no further instrument shall be required to effect the present or subsequent subordination of this lease. Government agrees, however, within twenty (20) business days next following the Contracting Officer's receipt of a written demand, to execute such instruments as Lessor may reasonably request to evidence further the subordination of this lease to any existing or future mortgage, deed of trust or other security interest pertaining to the premises, and to any water, sewer or access easement necessary or desirable to serve the premises or adjoining property owned in whole or in part by Lessor if such easement does not interfere with the full enjoyment of any right granted the Government under this lease.
- (b) No such subordination, to either existing or future mortgages, deeds of trust or other lien or security instrument shall operate to affect adversely any right of the Government under this lease so long as the Government is not in default under this lease. Lessor will include in any future mortgage, deed of trust or other security instrument to which this lease becomes subordinate, or in a separate nondisturbance agreement, a provision to the foregoing effect. Lessor warrants that the holders of all notes or other obligations secured by existing mortgages, deeds of trust or other security instruments have consented to the provisions of this clause, and agrees to provide true copies of all such consents to the Contracting Officer promptly upon demand.
- (c) In the event of any sale of the premises or any portion thereof by foreclosure of the lien of any such mortgage, deed of trust or other security instrument, or the giving of a deed in lieu of foreclosure, the Government will be deemed to have attorned to any purchaser, purchasers, transferee or transferees of the premises or any portion thereof and its or their successors and assigns, and any such purchasers and transferees will be deemed to have assumed all obligations of the Lessor under this lease, so as to establish direct privity of estate and contract between Government and such purchasers or transferees, with the same force, effect and relative priority in time and right as if the lease had initially been entered into between such purchasers or transferees and the Government; provided, further, that the Contracting Officer and such purchasers or transferees shall, with reasonable promptness following any such sale or deed delivery in lieu of foreclosure, execute all such revisions to this lease, or other writings, as shall be necessary to document the foregoing relationship.
- (d) None of the foregoing provisions may be deemed or construed to imply a waiver of the Government's rights as a sovereign.

5. 552.270-24 STATEMENT OF LEASE (SEP 1999)

(a) The Contracting Officer will, within thirty (30) days next following the Contracting Officer's receipt of a joint written request from Lessor and a prospective lender or purchaser of the building, execute and deliver to Lessor a letter stating that the same is issued subject to the conditions stated in this clause and, if such is the case, that (1) the lease is in full force and effect; (2) the date to which the rent and other charges have been paid in advance, if any; and (3) whether any notice of default has been issued.

IT IALS: LESSOR & SOVERNMENT

- (b) Letters issued pursuant to this clause are subject to the following conditions:
 - That they are based solely upon a reasonably diligent review of the Contracting Officer's lease file as of the date of issuance;
 - (2) That the Government shall not be held liable because of any defect in or condition of the premises or building;
 - (3) That the Contracting Officer does not warrant or represent that the premises or building comply with applicable Federal, State and local law; and
 - (4) That the Lessor, and each prospective lender and purchaser are deemed to have constructive notice of such facts as would be ascertainable by reasonable prepurchase and precommitment inspection of the Premises and Building and by inquiry to appropriate Federal, State and local Government officials.

6. 552.270-25 SUBSTITUTION OF TENANT AGENCY (SEP 1999)

The Government may, at any time and from time to time, substitute any Government agency or agencies for the Government agency or agencies, if any, named in the lease.

7. 552.270-26 NO WAIVER (SEP1999)

No failure by either party to insist upon the strict performance of any provision of this lease or to exercise any right or remedy consequent upon a breach thereof, and no acceptance of full or partial rent or other performance by either party during the continuance of any such breach shall constitute a waiver of any such breach of such provision.

8. 552.270-27 INTEGRATED AGREEMENT (SEP 1999)

This Lease, upon execution, contains the entire agreement of the parties and no prior written or oral agreement, express or implied, shall be admissible to contradict the provisions of the Lease.

9. 552.270-28 MUTUALITY OF OBLIGATION (SEP 1999)

The obligations and covenants of the Lessor, and the Government's obligation to pay rent and other Government obligations and covenants, arising under or related to this Lease, are interdependent. The Government may, upon issuance of and delivery to Lessor of a final decision asserting a claim against Lessor, set off such claim, in whole or in part, as against any payment or payments then or thereafter due the Lessor under this lease. No setoff pursuant to this clause shall constitute a breach by the Government of this lease.

10. 552.270-17 DELIVERY AND CONDITION (SEP 1999)

GOVERNMENT

LESSOR

- (a) Unless the Government elects to have the space occupied in increments, the space must be delivered ready for occupancy as a complete unit. The Government reserves the right to determine when the space is substantially complete.
- (b) If the premises do not in every respect comply with the provisions of this lease the Contracting Officer may, in accordance with the Failure in Performance clause of this lease, elect to reduce the rent payments.

11. 552.270-18 DEFAULT IN DELIVERY—TIME EXTENSIONS (SEP 1999) (VARIATION)

(a) With respect to Lessor's obligation to deliver the premises substantially complete by the delivery date, time is of the essence. If the Lessor fails to work diligently to ensure its substantial completion by the delivery date or fails to substantially complete the work by such date, the Government may by notice to the Lessor terminate this lease. Such termination is effective when received by Lessor. The Lessor and the Lessor's sureties, if any, are jointly and severally liable for any damages to the Government resulting from such termination, as provided in this clause. The Government shall be entitled to the following damages:

(1) The Government's aggregate rent and estimated real estate tax and operating cost adjustments for the firm term and all option terms of its replacement lease or leases,

in excess of the aggregate rent and estimated real estate tax and operating cost adjustments for the term. If the Government procures replacement premises for a term (including all option terms) in excess of this term, the Lessor is not liable for excess Government rent or adjustments during such excess lease term.

- (2) All administrative and other costs the Government incurs in procuring a replacement lease or leases.
- (3) Other, additional relief provided for in this lease, at law, or in equity.
- (b) Damages to which the Government is entitled to under this clause are due and payable thirty (30) days following the date Lessor receives notice from the Contracting Officer specifying such damages.
- (c) Delivery by Lessor of less than the minimum ANSI/BOMA Office Area square footage required by this lease shall in no event be construed as substantial completion, except as the Contracting Officer permits.
- (d) The Government shall not terminate this lease under this clause nor charge the Lessor with damages under this clause, if (1) the delay in substantially completing the work arises from excusable delays and (2) the Lessor within 10 days from the beginning of any such delay (unless extended in writing by the Contracting Officer) provides notice to the Contracting Officer of the causes of delay. The Contracting Officer shall ascertain the facts and the extent of delay. If the facts warrant, the Contracting Officer shall extend the delivery date, to the extent of such delay at no additional costs to the Government. A time extension is the sole remedy of the Lessor.

12. 552.270-19 PROGRESSIVE OCCUPANCY (SEP 1999)

The Government shall have the right to elect to occupy the space in partial increments prior to the substantial completion of the entire leased premises, and the Lessor agrees to schedule its work so as to deliver the space incrementally as elected by the Government. The Government shall pay rent commencing with the first business day following substantial completion of the entire leased premise unless the Government has elected to occupy the leased premises incrementally. In case of incremental occupancy, the Government shall pay rent pro rata upon the first business day following substantial completion of each incremental unit. Rental payments shall become due on the first workday of the month following the month in which an increment of space is substantially complete, except that should an increment of space be substantially completed after the fifteenth day of the month, the payment due date will be the first workday of the second month following the month in which it was substantially complete. The commencement date of the firm lease term will be a composite determined from all rent commencement dates.

13. 552.270-21 EFFECT OF ACCEPTANCE AND OCCUPANCY (SEP 1999)

Neither the Government's acceptance of the premises for occupancy, nor the Government's occupancy thereof, shall be construed as a waiver of any requirement of or right of the Government under this Lease, or as otherwise prejudicing the Government with respect to any such requirement or right.

14. 552.270-6 MAINTENANCE OF BUILDING AND PREMISES—RIGHT OF ENTRY (SEP 1999) (VARIATION)

Except in case of damage arising out of the willful act or negligence of a Government employee, Lessor shall maintain the premises, including the building, building systems, and all equipment, fixtures, and appurtenances furnished by the Lessor under this lease, in good repair and condition so that they are suitable in appearance and capable of supplying such heat, air conditioning, light, ventilation, safety systems, access and other things to the premises, without reasonably preventable or recurring disruption, as is required for the Government's access to, occupancy, possession, use and enjoyment of the premises as provided in this lease. For the purpose of so maintaining the premises, the Lessor may at reasonable times enter the premises with the approval of the authorized Government representative in charge.

15. 552.270-10 FAILURE IN PERFORMANCE (SEP 1999)

The covenant to pay rent and the covenant to provide any service, utility, maintenance, or repair required under this lease are interdependent. In the event of any failure by the Lessor to provide

INITIA S: LESSOR

GOVERNMENT

any service, utility, maintenance, repair or replacement required under this lease the Government may, by contract or otherwise, perform the requirement and deduct from any payment or payments under this lease, then or thereafter due, the resulting cost to the Government, including all administrative costs. If the Government elects to perform any such requirement, the Government and each of its contractors shall be entitled to access to any and all areas of the building, access to which is necessary to perform any such requirement, and the Lessor shall afford and facilitate such access. Alternatively, the Government may deduct from any payment under this lease, then or thereafter due, an amount which reflects the reduced value of the contract requirement not performed. No deduction from rent pursuant to this clause shall constitute a default by the Government under this lease. These remedies are not exclusive and are in addition to any other remedies which may be available under this lease or at law.

16. 552.270-22 DEFAULT BY LESSOR DURING THE TERM (SEP 1999)

- (a) Each of the following shall constitute a default by Lessor under this lease:
 - (1) Failure to maintain, repair, operate or service the premises as and when specified in this lease, or failure to perform any other requirement of this lease as and when required provided any such failure shall remain uncured for a period of thirty (30) days next following Lessor's receipt of notice thereof from the Contracting Officer or an authorized representative.
 - (2) Repeated and unexcused failure by Lessor to comply with one or more requirements of this lease shall constitute a default notwithstanding that one or all such failures shall have been timely cured pursuant to this clause.
- (b) If a default occurs, the Government may, by notice to Lessor, terminate this lease for default and if so terminated, the Government shall be entitled to the damages specified in the Default in Delivery-Time Extensions clause.

17. 552.270-7 FIRE AND CASUALTY DAMAGE (Jun 2008)

If the entire premises are destroyed by fire or other casualty, this lease will immediately terminate. In case of partial destruction or damage, so as to render the premises untenantable, as determined by the Government, the Government may terminate the lease by giving written notice to the Lessor within 15 calendar days **after such determination**. If so terminated, no rent will accrue to the Lessor after such partial destruction or damage; and if not so terminated, the rent will be reduced proportionately by supplemental agreement hereto effective from the date of such partial destruction or damage. Nothing in this lease shall be construed as relieving Lessor from liability for damage to or destruction of property of the United States of America caused by the willful or negligent act or omission of Lessor.

18.552.270-8 COMPLIANCE WITH APPLICABLE LAW (SEP 1999)

Lessor shall comply with all Federal, state and local laws applicable to the Lessor as owner or Lessor, or both, of the building or premises, including, without limitation, laws applicable to the construction, ownership, alteration or operation of both or either thereof, and will obtain all necessary permits, licenses and similar items at Lessor's expense. The Government will comply with all Federal, State and local laws applicable to and enforceable against it as a tenant under this lease; provided that nothing in this lease shall be construed as a waiver of any sovereign immunity of the Government. This lease shall be governed by Federal law.

19. 552.270-12 ALTERATIONS (SEP 1999)

The Government shall have the right during the existence of this lease to make alterations, attach fixtures, and erect structures or signs in or upon the premises hereby leased, which fixtures, additions or structures so placed in, on, upon, or attached to the said premises shall be and remain the property of the Government and may be removed or otherwise disposed of by the Government. If the lease contemplates that the Government is the sole occupant of the building, for purposes of this clause, the leased premises include the land on which the building is sited and the building itself. Otherwise, the Government shall have the right to tie into or make any physical connection with any structure located on the property as is reasonably necessary for appropriate utilization of the leased space.

INITIALS: LESSOR & GOVERNMENT

20. 552.270-29 ACCEPTANCE OF SPACE (SEP 1999) (VARIATION)

- When the Lessor has completed all alterations, improvements, and repairs necessary to meet the requirements of the lease, the Lessor shall notify the Contracting Officer. The Contracting Officer or designated representative shall promptly inspect the space.
- The Government will accept the space and the lease term will begin after determining that (b) the space is substantially complete and contains the required ANSI/BOMA Office Area square footage as indicated in the paragraph of this solicitation entitled "Amount and Type of Space.'

INSPECTION—RIGHT OF ENTRY (SEP 1999) 21. 552.270-9

- At any time and from time to time after receipt of an offer (until the same has been duly withdrawn or rejected), after acceptance thereof and during the term, the agents, employees and contractors of the Government may, upon reasonable prior notice to Offeror or Lessor, enter upon the offered premises or the premises, and all other areas of the building access to which is necessary to accomplish the purposes of entry, to determine the potential or actual compliance by the Offeror or Lessor with the requirements of the solicitation or this lease, which purposes shall include, but not be limited to:
 - (1) inspecting, sampling and analyzing of suspected asbestos-containing materials and air monitoring for asbestos fibers;

inspecting the heating, ventilation and air conditioning system, maintenance records, and mechanical rooms for the offered premises or the premises; inspecting for any leaks, spills, or other potentially hazardous conditions which may

involve tenant exposure to hazardous or toxic substances; and

inspecting for any current or past hazardous waste operations, to ensure that appropriate mitigative actions were taken to alleviate any environmentally unsound activities in accordance with Federal, State and local law.

(b) Nothing in this clause shall be construed to create a Government duty to inspect for toxic materials or to impose a higher standard of care on the Government than on other lessees. The purpose of this clause is to promote the ease with which the Government may inspect the building. Nothing in this clause shall act to relieve the Lessor of any duty to inspect or liability which might arise as a result of Lessor's failure to inspect for or correct a hazardous condition.

22. 52.204-7 **CENTRAL CONTRACTOR REGISTRATION (OCT 2003) (VARIATION)**

(a) Definitions. As used in this clause-

> "Central Contractor Registration (CCR) database" means the primary Government repository for Contractor information required for the conduct of business with the Government.

> "Data Universal Numbering System (DUNS) number" means the 9-digit number assigned by Dun and Bradstreet, Inc. (Ď&B) to identify unique business entities.

> "Data Universal Numbering System +4 (DUNS+4) number" means the DUNS number assigned by D&B plus a 4-character suffix that may be assigned by a business concern. (D&B has no affiliation with this 4-character suffix.) This 4-character suffix may be assigned at the discretion of the business concern to establish additional CCR records for identifying alternative Electronic Funds Transfer (EFT) accounts for the same parent concern.

> "Offeror" means the owner of the property offered, not an individual or agent representing the owner.

"Registered in the CCR database" means that-

- The Contractor has entered all mandatory information, including the DUNS number or the DUNS+4 number, into the CCR database; and
- (2) The Government has validated all mandatory data fields and has marked the record "Active."
- (1) By submission of an offer, the Offeror acknowledges the requirement that a (b) prospective awardee must be registered with D&B and in the CCR database prior to

GØVERNMENT

award, during performance, and through final payment of any contract resulting from this solicitation.

- The Offeror shall enter in the appropriate block, on the GSA Form 3518, entitled Representations and Certifications, the legal entity's name and address, followed by the DUNS or DUNS +4 number that identifies the Offeror's name and address exactly as stated in the offer. The DUNS number will be used by the Contracting Officer to verify that the Offeror is registered in the CCR database.
- If the Offeror does not have a DUNS number, it should contact Dun and Bradstreet directly (c) to obtain one.

(1) An Offeror may obtain a DUNS number-

- If located within the United States, by calling Dun and Bradstreet at 1-866-705-5711 or via the Internet at http://www.dnb.com; or
- If located outside the United States, by contacting the local Dun and Bradstreet office.
- The Offeror should be prepared to provide the following information:

Company legal business.

Tradestyle, doing business, or other name by which your entity is commonly recognized

Company Physical Street Address, City, State, and ZIP Code.

Company Mailing Address, City, State and ZIP Code (if separate from physical).

Company Telephone Number.

Date the company was started. Number of employees at your location. (vii)

Chief executive officer/key manager. (viii)

Line of business (industry).

- (x) Company Headquarters name and address (reporting relationship within your entity).
- If the Offeror does not become registered in the CCR database in the time prescribed by the (d) Contracting Officer, the Contracting Officer will proceed to award to the next otherwise successful registered Offeror.
- (e) Processing time, which normally takes 48 hours, should be taken into consideration when Offerors who are not registered should consider applying for registration immediately upon receipt of this solicitation.
- (f) The Contractor is responsible for the accuracy and completeness of the data within the CCR database, and for any liability resulting from the Government's reliance on inaccurate or incomplete data. To remain registered in the CCR database after the initial registration, the Contractor is required to review and update on an annual basis from the date of initial registration or subsequent updates its information in the CCR database to ensure it is current, accurate and complete. Updating information in the CCR does not alter the terms and conditions of this contract and is not a substitute for a properly executed contractual document.
- (i) If a Contractor has legally changed its business name, "doing business as" (g) (1) name, or division name (whichever is shown on the contract), or has name, or division name (whichever is snown on the contract), or has transferred the assets used in performing the contract, the Contractor shall comply with the requirements of Subpart 42.12 of the Federal Acquisition Regulations (FAR) and provide the responsible Contracting Officer a fully revised and initialed/signed GSA Form 3518, entitled Representations and Certifications, along with written notification of its intention to (A) change the name in the CCR database; and (B) provide the Contracting Officer with sufficient documentation to verify and confirm the legally changed name or sufficient documentation to verify and confirm the legally changed name or change in ownership.

If the Contractor fails to comply with the requirements of paragraph (g)(1)(i) of this clause, or fails to perform the agreement at paragraph (g)(1)(i)(C) of this clause, and, in the absence of a properly executed novation or change-of-name agreement, the CCR information that shows the Contractor to be other than the Contractor indicated in the contract will be considered to be incorrect information within the meaning of the "Suspension of Payment" paragraph of

the electronic funds transfer (EFT) clause of this contract.

GOVERNMENT

- (2) The Contractor shall not change the name or address for EFT payments or manual payments, as appropriate, in the CCR record to reflect an assignee for the purpose of assignment of claims. Assignees shall be separately registered in the CCR database. Information provided to the Contractor's CCR record that indicates payments, including those made by EFT, to an ultimate recipient other than that Contractor will be considered to be incorrect information.
- Offerors and Contractors may obtain information on registration and annual confirmation (h) requirements via the internet at http://www.ccr.gov or by calling 1-888-227-2423, or 269-961-5757.

23. 552.232-75 PROMPT PAYMENT (SEP 1999)

The Government will make payments under the terms and conditions specified in this clause. Payment shall be considered as being made on the day a check is dated or an electronic funds transfer is made. All days referred to in this clause are calendar days, unless otherwise specified.

- (a) Payment due date.
 - Rental payments. Rent shall be paid monthly in arrears and will be due on the first workday of each month, and only as provided for by the lease.
 - When the date for commencement of rent falls on the 15th day of the month or earlier, the initial monthly rental payment under this contract shall become due on the first workday of the month following the month in which the commencement of the rent is effective.
 - When the date for commencement of rent falls after the 15th day of the month, the initial monthly rental payment under this contract shall become due on the first workday of the second month following the month in which the commencement of the rent is effective.
 - Other payments. The due date for making payments other than rent shall be the later of the following two events:
 - The 30th day after the designated billing office has received a proper invoice
 - from the Contractor.

 The 30th day after Government acceptance of the work or service. However, if the designated billing office fails to annotate the invoice with the actual date of receipt, the invoice payment due date shall be deemed to be the 30th day after the Contractor's invoice is dated, provided a proper invoice is received and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.
- (b) Invoice and inspection requirements for payments other than rent.
 - The Contractor shall prepare and submit an invoice to the designated billing office after completion of the work. A proper invoice shall include the following items:
 - Name and address of the Contractor.
 - Invoice date.
 - (iii) Lease number.

GOVERNMENT

- Government's order number or other authorization. (iv)
- (v)
- Description, price, and quantity of work or services delivered.

 Name and address of Contractor official to whom payment is to be sent (must be the same as that in the remittance address in the lease or the order).
- (vii) Name (where practicable), title, phone number, and mailing address of person to be notified in the event of a defective invoice.
- The Government will inspect and determine the acceptability of the work performed or services delivered within 7 days after the receipt of a proper invoice or notification of completion of the work or services unless a different period is specified at the time the order is placed. If actual acceptance occurs later, for the purpose of determining the payment due date and calculation of interest, acceptance will be deemed to occur on the last day of the 7-day inspection period. If the work or service is rejected for failure to conform to the technical requirements of the contract, the 7 days will be counted beginning with receipt of a new invoice or notification. In either case, the Contractor is not entitled to any payment or interest unless actual acceptance by the Government occurs.

- (c) Interest Penalty.
 - (1) An interest penalty shall be paid automatically by the Government, without request from the Contractor, if payment is not made by the due date.
 - (2) The interest penalty shall be at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) that is in effect on the day after the due date. This rate is referred to as the "Renegotiation Board Interest Rate," and it is published in the *Federal Register* semiannually on or about January 1 and July 1. The interest penalty shall accrue daily on the payment amount approved by the Government and be compounded in 30-day increments inclusive from the first day after the due date through the payment date.
 - (3) Interest penalties will not continue to accrue after the filing of a claim for such penalties under the clause at 52.233-1, Disputes, or for more than 1 year. Interest penalties of less than \$1.00 need not be paid.
 - (4) Interest penalties are not required on payment delays due to disagreement between the Government and Contractor over the payment amount or other issues involving contract compliance or on amounts temporarily withheld or retained in accordance with the terms of the contract. Claims involving disputes, and any interest that may be payable, will be resolved in accordance with the clause at 52.233-1, Disputes.

24. 552.232-76 ELECTRONIC FUNDS TRANSFER PAYMENT (MAR 2000) (VARIATION)

- (a) The Government will make payments under this lease by electronic funds transfer (EFT). The Lessor must, no later than 30 days before the first payment:
 - (1) Designate a financial institution for receipt of EFT payments.
 - (2) Submit this designation to the Contracting Officer or other Government official, as directed.
- (b) The Lessor must provide the following information:
 - (1) The American Bankers Association 9-digit identifying number for Automated Clearing House (ACH) transfers of the financing institution receiving payment if the institution has access to the Federal Reserve Communications System.
 - (2) Number of account to which funds are to be deposited.
 - (3) Type of depositor account ("C" for checking, "S" for savings).
 - (4) If the Lessor is a new enrollee to the EFT system, the Lessor must complete and submit Form SF 3881, ACH Vendor/Miscellaneous Payment Enrollment Form, before payment can be processed.
- (c) If the Lessor, during the performance of this contract, elects to designate a different financial institution for the receipt of any payment, the appropriate Government official must receive notice of such change and the required information specified above no later than 30 days before the date such change is to become effective.
- (d) The documents furnishing the information required in this clause must be dated and contain the:
 - (1) Signature, title, and telephone number of the Lessor or the Lessor's authorized representative.
 - (2) Lessor's name.
 - (3) Lease number.
- (e) Lessor's failure to properly designate a financial institution or to provide appropriate payee bank account information may delay payments of amounts otherwise properly due.

NITIALS: LESSOR & GOVERNMENT

25. 552.232-70 INVOICE REQUIREMENTS (SEP 1999) (VARIATION)

(This clause is applicable to payments other than rent.)

- (a) Invoices shall be submitted in an original only, unless otherwise specified, to the designated billing office specified in this contract or order.
- (b) Invoices must include the Accounting Control Transaction (ACT) number provided below or on the order.

ACT Number (to be supplied on individual orders)

(c) If information or documentation in addition to that required by the Prompt Payment clause of this contract is required in connection with an invoice for a particular order, the order will indicate what information or documentation must be submitted.

26. 52.232-23 ASSIGNMENT OF CLAIMS (JAN 1986)

(Applicable to leases over \$2,500.)

- (a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 15 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.
- (b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.
- (c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

27. 552.270-20 PAYMENT (SEP 1999) (VARIATION)

- (a) When space is offered and accepted, the ANSI/BOMA Office Area square footage delivered will be confirmed by:
 - (1) the Government's measurement of plans submitted by the successful Offeror as approved by the Government, and an inspection of the space to verify that the delivered space is in conformance with such plans or
 - (2) a mutual on-site measurement of the space, if the Contracting Officer determines that it is necessary.
- (b) Payment will not be made for space which is in excess of the amount of ANSI/BOMA Office Area square footage stated in the lease.
- (c) If it is determined that the amount of ANSI/BOMA Office Area square footage actually delivered is less than the amount agreed to in the lease, the lease will be modified to reflect the amount of Usable space delivered and the annual rental will be adjusted as follows:

Usable square feet not delivered multiplied by the ANSI/BOMA Office Area square foot (USF) rate equals the reduction in annual rent. The rate per USF is determined by dividing the total annual rental by the Usable square footage set forth in the lease.

USF Not Delivered X Rate per USF = Reduction in Annual Rent.

28. 552.203-5 COVENANT AGAINST CONTINGENT FEES (FEB 1990)

(Applicable to leases over \$100,000.)

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to a null this contract without liability or, in its discretion, to deduct from

VITIALS A SOVERNMENT

the contract price or consideration, or otherwise recover the full amount of the contingent fee.

"Bona fide agency," as used in this clause, means an established commercial or selling (b) agency (including licensed real estate agents or brokers), maintained by a Contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

"Bona fide employee," as used in this clause, means a person, employed by a Contractor and subject to the Contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

"Contingent fee," as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

"Improper influence," as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

29. 52.203-7 **ANTI-KICKBACK PROCEDURES (JUL 1995)**

(Applicable to leases over \$100,000 average net annual rental, including option periods.)

Definitions.

"Kickback," as used in this clause, means any money, fee, commission, credit, gift, gratuity, thing of value, or compensation of any kind which is provided, directly or indirectly, to any prime Contractor, prime Contractor employee, subcontractor, or subcontractor employee for the purpose of improperly obtaining or rewarding favorable treatment in connection with a prime contract or in connection with a subcontract relating to a prime contract.

"Person," as used in this clause, means a corporation, partnership, business association of any kind, trust, joint-stock company, or individual.

"Prime contract," as used in this clause, means a contract or contractual action entered into by the United States for the purpose of obtaining supplies, materials, equipment, or services of any kind.

"Prime Contractor," as used in this clause, means a person who has entered into a prime contract with the United States.

"Prime Contractor employee," as used in this clause, means any officer, partner, employee, or agent of a prime Contractor.

"Subcontract," as used in this clause, means a contract or contractual action entered into by a prime Contractor or subcontractor for the purpose of obtaining supplies, materials, equipment, or services of any kind under a prime contract.

"Subcontractor," as used in this clause, (1) means any person, other than the prime Contractor, who offers to furnish or furnishes any supplies, materials, equipment, or services of any kind under a prime contract or a subcontract entered into in connection with such prime contract, and (2) includes any person who offers to furnish or furnishes general supplies to the prime Contractor or a higher tier subcontractor.

"Subcontractor employee," as used in this clause, means any officer, partner, employee, or agent of a subcontractor.

- The Anti-Kickback Act of 1986 (41 U.S.C. 51-58) (the Act), prohibits any person from-
 - Providing or attempting to provide or offering to provide any kickback;
 - Soliciting, accepting, or attempting to accept any kickback; or
 - Including, directly or indirectly, the amount of any kickback in the contract price

charged by a prime Contractor to the United States or in the contract price charged by a subcontractor to a prime Contractor or higher tier subcontractor.

- (c) (1) The Contractor shall have in place and follow reasonable procedures designed to prevent and detect possible violations described in paragraph (b) of this clause in its own operations and direct business relationships.
 - (2) When the Contractor has reasonable grounds to believe that a violation described in paragraph (b) of this clause may have occurred, the Contractor shall promptly report in writing the possible violation. Such reports shall be made to the inspector general of the contracting agency, the head of the contracting agency if the agency does not have an inspector general, or the Department of Justice.
 - (3) The Contractor shall cooperate fully with any Federal agency investigating a possible violation described in paragraph (b) of this clause.
 - (4) The Contracting Officer may (i) offset the amount of the kickback against any monies owed by the United States under the prime contract and/or (ii) direct that the Prime Contractor withhold from sums owed a subcontractor under the prime contract, the amount of the kickback. The Contracting Officer may order that monies withheld under subdivision (c)(4)(ii) of this clause be paid over to the Government unless the Government has already offset those monies under subdivision (c)(4)(i) of this clause. In either case, the Prime Contractor shall notify the Contracting Officer when the monies are withheld.
 - (5) The Contractor agrees to incorporate the substance of this clause, including paragraph (c)(5) but excepting paragraph (c)(1), in all subcontracts under this contract which exceed \$100,000.

30. 52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(a) Definitions. As used in this clause—

"Controlled substance" means a controlled substance in schedules I through V of section 202 of the Controlled Substances Act (21 U.S.C. 812) and as further defined in regulation at 21 CFR 1308.11 - 1308.15.

"Conviction" means a finding of guilt (including a plea of *nolo contendere*) or imposition of sentence, or both, by any judicial body charged with the responsibility to determine violations of the Federal or State criminal drug statutes.

"Criminal drug statute" means a Federal or non-Federal criminal statute involving the manufacture, distribution, dispensing, possession, or use of any controlled substance.

"Drug-free workplace" means the site(s) for the performance of work done by the Contractor in connection with a specific contract where employees of the Contractor are prohibited from engaging in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance.

"Employee" means an employee of a Contractor directly engaged in the performance of work under a Government contract. "Directly engaged" is defined to include all direct cost employees and any other Contractor employee who has other than a minimal impact or involvement in contract performance.

"Individual" means an Offeror/Contractor that has no more than one employee including the Offeror/Contractor.

- (b) The Contractor, if other than an individual, shall—within 30 days after award (unless a longer period is agreed to in writing for contracts of 30 days or more performance duration), or as soon as possible for contracts of less than 30 days performance duration—
 - (1) Publish a statement notifying its employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the Contractor's workplace and specifying the actions that will be taken against employees for violations of such prohibition;

NITIALS: LESSOR & GOVERNMENT

(2) Establish an ongoing drug-free awareness program to inform such employees about-

The dangers of drug abuse in the workplace;

The Contractor's policy of maintaining a drug-free workplace;

- Any available drug counseling, rehabilitation, and employee assistance programs; and
- The penalties that may be imposed upon employees for drug abuse violations occurring in the workplace:
- Provide all employees engaged in performance of the contract with a copy of the statement required by paragraph (b)(1) of this clause;
- Notify such employees in writing in the statement required by paragraph (b)(1) of this clause that, as a condition of continued employment on this contract, the employee will-

Abide by the terms of the statement; and

- Notify the employer in writing of the employee's conviction under a criminal drug statute for a violation occurring in the workplace no later than 5 days after such conviction;
- (5) Notify the Contracting Officer in writing within 10 days after receiving notice under subdivision (b)(4)(ii) of this clause, from an employee or otherwise receiving actual notice of such conviction. The notice shall include the position title of the employee;
- Within 30 days after receiving notice under subdivision (b)(4)(ii) of this clause of a conviction, take one of the following actions with respect to any employee who is convicted of a drug abuse violation occurring in the workplace:

Taking appropriate personnel action against such employee, up to and

including termination; or

- Require such employee to satisfactorily participate in a drug abuse assistance (ii) or rehabilitation program approved for such purposes by a Federal, State, or local health, law enforcement, or other appropriate agency; and
- Make a good faith effort to maintain a drug-free workplace through implementation of paragraphs (b)(1) through (b)(6) of this clause.
- (c) The Contractor, if an individual, agrees by award of the contract or acceptance of a purchase order, not to engage in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance while performing this contract.
- (d) In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of paragraph (b) or (c) of this clause may, pursuant to FAR 23.506, render the Contractor subject to suspension of contract payments, termination of the contract or default, and suspension or debarment.

31. 552.203-70 PRICE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (SEP 1999)

(Applicable to leases over \$100,000.)

- If the head of the contracting activity (HCA) or his or her designee determines that there was a violation of subsection 27(a) of the Office of Federal Procurement Policy Act, as amended (41 U.S.C. 423), as implemented in the Federal Acquisition Regulation, the Government, at its election, may-
 - Reduce the monthly rental under this lease by 5 percent of the amount of the rental for each month of the remaining term of the lease, including any option periods, and recover 5 percent of the rental already paid;
 - (2) Reduce payments for alterations not included in monthly rental payments by 5 percent of the amount of the alterations agreement; or
 - Reduce the payments for violations by a Lessor's subcontractor by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was placed.
- Prior to making a determination as set forth above, the HCA or designee shall provide to the Lessor a written notice of the action being considered and the basis therefor. The Lessor shall have a period determined by the agency head or designee, but not less than

GOVERNMENT

30 calendar days after receipt of such notice, to submit in person, in writing, or through a representative, information and argument in opposition to the proposed reduction. The agency head or designee may, upon good cause shown, determine to deduct less than the above amounts from payments.

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law or under this lease.

32. 52.215-10 PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA (OCT 1997)

(Applicable when cost or pricing data are required for work or services over \$500,000.)

- If any price, including profit or fee, negotiated in connection with this contract, or any cost reimbursable under this contract, was increased by any significant amount because-
 - The Contractor or a subcontractor furnished cost or pricing data that were not complete, accurate, and current as certified in its Certificate of Čurrent Cost or Pricing Data:
 - A subcontractor or prospective subcontractor furnished the Contractor cost or pricing data that were not complete, accurate, and current as certified in the Contractor's Certificate of Current Cost or Pricing Data; or
 - Any of these parties furnished data of any description that were not accurate, the price or cost shall be reduced accordingly and the contract shall be modified to reflect the reduction.
- (b) Any reduction in the contract price under paragraph (a) of this clause due to defective data from a prospective subcontractor that was not subsequently awarded the subcontract shall be limited to the amount, plus applicable overhead and profit markup, by which-

The actual subcontract or

- The actual cost to the Contractor, if there was no subcontract, was less than the prospective subcontract cost estimate submitted by the Contractor; provided, that the actual subcontract price was not itself affected by defective cost or pricing data.
- (c) If the Contracting Officer determines under paragraph (a) of this clause that a price or cost reduction should be made, the Contractor agrees not to raise the following matters as a defense:
 - The Contractor or subcontractor was a sole source supplier or otherwise was in a superior bargaining position and thus the price of the contract would not have been modified even if accurate, complete, and current cost or pricing data had been submitted.
 - The Contracting Officer should have known that the cost or pricing data in issue were defective even though the Contractor or subcontractor took no affirmative action to bring the character of the data to the attention of the Contracting Officer
 - The contract was based on an agreement about the total cost of the contract and there was no agreement about the cost of each item procured under the contract
 - The Contractor or subcontractor did not submit a Certificate of Current Cost or Pricing Data.
 - (2)Except as prohibited by subdivision (c)(2)(ii) of this clause, an offset in an amount determined appropriate by the Contracting Officer based upon the facts shall be allowed against the amount of a contract price reduction if-

The Contractor certifies to the Contracting Officer that, to the best of the Contractor's knowledge and belief, the Contractor is entitled to the offset in the amount requested; and

(B) The Contractor proves that the cost or pricing data were available before the "as of" date specified on its Certificate of Current Cost or Pricing Data, and that the data were not submitted before such date.

An offset shall not be allowed if-

ØOVERNMENT

The understated data were known by the Contractor to be understated before the "as of" date specified on its Certificate of Current Cost or Pricing Data: or

(B) The Government proves that the facts demonstrate that the contract price would not have increased in the amount to be offset even if the

106

GSA FORM 3517B PAGE 16 (REV 06/08)

available data had been submitted before the "as of" date specified on its Certificate of Current Cost or Pricing Data.

- (d) If any reduction in the contract price under this clause reduces the price of items for which payment was made prior to the date of the modification reflecting the price reduction, the Contractor shall be liable to and shall pay the United States at the time such overpayment is repaid—
 - (1) Simple interest on the amount of such overpayment to be computed from the date(s) of overpayment to the Contractor to the date the Government is repaid by the Contractor at the applicable underpayment rate effective for each quarter prescribed by the Secretary of the Treasury under 26 U.S.C. 6621(a)(2); and
 - (2) A penalty equal to the amount of the overpayment, if the Contractor or subcontractor knowingly submitted cost or pricing data that were incomplete, inaccurate, or noncurrent.

33. 552.270-13 PROPOSALS FOR ADJUSTMENT (SEP 1999)

- (a) The Contracting Officer may, from time to time during the term of this lease, require changes to be made in the work or services to be performed and in the terms or conditions of this lease. Such changes will be required under the Changes clause.
- (b) If the Contracting Officer makes a change within the general scope of the lease, the Lessor shall submit, in a timely manner, an itemized cost proposal for the work to be accomplished or services to be performed when the cost exceeds \$100,000. The proposal, including all subcontractor work, will contain at least the following detail—
 - (1) Material quantities and unit costs:
 - Labor costs (identified with specific item or material to be placed or operation to be performed;
 - (3) Equipment costs;
 - (4) Worker's compensation and public liability insurance;
 - (5) Overhead;
 - (6) Profit; and
 - (7) Employment taxes under FICA and FUTA.
- (c) The following Federal Acquisition Regulation (FAR) provisions also apply to all proposals exceeding \$500,000 in cost—
 - The Lessor shall provide cost or pricing data including subcontractor cost or pricing data (48 CFR 15.403-4) and
 - (2) The Lessor's representative, all Contractors, and subcontractors whose portion of the work exceeds \$500,000 must sign and return the "Certificate of Current Cost or Pricing Data" (48 CFR 15.406-2).
- (d) Lessors shall also refer to 48 CFR Part 31, Contract Cost Principles, for information on which costs are allowable, reasonable, and allocable in Government work.

34. 552.270-14 CHANGES (SEP 1999) (VARIATION)

- (a) The Contracting Officer may at any time, by written order, make changes within the general scope of this lease in any one or more of the following:
 - (1) Specifications (including drawings and designs);
 - (2) Work or services:
 - (3) Facilities or space layout; or

INITIALS LESSOR & GOVERNMENT

- (4) Amount of space, provided the Lessor consents to the change.
- (b) If any such change causes an increase or decrease in Lessor's cost of or the time required for performance under this lease, whether or not changed by the order, the Contracting Officer shall modify this lease to provide for one or more of the following:
 - (1) A modification of the delivery date;
 - (2) An equitable adjustment in the rental rate;
 - (3) A lump sum equitable adjustment; or
 - (4) An equitable adjustment of the annual operating costs per ANSI/BOMA Office Area square foot specified in this lease.
- (c) The Lessor shall assert its right to an adjustment under this clause within 30 days from the date of receipt of the change order and shall submit a proposal for adjustment. Failure to agree to any adjustment shall be a dispute under the Disputes clause. However, nothing in this clause shall excuse the Lessor from proceeding with the change as directed.
- (d) Absent such written change order, the Government shall not be liable to Lessor under this clause.

35. 552.215-70 EXAMINATION OF RECORDS BY GSA (FEB 1996)

The Contractor agrees that the Administrator of General Services or any duly authorized representative shall, until the expiration of 3 years after final payment under this contract, or of the time periods for the particular records specified in Subpart 4.7 of the Federal Acquisition Regulation (48 CFR 4.7), whichever expires earlier, have access to and the right to examine any books, documents, papers, and records of the Contractor involving transactions related to this contract or compliance with any clauses thereunder. The Contractor further agrees to include in all its subcontracts hereunder a provision to the effect that the subcontractor agrees that the Administrator of General Services or any duly authorized representatives shall, until the expiration of 3 years after final payment under the subcontract, or of the time periods for the particular records specified in Subpart 4.7 of the Federal Acquisition Regulation (48 CFR 4.7), whichever expires earlier, have access to and the right to examine any books, documents, papers, and records of such subcontractor involving transactions related to the subcontract or compliance with any clauses thereunder. The term "subcontract" as used in this clause excludes (a) purchase orders not exceeding \$100,000 and (b) subcontracts or purchase orders for public utility services at rates established for uniform applicability to the general public.

36. 52.215-2 AUDIT AND RECORDS—NEGOTIATION (JUN 1999)

- (a) As used in this clause, "records" includes books, documents, accounting procedures and practices, and other data, regardless of type and regardless of whether such items are in written form, in the form of computer data, or in any other form.
- (b) Examination of costs. If this is a cost-reimbursement, incentive, time-and-materials, labor-hour, or price redeterminable contract, or any combination of these, the Contractor shall maintain and the Contracting Officer, or an authorized representative of the Contracting Officer, shall have the right to examine and audit all records and other evidence sufficient to reflect properly all costs claimed to have been incurred or anticipated to be incurred directly or indirectly in performance of this contract. This right of examination shall include inspection at all reasonable times of the Contractor's plants, or parts of them, engaged in performing the contract.
- (c) Cost or pricing data. If the Contractor has been required to submit cost or pricing data in connection with any pricing action relating to this contract, the Contracting Officer, or an authorized representative of the Contracting Officer, in order to evaluate the accuracy, completeness, and currency of the cost or pricing data, shall have the right to examine and audit all of the Contractor's records, including computations and projections, related to—
 - (1) The proposal for the contract, subcontract, or modification;
 - (2) The discussions conducted on the proposal(s), including those related to negotiating;
 - (3) Pricing of the contract, subcontract, or modification; or

INITIALS: 15 A SOVÉRNMENT

- (4) Performance of the contract, subcontract or modification.
- (d) Comptroller General.
 - (1) The Comptroller General of the United States, or an authorized representative, shall have access to and the right to examine any of the Contractor's directly pertinent records involving transactions related to this contract or a subcontract hereunder.
 - (2) This paragraph may not be construed to require the Contractor or subcontractor to create or maintain any record that the Contractor or subcontractor does not maintain in the ordinary course of business or pursuant to a provision of law.
- (e) Reports. If the Contractor is required to furnish cost, funding, or performance reports, the Contracting Officer or an authorized representative of the Contracting Officer shall have the right to examine and audit the supporting records and materials, for the purpose of evaluating—
 - (1) The effectiveness of the Contractor's policies and procedures to produce data compatible with the objectives of these reports; and
 - (2) The data reported.
- (f) Availability. The Contractor shall make available at its office at all reasonable times the records, materials, and other evidence described in paragraphs (a), (b), (c), (d), and (e) of this clause, for examination, audit, or reproduction, until 3 years after final payment under this contract or for any shorter period specified in Subpart 4.7, Contractor Records Retention, of the Federal Acquisition Regulation (FAR), or for any longer period required by statute or by other clauses of this contract. In addition—
 - If this contract is completely or partially terminated, the Contractor shall make available the records relating to the work terminated until 3 years after any resulting final termination settlement; and
 - (2) The Contractor shall make available records relating to appeals under the Disputes clause or to litigation or the settlement of claims arising under or relating to this contract until such appeals, litigation, or claims are finally resolved.
- (g) The Contractor shall insert a clause containing all the terms of this clause, including this paragraph (g), in all subcontracts under this contract that exceed the simplified acquisition threshold, and—
 - (1) That are cost-reimbursement, incentive, time-and-materials, labor-hour, or price-redeterminable type or any combination of these;
 - (2) For which cost or pricing data are required; or
 - (3) That require the subcontractor to furnish reports as discussed in paragraph (e) of this clause.

The clause may be altered only as necessary to identify properly the contracting parties and the Contracting Officer under the Government prime contract.

37. 52.233-1 DISPUTES (JUL 2002)

- (a) This contract is subject to the Contract Disputes Act of 1978, as amended (41 U.S.C. 601-613).
- (b) Except as provided in the Act, all disputes arising under or relating to this contract shall be resolved under this clause.
- (c) "Claim," as used in this clause, means a written demand or written assertion by one of the contracting parties seeking, as a matter of right, the payment of money in a sum certain, the adjustment or interpretation of contract terms, or other relief arising under or relating to this contract. However, a written demand or written assertion by the Contractor seeking the payment of money exceeding \$100,000 is not a claim under the Act until certified. A voucher, invoice, of other routine request for payment that is not in dispute when submitted

INITIALS

EDNIMENT.

is not a claim under the Act. The submission may be converted to a claim under the Act, by complying with the submission and certification requirements of this clause, if it is disputed either as to liability or amount or is not acted upon in a reasonable time.

- (d) (1) A claim by the Contractor shall be made in writing and, unless otherwise stated in this contract, submitted within 6 years after accrual of the claim to the Contracting Officer for a written decision. A claim by the Government against the Contractor shall be subject to a written decision by the Contracting Officer.
 - (2) (i) The Contractor shall provide the certification specified in paragraph (d)(2)(iii) of this clause when submitting any claim exceeding \$100,000.

ii) The certification requirement does not apply to issues in controversy that have

not been submitted as all or part of a claim.

- (iii) The certification shall state as follows: "I certify that the claim is made in good faith; that the supporting data are accurate and complete to the best of my knowledge and belief; that the amount requested accurately reflects the contract adjustment for which the Contractor believes the Government is liable; and that I am duly authorized to certify the claim on behalf of the Contractor."
- (3) The certification may be executed by any person duly authorized to bind the Contractor with respect to the claim.
- (e) For Contractor claims of \$100,000 or less, the Contracting Officer must, if requested in writing by the Contractor, render a decision within 60 days of the request. For Contractorcertified claims over \$100,000, the Contracting Officer must, within 60 days, decide the claim or notify the Contractor of the date by which the decision will be made.
- (f) The Contracting Officer's decision shall be final unless the Contractor appeals or files a suit as provided in the Act.
- (g) If the claim by the Contractor is submitted to the Contracting Officer or a claim by the Government is presented to the Contractor, the parties, by mutual consent, may agree to use alternative dispute resolution (ADR). If the Contractor refuses an offer for ADR, the Contractor shall inform the Contracting Officer, in writing, of the Contractor's specific reasons for rejecting the offer.
- (h) The Government shall pay interest on the amount found due and unpaid from (1) the date that the Contracting Officer receives the claim (certified, if required); or (2) the date that payment otherwise would be due, if that date is later, until the date of payment. With regard to claims having defective certifications, as defined in FAR 33.201, interest shall be paid from the date that the Contracting Officer initially receives the claim. Simple interest on claims shall be paid at the rate, fixed by the Secretary of the Treasury as provided in the Act, which is applicable to the period during which the Contracting Officer receives the claim and then at the rate applicable for each 6-month period as fixed by the Treasury Secretary during the pendency of the claim.
- (i) The Contractor shall proceed diligently with performance of this contract, pending final resolution of any request for relief, claim, appeal, or action arising under the contract, and comply with any decision of the Contracting Officer.

38. 52.222-26 EQUAL OPPORTUNITY (APR 2002)

(Applicable to leases over \$10,000.)

- (a) Definition. "United States," as used in this clause, means the 50 States, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, the U.S. Virgin Islands, and Wake Island.
- (b) If, during any 12-month period (including the 12 months preceding the award of this contract), the Contractor has been or is awarded nonexempt Federal contracts and/or subcontracts that have an aggregate value in excess of \$10,000, the Contractor shall comply with paragraphs (b)(1) through (b)(11) of this clause, except for work performed outside the United States by employees who were not recruited within the United States. Upon request, the Contractor shall provide information necessary to determine the applicability of this clause.

(1) The Contractor shall not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. However, it shall

INITIALS MESSOR & GOVERNMENT

not be a violation of this clause for the Contractor to extend a publicly announced preference in employment to Indians living on or near an Indian reservation, in connection with employment opportunities on or near an Indian reservation, as permitted by 41 CFR 60-1.5.

(2) The Contractor shall take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex, or national origin. This shall include, but not be limited to—

(i) Employment;(ii) Upgrading;

- (iii) Demotion; (iv) Transfer:
- (iv) Transfer;
- (v) Recruitment or recruitment advertising;

(vi) Layoff or termination;

- (vii) Rates of pay or other forms of compensation; and
- (viii) Selection for training, including apprenticeship.
- (3) The Contractor shall post in conspicuous places available to employees and applicants for employment the notices to be provided by the Contracting Officer that explain this clause.
- (4) The Contractor shall, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, or national origin.
- (5) The Contractor shall send, to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding, the notice to be provided by the Contracting Officer advising the labor union or workers' representative of the Contractor's commitments under this clause, and post copies of the notice in conspicuous places available to employees and applicants for employment.
- (6) The Contractor shall comply with Executive Order 11246, as amended, and the rules, regulations, and orders of the Secretary of Labor.
- (7) The Contractor shall furnish to the contracting agency all information required by Executive Order 11246, as amended, and by the rules, regulations, and orders of the Secretary of Labor. The Contractor shall also file Standard Form 100, (EEO-1), or any successor form, as prescribed in 41 CFR part 60-1. Unless the Contractor has filed within the 12 months preceding the date of contract award, the Contractor shall, within 30 days after contract award, apply to either the regional Office of Federal Contract Compliance Programs (OFCCP) or the local office of the Equal Employment Opportunity Commission for the necessary forms.
- (8) The Contractor shall permit access to its premises, during normal business hours, by the contracting agency or the OFCCP for the purpose of conducting on-site compliance evaluations and complaint investigations. The Contractor shall permit the Government to inspect and copy any books, accounts, records (including computerized records), and other material that may be relevant to the matter under investigation and pertinent to compliance with Executive Order 11246, as amended, and rules and regulations that implement the Executive Order.
- (9) If the OFCCP determines that the Contractor is not in compliance with this clause or any rule, regulation, or order of the Secretary of Labor, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts, under the procedures authorized in Executive Order 11246, as amended. In addition, sanctions may be imposed and remedies invoked against the Contractor as provided in Executive Order 11246, as amended; in the rules, regulations, and orders of the Secretary of Labor; or as otherwise provided by law.
- (10) The Contractor shall include the terms and conditions of paragraphs (b)(1) through (11) of this clause in every subcontract or purchase order that is not exempted by the rules, regulations, or orders of the Secretary of Labor issued under Executive Order 11246, as amended, so that these terms and conditions will be binding upon each subcontractor or vendor.

(11) The Contractor shall take such action with respect to any subcontract or purchase

INITIALS: LESSOR & GOVERNMENT

order as the Contracting Officer may direct as a means of enforcing these terms and conditions, including sanctions for noncompliance, provided, that if the Contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of any direction, the Contractor may request the United States to enter into the litigation to protect the interests of the United States.

(c) Notwithstanding any other clause in this contract, disputes relative to this clause will be governed by the procedures in 41 CFR 60-1.1.

39. 52.222-24 PREAWARD ON-SITE EQUAL OPPORTUNITY COMPLIANCE EVALUATION (FEB 1999)

(Applicable to leases over \$10,000,000.)

If a contract in the amount of \$10 million or more will result from this solicitation, the prospective Contractor and its known first-tier subcontractors with anticipated subcontracts of \$10 million or more shall be subject to a preaward compliance evaluation by the Office of Federal Contract Compliance Programs (OFCCP), unless, within the preceding 24 months, OFCCP has conducted an evaluation and found the prospective Contractor and subcontractors to be in compliance with Executive Order 11246.

40. 52.222-21 PROHIBITION OF SEGREGATED FACILITIES (FEB 1999)

(Applicable to leases over \$10,000.)

- (a) "Segregated facilities," as used in this clause, means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees, that are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, or national origin because of written or oral policies or employee custom. The term does not include separate or single-user rest rooms or necessary dressing or sleeping areas provided to assure privacy between the sexes.
- (b) The Contractor agrees that it does not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Contractor agrees that a breach of this clause is a violation of the Equal Opportunity clause in this contract.
- (c) The Contractor shall include this clause in every subcontract and purchase order that is subject to the Equal Opportunity clause of this contract.

41. 52.222-35 EQUAL OPPORTUNITY FOR SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)

(Applicable to leases over \$25,000.)

(a) Definitions. As used in this clause—

"All employment openings" means all positions except executive and top management, those positions that will be filled from within the Contractor's organization, and positions lasting 3 days or less. This term includes full-time employment, temporary employment of more than 3 days duration, and part-time employment.

"Executive and top management" means any employee--

- (1) Whose primary duty consists of the management of the enterprise in which the individual is employed or of a customarily recognized department or subdivision thereof;
- (2) Who customarily and regularly directs the work of two or more other employees;
- (3) Who has the authority to hire or fire other employees or whose suggestions and recommendations as to the hiring or firing and as to the advancement and promotion or any other change of status of other employees will be given particular weight;
- (4) Who customarily and regularly exercises discretionary powers; and

INITIALS LESSOR & GOVERNMENT 112

(5) Who does not devote more than 20 percent or, in the case of an employee of a retail or service establishment, who does not devote more than 40 percent of total hours of work in the work week to activities that are not directly and closely related to the performance of the work described in paragraphs (1) through (4) of this definition. This paragraph (5) does not apply in the case of an employee who is in sole charge of an establishment or a physically separated branch establishment, or who owns at least a 20 percent interest in the enterprise in which the individual is employed.

"Other eligible veteran" means any other veteran who served on active duty during a war or in a campaign or expedition for which a campaign badge has been authorized.

"Positions that will be filled from within the Contractor's organization" means employment openings for which the Contractor will give no consideration to persons outside the Contractor's organization (including any affiliates, subsidiaries, and parent companies) and includes any openings the Contractor proposes to fill from regularly established "recall" lists. The exception does not apply to a particular opening once an employer decides to consider applicants outside of its organization.

"Qualified special disabled veteran" means a special disabled veteran who satisfies the requisite skill, experience, education, and other job-related requirements of the employment position such veteran holds or desires, and who, with or without reasonable accommodation, can perform the essential functions of such position.

"Special disabled veteran" means—

(1) A veteran who is entitled to compensation (or who but for the receipt of military retired pay would be entitled to compensation) under laws administered by the Department of Veterans Affairs for a disability-

Rated at 30 percent or more; or

- Rated at 10 or 20 percent in the case of a veteran who has been determined under 38 U.S.C. 3106 to have a serious employment handicap (i.e., a significant impairment of the veteran's ability to prepare for, obtain, or retain employment consistent with the veteran's abilities, aptitudes, and interests); or
- (2) A person who was discharged or released from active duty because of a service-connected disability.

"Veteran of the Vietnam era" means a person who-

(1) Served on active duty for a period of more than 180 days and was discharged or released from active duty with other than a dishonorable discharge, if any part of such active duty occurred-

(i) In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

Between August 5, 1964, and May 7, 1975, in all other cases; or

Was discharged or released from active duty for a service-connected disability if any part of the active duty was performed-

In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

Between August 5, 1964, and May 7, 1975, in all other cases.

(b) General.

The Contractor shall not discriminate against the individual because the individual is a special disabled veteran, a veteran of the Vietnam era, or other eligible veteran, regarding any position for which the employee or applicant for employment is qualified. The Contractor shall take affirmative action to employ, advance in employment, and otherwise treat qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans without discrimination based upon their disability or veterans' status in all employment practices such as-

Recruitment, advertising, and job application procedures;

- Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff and rehiring;
 Rate of pay or any other form of compensation and changes in compensation;
- Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;

Leaves of absence, sick leave, or any other leave;

GOVERNMENT

- Fringe benefits available by virtue of employment, whether or not administered by the Contractor;
 - Selection and financial support for training, including apprenticeship, and onthe-job training under 38 U.S.C. 3687, professional meetings, conferences, and

- other related activities, and selection for leaves of absence to pursue training;
- (viii) Activities sponsored by the Contractor including social or recreational programs; and
- (ix) Any other term, condition, or privilege of employment.
- (2) The Contractor shall comply with the rules, regulations, and relevant orders of the Secretary of Labor issued under the Vietnam Era Veterans' Readjustment Assistance Act of 1972 (the Act), as amended (38 U.S.C. 4211 and 4212).

(c) Listing openings.

- (1) The Contractor shall immediately list all employment openings that exist at the time of the execution of this contract and those which occur during the performance of this contract, including those not generated by this contract, and including those occurring at an establishment of the Contractor other than the one where the contract is being performed, but excluding those of independently operated corporate affiliates, at an appropriate local public employment service office of the State wherein the opening occurs. Listing employment openings with the U.S. Department of Labor's America's Job Bank shall satisfy the requirement to list jobs with the local employment service office.
- (2) The Contractor shall make the listing of employment openings with the local employment service office at least concurrently with using any other recruitment source or effort and shall involve the normal obligations of placing a bona fide job order, including accepting referrals of veterans and nonveterans. This listing of employment openings does not require hiring any particular job applicant or hiring from any particular group of job applicants and is not intended to relieve the Contractor from any requirements of Executive orders or regulations concerning nondiscrimination in employment.
- (3) Whenever the Contractor becomes contractually bound to the listing terms of this clause, it shall advise the State public employment agency in each State where it has establishments of the name and location of each hiring location in the State. As long as the Contractor is contractually bound to these terms and has so advised the State agency, it need not advise the State agency of subsequent contracts. The Contractor may advise the State agency when it is no longer bound by this contract clause.
- (d) Applicability. This clause does not apply to the listing of employment openings that occur and are filled outside the 50 States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, American Samoa, Guam, the Virgin Islands of the United States, and Wake Island.

(e) Postings.

- (1) The Contractor shall post employment notices in conspicuous places that are available to employees and applicants for employment.
- (2) The employment notices shall—
 - (i) State the rights of applicants and employees as well as the Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified employees and applicants who are special disabled veterans, veterans of the Vietnam era, and other eligible veterans; and
 - (ii) Be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance Programs, Department of Labor (Deputy Assistant Secretary of Labor), and provided by or through the Contracting Officer.
- (3) The Contractor shall ensure that applicants or employees who are special disabled veterans are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled veteran, or may lower the posted notice so that it can be read by a person in a wheelchair).
- (4) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement, or other contract understanding, that the Contractor is bound by the terms of the Act and is committed to take affirmative action to employ, and advance in employment, qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans.

INITIALS: LESSOR & GOVERNMENT

- (f) Noncompliance. If the Contractor does not comply with the requirements of this clause, the Government may take appropriate actions under the rules, regulations, and relevant orders of the Secretary of Labor issued pursuant to the Act.
- Subcontracts. The Contractor shall insert the terms of this clause in all subcontracts or purchase orders of \$25,000 or more unless exempted by rules, regulations, or orders of the (g) Secretary of Labor. The Contractor shall act as specified by the Deputy Assistant Secretary of Labor to enforce the terms, including action for noncompliance.

42. 52.222-36 AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (JUN 1998)

(Applicable to leases over \$10,000.)

- (a) General.
 - Regarding any position for which the employee or applicant for employment is qualified, the Contractor shall not discriminate against any employee or applicant because of physical or mental disability. The Contractor agrees to take affirmative action to employ, advance in employment and otherwise treat qualified individuals with disabilities without discrimination based upon their physical or mental disability in all employment practices such as-

Recruitment, advertising, and job application procedures;

- Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff, and rehiring;
- Rates of pay or any other form of compensation and changes in compensation;
- Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;

Leaves of absence, sick leave, or any other leave;

- Fringe benefits available by virtue of employment, whether or not administered (vi) by the Contractor;
- Selection and financial support for training, including apprenticeships, professional meetings, conferences, and other related activities, and selection (vii) for leaves of absence to pursue training;
- (viii) Activities sponsored by the Contractor, including social or recreational programs: and
- (ix) Any other term, condition, or privilege of employment.
- The Contractor agrees to comply with the rules, regulations, and relevant orders of the Secretary of Labor (Secretary) issued under the Rehabilitation Act of 1973 (29 U.S.C. 793) (the Act), as amended.

(b) Postings.

- The Contractor agrees to post employment notices stating
 - the Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified individuals with disabilities and
 - (ii) the rights of applicants and employees.
- (2) These notices shall be posted in conspicuous places that are available to employees and applicants for employment. The Contractor shall ensure that applicants and employees with disabilities are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled individual, or may lower the posted notice so that it might be read by a person in a wheelchair). The notices shall be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance of the U.S. Department of Labor (Deputy Assistant Secretary) and shall be provided by or through the Contracting Officer.
- The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement or other contract understanding, that the Contractor is bound by the terms of Section 503 of the Act and is committed to take affirmative action to employ, and advance in employment, qualified individuals with physical or mental disabilities.
- (c) Noncompliance. If the Contractor does not comply with the requirements of this clause, appropriate actions may be taken under the rules, regulations, and relevant orders of the Secretary issued pursuant to the Act.

(d) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of \$10,000 unless exempted by rules, regulations, or orders of the Secretary. The Contractor shall act as specified by the Deputy Assistant Secretary to enforce the terms, including action for noncompliance.

43. 52.222-37 EMPLOYMENT REPORTS ON SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)

(Applicable to leases over \$25,000.)

- (a) Unless the Contractor is a State or local government agency, the Contractor shall report at least annually, as required by the Secretary of Labor, on—
 - (1) The number of special disabled veterans, the number of veterans of the Vietnam era, and other eligible veterans in the workforce of the Contractor by job category and hiring location; and
 - (2) The total number of new employees hired during the period covered by the report, and of the total, the number of special disabled veterans, the number of veterans of the Vietnam era, and the number of other eligible veterans; and
 - (3) The maximum number and the minimum number of employees of the Contractor during the period covered by the report.
- (b) The Contractor shall report the above items by completing the Form VETS-100, entitled "Federal Contractor Veterans' Employment Report (VETS-100 Report)."
- (c) The Contractor shall submit VETS-100 Reports no later than September 30 of each year beginning September 30, 1988.
- (d) The employment activity report required by paragraph (a)(2) of this clause shall reflect total hires during the most recent 12-month period as of the ending date selected for the employment profile report required by paragraph (a)(1) of this clause. Contractors may select an ending date—
 - As of the end of any pay period between July 1 and August 31 of the year the report is due; or
 - (2) As of December 31, if the Contractor has prior written approval from the Equal Employment Opportunity Commission to do so for purposes of submitting the Employer Information Report EEO-1 (Standard Form 100).
- (e) The Contractor shall base the count of veterans reported according to paragraph (a) of this clause on voluntary disclosure. Each Contractor subject to the reporting requirements at 38 U.S.C. 4212 shall invite all special disabled veterans, veterans of the Vietnam era, and other eligible veterans who wish to benefit under the affirmative action program at 38 U.S.C. 4212 to identify themselves to the Contractor. The invitation shall state that—
 - (1) The information is voluntarily provided;
 - (2) The information will be kept confidential;
 - (3) Disclosure or refusal to provide the information will not subject the applicant or employee to any adverse treatment; and
 - (4) The information will be used only in accordance with the regulations promulgated under 38 U.S.C. 4212.
- (f) The Contractor shall insert the terms of this clause in all subcontracts or purchase orders of \$25,000 or more unless exempted by rules, regulations, or orders of the Secretary of Labor.

INITIALS LESSOR & OVERNMENT

44. 52.209-6 PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (JAN 2005)

(Applicable to leases over \$25,000.)

- (a) The Government suspends or debars Contractors to protect the Government's interests. The Contractor shall not enter into any subcontract in excess of \$25,000 with a Contractor that is debarred, suspended, or proposed for debarment unless there is a compelling reason to do so.
- (b) The Contractor shall require each proposed first-tier subcontractor, whose subcontract will exceed \$25,000, to disclose to the Contractor, in writing, whether as of the time of award of the subcontract, the subcontractor, or its principals, is or is not debarred, suspended, or proposed for debarment by the Federal Government
- (c) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party that is debarred, suspended, or proposed for debarment (see FAR 9.404 for information on the Excluded Parties List System). The notice must include the following:
 - (1) The name of the subcontractor.
 - (2) The Contractor's knowledge of the reasons for the subcontractor being in the Excluded Parties List System.
 - (3) The compelling reason(s) for doing business with the subcontractor notwithstanding its inclusion in the Excluded Parties List System.
 - (4) The systems and procedures the Contractor has established to ensure that it is fully protecting the Government's interests when dealing with such subcontractor in view of the specific basis for the party's debarment, suspension, or proposed debarment.

45. 52.215-12 SUBCONTRACTOR COST OR PRICING DATA (OCT 1997)

(Applicable when the clause at FAR 52.215-10 is applicable.)

- (a) Before awarding any subcontract expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4, on the date of agreement on price or the date of award, whichever is later; or before pricing any subcontract modification involving a pricing adjustment expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4, the Contractor shall require the subcontractor to submit cost or pricing data (actually or by specific identification in writing), unless an exception under FAR 15.403-1 applies.
- (b) The Contractor shall require the subcontractor to certify in substantially the form prescribed in FAR 15.406-2 that, to the best of its knowledge and belief, the data submitted under paragraph (a) of this clause were accurate, complete, and current as of the date of agreement on the negotiated price of the subcontract or subcontract modification.
- (c) In each subcontract that exceeds the threshold for submission of cost or pricing data at FAR 15.403-4, when entered into, the Contractor shall insert either—
 - (1) The substance of this clause, including this paragraph (c), if paragraph (a) of this clause requires submission of cost or pricing data for the subcontract; or
 - (2) The substance of the clause at FAR 52.215-13, Subcontractor Cost or Pricing Data— Modifications.

46. 52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (MAY 2004)

(Applicable to leases over \$100,000 average net annual rental, including option periods.)

(a) It is the policy of the United States that small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns shall have the maximum practicable opportunity to participate in performing contracts let by any Federal agency, including contracts and subcontracts for subsystems, assemblies, components, and related services for major systems. It is further

INITIALS: LESSOR & JEV.

the policy of the United States that its prime contractors establish procedures to ensure the timely payment of amounts due pursuant to the terms of their subcontracts with small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns.

- (b) The Contractor hereby agrees to carry out this policy in the awarding of subcontracts to the fullest extent consistent with efficient contract performance. The Contractor further agrees to cooperate in any studies or surveys as may be conducted by the United States Small Business Administration or the awarding agency of the United States as may be necessary to determine the extent of the Contractor's compliance with this clause.
- (c) Definitions. As used in this contract—

"HUBZone small business concern" means a small business concern that appears on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration.

"Service-disabled veteran-owned small business concern"—

(1) Means a small business concern-

- Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and
- (ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a service-disabled veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.
- (2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

"Small business concern" means a small business as defined pursuant to Section 3 of the Small Business Act and relevant regulations promulgated pursuant thereto.

"Small disadvantaged business concern" means a small business concern that represents, as part of its offer that—

- It has received certification as a small disadvantaged business concern consistent with 13 CFR part 124, Subpart B;
- (2) No material change in disadvantaged ownership and control has occurred since its certification;
- (3) Where the concern is owned by one or more individuals, the net worth of each individual upon whom the certification is based does not exceed \$750,000 after taking into account the applicable exclusions set forth at 13 CFR 124.104(c)(2); and
- (4) It is identified, on the date of its representation, as a certified small disadvantaged business in the database maintained by the Small Business Administration (PRO-Net).

"Veteran-owned small business concern" means a small business concern—

- (1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and
- (2) The management and daily business operations of which are controlled by one or more veterans.

"Women-owned small business concern" means a small business concern—

(1) That is at least 51 percent owned by one or more women, or, in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

INITIALS: LESSOR & GOVERNMENT

- (2) Whose management and daily business operations are controlled by one or more women.
- (d) Contractors acting in good faith may rely on written representations by their subcontractors regarding their status as a small business concern, a veteran-owned small business concern, a service-disabled veteran-owned small business concern, a HUBZone small business concern, a small disadvantaged business concern, or a women-owned small business concern.

47. 52.219-9 SMALL BUSINESS SUBCONTRACTING PLAN (JUL 2005)

(Applicable to leases over \$500,000.)

- (a) This clause does not apply to small business concerns.
- (b) Definitions. As used in this clause-

"Commercial item" means a product or service that satisfies the definition of commercial item in section 2.101 of the Federal Acquisition Regulation.

"Commercial plan" means a subcontracting plan (including goals) that covers the Offeror's fiscal year and that applies to the entire production of commercial items sold by either the entire company or a portion thereof (e.g., division, plant, or product line).

"Individual contract plan" means a subcontracting plan that covers the entire contract period (including option periods), applies to a specific contract, and has goals that are based on the Offeror's planned subcontracting in support of the specific contract, except that indirect costs incurred for common or joint purposes may be allocated on a prorated basis to the contract.

"Master plan" means a subcontracting plan that contains all the required elements of an individual contract plan, except goals, and may be incorporated into individual contract plans, provided the master plan has been approved.

"Subcontract" means any agreement (other than one involving an employer-employee relationship) entered into by a Federal Government prime Contractor or subcontractor calling for supplies or services required for performance of the contract or subcontract.

- (c) The Offeror, upon request by the Contracting Officer, shall submit and negotiate a subcontracting plan, where applicable, that separately addresses subcontracting with small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business concerns, small disadvantaged business, and women-owned small business concerns. If the Offeror is submitting an individual contract plan, the plan must separately address subcontracting with small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns, with a separate part for the basic contract and separate parts for each option (if any). The plan shall be included in and made a part of the resultant contract. The subcontracting plan shall be negotiated within the time specified by the Contracting Officer. Failure to submit and negotiate the subcontracting plan shall make the Offeror ineligible for award of a contract.
- (d) The Offeror's subcontracting plan shall include the following:
 - (1) Goals, expressed in terms of percentages of total planned subcontracting dollars, for the use of small business, veteran-owned small business, service-disabled veteranowned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns as subcontractors. The Offeror shall include all subcontracts that contribute to contract performance, and may include a proportionate share of products and services that are normally allocated as indirect costs.

(2) A statement of—

(i) Total dollars planned to be subcontracted for an individual contract plan; or the Offeror's total projected sales, expressed in dollars, and the total value of projected subcontracts to support the sales for a commercial plan;

(iii) Total dollars planned to be subcontracted to small business concerns;

- (iii) Total dollars planned to be subcontracted to veteran-owned small business concerns;
- (iv) Total dollars planned to be subcontracted to service-disabled veteran-owned

INITIAL LESSOR

small business;

- Total dollars planned to be subcontracted to HUBZone small business concerns
- Total dollars planned to be subcontracted to small disadvantaged business concerns; and
- Total dollars planned to be subcontracted to women-owned small business concerns.
- A description of the principal types of supplies and services to be subcontracted, and an identification of the types planned for subcontracting to-

Small business concerns;

Veteran-owned small business concerns;

(iii) Service-disabled veteran-owned small business concerns;

HUBZone small business concerns; (iv)

- Small disadvantaged business concerns; and
- Women-owned small business concerns.
- (4) A description of the method used to develop the subcontracting goals in paragraph (d)(1) of this clause.
- (5) A description of the method used to identify potential sources for solicitation purposes (e.g., existing company source lists, the Procurement Marketing and Access Network (PRO-Net) of the Small Business Administration (SBA), veterans service organizations, the National Minority Purchasing Council Vendor Information Service, the Research and Information Division of the Minority Business Development Agency in the Department of Commerce, or small, HUBSone, small disadvantaged, and women-owned small business trade associations). A firm may rely on the information contained in PRO-Net as an accurate representation of a concern's size and ownership characteristics for the purposes of maintaining a small, veteran-owned small, service-disabled veteran-owned small, HUBZone small, small disadvantaged, and women-owned small business source list. Use of PRO-Net as its source list does not relieve a firm of its responsibilities (e.g., outreach, assistance, counseling, or publicizing subcontracting opportunities) in this clause.
- (6) A statement as to whether or not the Offeror included indirect costs in establishing subcontracting goals, and a description of the method used to determine the proportionate share of indirect costs to be incurred with-

Small business concerns:

Veteran-owned small business concerns;

(iii) Service-disabled veteran-owned small business concerns;

HUBZone small business concerns; (iv)

- Small disadvantaged business concerns; and
- Women-owned small business concerns.
- (7) The name of the individual employed by the Offeror who will administer the Offeror's subcontracting program, and a description of the duties of the individual.
- (8) A description of the efforts the Offeror will make to assure that small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns have an equitable opportunity to compete for subcontracts.
- (9) Assurances that the Offeror will include the clause of this contract entitled "Utilization of Small Business Concerns" in all subcontracts that offer further subcontracting opportunities, and that the Offeror will require all subcontractors (except small business concerns) that receive subcontracts in excess of \$500,000 (\$1,000,000 for construction of any public facility) to adopt a subcontracting plan that complies with the requirements of this clause.

(10) Assurances that the Offeror will-

Cooperate in any studies or surveys as may be required;

Submit periodic reports so that the Government can determine the extent of

compliance by the Offeror with the subcontracting plan; Submit Standard Form (SF) 294, Subcontracting Report for Individual Contracts, and/or SF 295, Summary Subcontract Report, in accordance with paragraph (j) of this clause. The reports shall provide information on subcontract awards to small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone

small business concerns, small disadvantaged business concerns, womenowned small business concerns, and Historically Black Colleges and Universities and Minority Institutions. Reporting shall be in accordance with the instructions on the forms or as provided in agency regulations. Ensure that its subcontractors agree to submit SF 294 and SF 295.

(iv)

A description of the types of records that will be maintained concerning procedures that have been adopted to comply with the requirements and goals in the plan, including establishing source lists; and a description of the Offeror's efforts to locate small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and womenowned small business concerns and award subcontracts to them. The records shall include at least the following (on a plant-wide or company-wide basis, unless otherwise indicated):

Source lists (e.g., PRO-Net), guides, and other data that identify small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns.

Organizations contacted in an attempt to locate sources that are small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, or women-owned small business concerns.

Records on each subcontract solicitation resulting in an award of more than \$100,000, indicating

Whether small business concerns were solicited and, if not, why not;

Whether veteran-owned small business concerns were solicited and, if not, why not:

(C) Whether service-disabled veteran-owned small business concerns were solicited and, if not, why not:

- (D) Whether HUBZone small business concerns were solicited and, if not, why not;
- Whether small disadvantaged business concerns were solicited and, if (E) not, why not:
- (F) Whether women-owned small business concerns were solicited and, if not, why not; and (G)
- If applicable, the reason award was not made to a small business concern.
- Records of any outreach efforts to contact-

Trade associations;

B) Business development organizations;

(C) Conferences and trade fairs to locate small, HUBZone small, small disadvantaged, and women-owned small business sources; and

(D) Veterans service organizations.

Records of internal guidance and encouragement provided to buyers through-(v) Workshops, seminars, training, etc.; and

ďΒΊ Monitoring performance to evaluate compliance with the program's requirements.

- On a contract-by-contract basis, records to support award data submitted by the Offeror to the Government, including the name, address, and business size of each subcontractor. Contractors having commercial plans need not comply with this requirement.
- In order to effectively implement this plan to the extent consistent with efficient contract (e) performance, the Contractor shall perform the following functions:
 - (1) Assist small business, veteran-owned small business, service-disabled veteranowned small business, HUBZone small business, small disadvantaged business, and women-owned small business concerns by arranging solicitations, time for the preparation of bids, quantities, specifications, and delivery schedules so as to facilitate the participation by such concerns. Where the Contractor's lists of potential small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and womenowned small business subcontractors are excessively long, reasonable effort shall be made to give all such small business concerns an opportunity to compete over a period of time.
 - (2) Provide adequate and timely consideration of the potentialities of small business, veteran-owned small business, service-disabled veteran-owned small business,

- HUBZone small business, small disadvantaged business, and women-owned small business concerns in all "make-or-buy" decisions.
- (3) Counsel and discuss subcontracting opportunities with representatives of small business, veteran-owned small business, service-disabled veteran-owned small business, HUBZone small business, small disadvantaged business, and womenowned small business firms.
- (4) Confirm that a subcontractor representing itself as a HUBZone small business concern is identified as a certified HUBZone small business concern by accessing the Central Contractor Registration (CCR) database or by contacting SBA.
- (5) Provide notice to subcontractors concerning penalties and remedies for misrepresentations of business status as small, veteran-owned small business, HUBZone small, small disadvantaged, or women-owned small business for the purpose of obtaining a subcontract that is to be included as part or all of a goal contained in the Contractor's subcontracting plan.
- (f) A master plan on a plant or division-wide basis that contains all the elements required by paragraph (d) of this clause, except goals, may be incorporated by reference as a part of the subcontracting plan required of the Offeror by this clause; provided—
 - (1) The master plan has been approved:
 - (2) The Offeror ensures that the master plan is updated as necessary and provides copies of the approved master plan, including evidence of its approval, to the Contracting Officer; and
 - (3) Goals and any deviations from the master plan deemed necessary by the Contracting Officer to satisfy the requirements of this contract are set forth in the individual subcontracting plan.
- (g) A commercial plan is the preferred type of subcontracting plan for contractors furnishing commercial items. The commercial plan shall relate to the Offeror's planned subcontracting generally, for both commercial and Government business, rather than solely to the Government contract. Commercial plans are also preferred for subcontractors that provide commercial items under a prime contract, whether or not the prime contractor is supplying a commercial item.
- (h) Prior compliance of the Offeror with other such subcontracting plans under previous contracts will be considered by the Contracting Officer in determining the responsibility of the Offeror for award of the contract.
- (i) The failure of the Contractor or subcontractor to comply in good faith with—
 - (1) The clause of this contract entitled "Utilization Of Small Business Concerns"; or
 - (2) An approved plan required by this clause, shall be a material breach of the contract.
- (j) The Contractor shall submit the following reports:
 - (1) Standard Form 294, Subcontracting Report for Individual Contracts. This report shall be submitted to the Contracting Officer semiannually and at contract completion. The report covers subcontract award data related to this contract. This report is not required for commercial plans.
 - (2) Standard Form 295, Summary Subcontract Report. This report encompasses all of the contracts with the awarding agency. It must be submitted semi-annually for contracts with the Department of Defense and annually for contracts with civilian agencies. If the reporting activity is covered by a commercial plan, the reporting activity must report annually all subcontract awards under that plan. All reports submitted at the close of each fiscal year (both individual and commercial plans) shall include a breakout, in the Contractor's format, of subcontract awards, in whole dollars, to small disadvantaged business concerns by North American Industry Classification System (NAICS) Industry Subsector. For a commercial plan, the Contractor may obtain from each of its subcontractors a predominant NAICS Industry Subsector and report all awards to that subcontractor under its predominant NAICS Industry Subsector.

NITIALS: LESSOR

48. 52.219-16 LIQUIDATED DAMAGES—SUBCONTRACTING PLAN (JAN 1999)

(Applicable to leases over \$500,000.)

- (a) Failure to make a good faith effort to comply with the subcontracting plan, as used in this clause, means a willful or intentional failure to perform in accordance with the requirements of the subcontracting plan approved under the clause in this contract entitled "Small Business Subcontracting Plan," or willful or intentional action to frustrate the plan.
- (b) Performance shall be measured by applying the percentage goals to the total actual subcontracting dollars or, if a commercial plan is involved, to the pro rata share of actual subcontracting dollars attributable to Government contracts covered by the commercial plan. If, at contract completion or, in the case of a commercial plan, at the close of the fiscal year for which the plan is applicable, the Contractor has failed to meet its subcontracting goals and the Contracting Officer decides in accordance with paragraph (c) of this clause that the Contractor failed to make a good faith effort to comply with its subcontracting plan, established in accordance with the clause in this contract entitled "Small Business Subcontracting Plan," the Contractor shall pay the Government liquidated damages in an amount stated. The amount of probable damages attributable to the Contractor's failure to comply shall be an amount equal to the actual dollar amount by which the Contractor failed to achieve each subcontract goal.
- Before the Contracting Officer makes a final decision that the Contractor has failed to make such good faith effort, the Contracting Officer shall give the Contractor written notice specifying the failure and permitting the Contractor to demonstrate what good faith efforts have been made and to discuss the matter. Failure to respond to the notice may be taken as an admission that no valid explanation exists. If, after consideration of all the pertinent data, the Contracting Officer finds that the Contractor failed to make a good faith effort to comply with the subcontracting plan, the Contracting Officer shall issue a final decision to that effect and require that the Contractor pay the Government liquidated damages as provided in paragraph (b) of this clause.
- (d) With respect to commercial plans, the Contracting Officer who approved the plan will perform the functions of the Contracting Officer under this clause on behalf of all agencies with contracts covered by the commercial plan.
- (e) The Contractor shall have the right of appeal, under the clause in this contract entitled, Disputes, from any final decision of the Contracting Officer.
- (f) Liquidated damages shall be in addition to any other remedies that the Government may have,


INITIALS: LESSOR & COVERNMENT

| REPRESENT | ATIONS AND | CERTIFIC | ATIONS |
|-----------------|--------------|--------------|---------------|
| (Acquisition of | Leasehold In | terests in R | leal Property |

Solicitation Number 3NY 0336

Complete appropriate boxes, sign the form, and attach to offer.

The Offeror makes the following Representations and Certifications. NOTE: The "Offeror," as used on this form, is the owner of the property offered, not an individual or agent representing the owner.



INITIALS: MITM & GOVERNMENT

2.

| b) (4) | | |
|--------|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

INITIOLS: LESSOR & GOVERNMEN

| (b) (4) | | | |
|---------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

LESSOR & GOVERNMEI

| (b) (4) | |
|---------|--|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

| | (a) | l axpaver lo (b) (4) | dentification N | umber (TIN) | | | |
|----|---------|-------------------------|-----------------|-------------|--|---|--|
| | | | | | | that does not siness in the fiscal paying | |
| | (b) (4) | | | | | | |
| 4; | | | | | | | |
| | | | | | | | |
| | | Name . | | - | | | |
| | | TIN . | | | | | |

9. 52.204-6 - Data Universal Numbering System (DUNS) Number (OCT 2003)

- The Offeror shall enter, in the block with its name and address on the cover page of its offer, the annotation "DUNS" or "DUNS+4" followed by the DUNS number or "DUNS+4" that identifies the Offeror's name and address exactly as stated in the offer. The DUNS number is a nine-digit number assigned by Dun and Bradstreet, Inc. The DUNS+4 is the DUNS (a) number plus a 4-character suffix that may be assigned at the discretion of the Offeror to establish additional CCR records for identifying alternative Electronic Funds Transfer (EFT) accounts (see Subpart 32.11) for the same parent concern.
- (b) If the Offeror does not have a DUNS number, it should contact Dun and Bradstreet directly to obtain one.
 - (1)An Offeror may obtain a DUNS number—
 - If located within the United States, by calling Dun and Bradstreet at 1-866-705-5711 or via the Internet at http://www.dnb.com; or
 - (ii) If located outside the United States, by contacting the local Dun and Bradstreet office.
 - (2)The Offeror should be prepared to provide the following information:
 - Company legal business name.
 - Tradestyle, doing business, or other name by which your entity is commonly recognized.
 - (iii) Company physical street address, city, state and zip code.
 - Company mailing address, city, state and zip code (if separate from physical).
 - (v)Company telephone number.
 - Date the company was started.
 - Number of employees at your location. Chief executive officer/key manager. (vii)
 - (viii)
 - Line of business (industry).
 - Company Headquarters name and address (reporting relationship within your entity).

10. DUNS NUMBER (JUN 2004)

Notwithstanding the above instructions, in addition to inserting the DUNS Number on the offer cover page, the Offeror shall also provide its DUNS Number as part of this submission:

DUNS#

074019530

11. CENTRAL CONTRACTOR REGISTRATION (JAN 2007)
(b) (4)

OFFEROR OR AUTHORIZED REPRESENTATIVE

NAME, ADDRESS (INCLUDING ZIP CODE)

(b) (6)

THE CLARAND PREJUGISHOS OF DECLARADO, L.P.

[O) COS PRESE. MARKENING, 5-500

ANUKASI, NY JUBAL

(b) (6)

Signature

TELEPHONE NUMBER

(716) 834-5000

[D) (6)

Date

Attachment A Lease No: GS-02B-23815


LESSOR GOVT

| (b) (7)(F) | | | |
|------------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Mitials bale 2 8 SOR GOVT .

Attachment B Lease No: GS-02B-23815

Initial/Dale TM & SW GOVT



3260.99-51tcPlan.pdf

AUTSTIE 10% 0052600528002878Att





Attachment C Lease No: GS-02B-23815

Initials Date LESSOR GOVT

| | SMALL BUSINESS SUBCONTRACTING PLAN |
|---------|------------------------------------|
| (b) (4) | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

Initials Date LESS OR GOVT

| D) (4) | | | |
|--------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

2 communes and

| (5) (4) | | |
|---------|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| b) (4) | | | |
|--------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| (b) (4) | | | |
|---------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

MAM

| D) (4) | | | |
|--------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Initials/Date & LESSOR GOVT

| (b) (4) | | |
|---------|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| This subcontracting plan was submitted by Signature: (b) (4), (b) (6) Typed Nar Title: Vi Phone Nur Facsimile I | ate December 10, 2010 | |
|---|-----------------------|---------------|
| Agency Small Business Review Signature: Typed Name: Title: | /Date | • • |
| U. S. Small Business Administration Signature: Typed Name: Title: | /Date | SEE FOLLOWING |
| Contracting Officer Approval: | /Date_ | PAGE |

Initials/Date 8 SOVI

By statute, SBA does not approve or disapprove a subcontracting plan; rather, SBA's comments are advisory, and the contracting officer approves or disapproves the plan.

| This subcontracting plan was submitted by: Signature Typed No Title: Phone No Facsimile | Onte December 10, 2010 |
|--|---|
| Agency Small Business Review Signature: Typed Name: Title: | /Date |
| U. S. Small Business Administration Signature: Typed Name Title: Romant Canta Recress Contracting Officer Approval. | nate 12/17/10 Pate 12/17/10 Date 12/17/10 |

By statute, SBA does not approve or disapprove a subcontracting plan; rather, SBA's comments are advisory, and the contracting officer approves or disapproves the plan.

